Purifiable classical processes need not be mixtures of process functions

Subtitle: every process function lifts to a unitary process, but quantum purifiability strictly enlarges the classical-process set beyond the process-function hull (three binary parties).

Draft note. Not submitted. Not refereed. Canonical source of the paper; `lift.pdf` is built from this file.

Abstract

A classical process (a point of the Baumeler-Wolf polytope) is purifiable in the sense of Araujo et al. (2017) if it arises from a pure process, one that stays unitary under all local unitaries with ancillas, by restricting to classical interventions. Mixtures of process functions are purifiable, and it was natural to ask whether nothing else is; we had conjectured so. **The main result of this note is that this is false.** Theorem H.12.1 gives a three-party binary classical process p, induced by an explicit Switchboard with eight 8x8 boards whose entries lie in Z[i]/8 and a source state with phases in Q(zeta_8), such that p is valid, the machine is pure, and p violates a facet inequality of the process-function (PF) hull: L(p) = 1/4 - (3/16) sqrt 2 < 0, while L ≥ 0 on all 744 process functions. The verification is exact. It has been re-derived independently from the paper text alone (code/stochastic/cyclic/switchboard/verify_h12), and the statement `purification_conjecture_false : ∃ p, Valid p ∧ Purifiable p ∧ p ∉ convexHull ℝ PFset` is checked by the Lean 4 proof assistant with Mathlib (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/PFUL/Counterexample.lean; standard axioms only, no `sorry`, no `native_decide`). The two gaps stated in earlier versions (finite-dimensional ancillas; self-contained definitions not linked to the process-matrix framework) are now closed in Lean. The theorem is restated with validity and purity defined through process matrices, CPTP Choi matrices and the link product (`purification_conjecture_false_choi`). The Switchboard is proved pure with ancillas in arbitrary Hilbert spaces, and valid under normal CPTP local channels on ancillas of any cardinality (H.19, H.20). Round 13 (H.20) closes in Lean the four formal gaps left by Round 12: for every process, purity against finite ancillas implies purity against ancillas in arbitrary Hilbert spaces; pure process matrices are exactly the valid Choi projectors of unitaries (AFNB's Theorem 2, for equal local input and output dimensions); the Kraus theorem and normal-CPTP validity hold without countability; and validity and purity defined with a link product over ancillas of any cardinality agree with the finite-ancilla definitions. The caveats that remain are listed in Section 9. The paper has not been peer reviewed.

The counterexample sits exactly where earlier structural results said it must. If some party is first at the operator level in a purification, the process is a PF blend (H.6); in the counterexample no party is first, and every party's input depends on another party's output. For two parties every valid classical process is a PF blend (Appendix G), so three parties are needed. Classically reversible purification gives exactly the PF hull (D.6), so the gap is a quantum effect. Exact non-purifiability certificates for E_{ex1} and two vertex orbits (C.2) show the purifiable set is still a proper subset of the valid processes.

The first part of the note proves the lifting theorem that the purification question starts from. A process function is a classical map w from the outputs of several parties to their inputs such that every choice of local deterministic interventions has exactly one fixed point. Baumeler, Costa, Ralph, Wolf and Zych showed that every process function extends to a bijection by adding a source and a sink, and left open whether every such bijection quantizes

to a valid unitary quantum process; Daher Ahmed and Kunjwal (2026) state this as a conjecture and prove it for a subclass. We give a short argument that it holds for every process function with finite alphabets: the permutation unitary $U|o,e\rangle = |w(o)+e, o\rangle$ composed with arbitrary local unitaries induces a unitary from source to sink. The key combinatorial fact, that two distinct output strings always disagree at some party whose input w assigns equally, is the pairwise-exclusivity property of Dourdent et al. (2026). The identity $M M^\dagger = 1$ and the validity chain are machine-checked in Lean 4 (PFUL.induced_unitary, PFUL.valid_kraus, PFUL.valid_instrument, PFUL.Choi.bornC_anc_eq_one, PFUL.Choi.afnb_iff_density, PFUL.Choi.isCP_iff_choi, PFUL.Choi.validity_package; standard axioms only), and Appendix F extends it to countable alphabets (PFUL.Countable.induced_unitary_l2). The Choi form in infinite dimensions is formalised as a convergent Born-pairing series (Section 9), and continuous alphabets are settled only partly (F.5: point-map local operations, or causal w). The philosophical sections read the lifting theorem as saying that fixed-point consistency is already a quantization condition, and Section 10 reads H.12 as saying that purity does not, in addition, single out mixtures of deterministic loops. Section 9 states exactly what is proved, certified, numerical, or open.

0. Introduction and contributions

Process functions are the deterministic classical processes without global causal order: every local choice has exactly one consistent history. Their mixtures form a polytope, conv(PF), inside the larger polytope of valid classical processes. Purity (unitarity under all local operations, Araujo et al. 2017) is the standard candidate for the physically admissible processes. Two questions follow: does every process function purify, and are mixtures of process functions the only classical processes that do? This note answers the first yes and the second no.

Contributions, in the order of the evidence for them:

1. **A purifiable classical process outside the PF hull (Theorem H.12.1) [proved; exact; independently re-derived; Lean-checked, in the process-matrix framework and with infinite-dimensional ancillas; the Round 12 formal gaps (a)–(d) are closed in Lean (H.20); remaining caveats in Section 9].** Three binary parties, an explicit X-type Switchboard and source state, a facet inequality of conv(PF) violated by 1/4 - (3/16) sqrt 2. Section 9 and H.12 list what each check covers.
2. **Every process function lifts to a unitary process (Section 1, Appendix A) [proved; Lean-checked in finite dimensions; countable alphabets in Appendix F].**
3. **Where purifiable non-blends can and cannot live [proved].** Mixtures of PFs are purifiable (C.1). Two parties: every valid classical process is a PF blend (Appendix G). Three parties: a party last, or a party first with valid conditionals, forces a PF blend (H.1, H.2), and so does a party that is first at the operator level in some purification (H.6). Switchboard structure: the purity conditions are an operator form of pairwise exclusivity, ancillas add nothing, and commuting or two-term boards give PF blends (H.8, H.10.6).
4. **Limits of the purifiable set [certified exact].** E_{ex1} and vertex orbits 7 and 50 are not purifiable (C.2), so the purifiable set lies strictly between conv(PF) and the valid polytope.
5. **The complete facet list of the three-party binary PF hull** (29,344 facets in 93 orbits, D.7), negative results for several certificate routes (D.8, Appendix E, C.5, C.6), and numerical surveys, all labelled as such. Of the 22 genuine never-crossed facet orbits, 15 are crossed by pure processes with exact certificates (H.22.2, H.28.1) and 7 remain open (Section 10 item 7). Round 22 (H.29) reduces the time-reversed PF lifts to phase boards at their extreme points and classifies all valid three-qubit phase processes (34 components). An exact search over them reproduces the known crossings but crosses none of the seven. Round 23 (H.30) proves the ten H.27 orbits on every non-Lugano phase component and on time-reversed lifts on single-block rules, and makes the classification exact; the open region is now the Lugano-type families.

Glossary. Appendix K defines the main technical terms in alphabetical order, with notation, the section where each is defined, the source in the reference list, and notes where the paper's usage differs from the literature.

Earlier versions of this note stated the "only if" direction as a conjecture and collected evidence for it. That material is kept as a record and marked superseded where H.12 overturns it; nothing in it is used in the proof of H.12.1.

Novelty and prior work (literature check of Oct 23 2026). Status of each main claim, as far as we could find:

- *Purifiable classical processes beyond conv(PF) (H.12.1, H.13.2) and convexity of Purif (H.13.1): new, as far as we can tell.* The inclusion conv(PF) ⊆ Purif was asserted earlier by Baumeler, Gilani and Rashid (Quantum 6, 673 (2022), ref. 27), without a separate proof for the coherent operator. We found no published statement of the converse ("purifiable classical = mixture of PFs"); it appears to be our own conjecture (C.3), and we found no earlier proof or counterexample. AFNB 2017 ask a different question (are all extensibly causal processes purifiable?). The nearest open question is Kunjwal and Oreshkov's (arXiv:2307.02565, ref. 36): can correlations from unitarily extendible process matrices be antinomic? We do not answer it. The H.13.2 correlation lies inside the (3,2,2) nomic polytope (H.13.5).
    - *Update after H.15.7e (literature recheck, Oct 23 2026; see H.15.8).*
        - The H.13.2 **board is not new**. Up to Hadamards and Pauli-X flips on the agent wires (and unitaries on source and sink), it is the time-reversed Lugano process $|w_r\rangle$. Guérin and Brukner (NJP 20, 103031 (2018), arXiv:1805.12429, Sec. IV and App. D; ref. 38) define it, prove that it is a valid pure process, and show numerically that it violates a causal inequality.
        - What we did not find stated anywhere is the *classical* fact: read in the Hadamard basis on the agent wires, this known pure process induces a classical process outside conv(PF). Read in the computational basis, it induces a PF mixture (H.15.8).
        - So the claim "purifiable classical processes beyond conv(PF)" stands, as far as we can tell. For H.13.2, however, it rests on a known board read in a non-standard basis, not on a new board.
        - The H.12 board is not of this form in the Hadamard frame (H.15.8). Whether it is equivalent to a time-reversed PF purification in some other local frame is OPEN. *Update (H.21.2): H.12 is the frame-rotated time reverse of the √X-Lugano process, the Lugano purification with Bob's flip replaced by √X. That process is a member of VOKB's Lugano family (CITED), but not a PF purification.*
- *Every process function lifts to a unitary process (Section 1, Appendix A; countable alphabets, Appendix F): partly known.* Baumeler, Gilani and Rashid asserted it without a coherent-level proof. It was proved for the Lugano process (AFNB 2017, Section 7), for an n-party family (Araújo, Guérin and Baumeler, PRA 96, 052315 (2017), Appendix B, ref. 37), and for MECC unitaries (Daher Ahmed and Kunjwal, arXiv:2610.00579, Theorem VII.1, ref. 24). Those last authors state the general case as Conjecture VII.1. Our general proof appears to settle it (Section 6). We found no earlier treatment of countable alphabets.
- *The X-type term threshold (H.14.1: boards with at most three terms always give PF blends; four terms can leave the hull): new.* It is stated in terms of this note's Switchboard definitions, and we found nothing comparable.
- *No single-use fine-grained model for H.13.2 (H.15.7b): an application of known results.* That single-use acyclic and QC-QC realisations give causal correlations is due to Wechs, Dourdent, Abbott and Branciard (PRX Quantum 2, 030335 (2021)) and related work. What is ours is the exact causal-inequality certificate for this particular purifiable non-blend. Lugano, a PF, already violates causal inequalities, so "purifiable but not QC-QC" is not new in itself. Moreover, the board of H.13.2 is locally equivalent to the time-reversed

Lugano process, and Guérin and Brukner (2018, ref. 38) already found a causal-inequality violation for that process (a numerical seesaw, $I_1 \approx -1/4$, with a uniform-superposition source). Our contribution there is only an exact certificate in a different frame, with a different inequality and source. Likewise, the valid routed graph for H.13.2 (H.15.7e) is a direct corollary of VOKB's Lugano graph plus time reversal. VOKB themselves define the adjoint (time-reversed) routed graph and build both validity principles symmetrically from it, so "the reverse of a valid graph is valid" is immediate from their definitions. We found no explicit statement of it, and no treatment of reversed Lugano, in 2206.10042v3 or in Vanrietvelde's thesis (H.15.9(A)).

Coverage caveat: we searched by web search and read the primary sources cited here. We did not run a systematic citation-graph or Google Scholar search, and preprints from the last few weeks may be missing.

1. Result and short proof

Setting. Parties k = 1..n. Party k has a finite input alphabet I_k, identified with the cyclic group $Z_{|I_k|}$, and a finite output alphabet O_k. A process function is $w = (w_k)$: prod $O_k \to$ prod I_k such that for every tuple of local functions $f_k : I_k \to O_k$ the map $o \to (f_k(w_k(o)))_k$ has exactly one fixed point. The source has output space $P = \text{prod } I_k$, the sink has input space $F = \text{prod } O_k$, and

$$U\ |o\rangle_O\ |e\rangle_P = |w(o) + e\rangle_I\ |o\rangle_F \qquad \text{(componentwise addition mod } |I_k|).$$

U is a permutation of basis states, hence unitary, for every map w (Baumeler et al. 2019, Theorem 2).

Lemma (exclusivity). If w is a process function and $s \neq s'$ in prod O_k, there is a party k with $s_k \neq s'_k$ and $w_k(s) = w_k(s')$.

Proof. Otherwise, for every k, $w_k(s) = w_k(s')$ implies $s_k = s'_k$. Define $f_k(x) = s_k$ if $x = w_k(s)$, $f_k(x) = s'_k$ if $x = w_k(s')$ (and arbitrary otherwise); the two clauses agree when $w_k(s) = w_k(s')$. Then s and s' are two distinct fixed points of the same intervention, a contradiction. (This is the forward direction of Dourdent et al. 2026, Theorem 7.)

Theorem. Let V_k be any unitary from $I_k \otimes X_k$ to $O_k \otimes Y_k$, with local ancilla spaces X_k, Y_k ($|I_k||X_k| = |O_k||Y_k|$). Composing U with the V_k (feeding each I_k into V_k and each O_k back into U) gives the operator M from $P \otimes X$ to $F \otimes Y$ with entries

$$M[(s,y),(e,x)] = \prod_k V_k[(s_k, y_k), (w_k(s) + e_k, x_k)].$$

M is unitary.

Proof. $(M\,M^\dagger)[(s,y),(s',y')]$ = sum over e, x of the product over k, which factorises as $\prod_k \sum_{e_k,\, x_k} V_k[(s_k,y_k), (w_k(s)+e_k, x_k)]\ \text{conj}\ V_k[(s'_k,y'_k),(w_k(s')+e_k, x_k)]$. If $w_k(s) = w_k(s')$, substituting $i = w_k(s) + e_k$ turns the k-th factor into the inner product of rows (s_k,y_k) and (s'_k,y'_k) of the unitary V_k, i.e. a Kronecker delta. If $s = s'$ every factor is of this kind, giving $\text{delta}_{y,y'}$. If $s \neq s'$, the Lemma gives a party with $w_k(s) = w_k(s')$ and $s_k \neq s'_k$, whose factor is 0. So $M\,M^\dagger = 1$, and M is square, hence unitary.

In the language of Araújo, Feix, Navascués and Brukner (2017, Definition 1), the process $|U\rangle\rangle\langle\langle U|$ is therefore *pure*. Section 2 spells out why this implies validity for arbitrary local CPTP maps and instruments, including ancillas shared or entangled with outside systems. Fixing the source to $|0\rangle$ and tracing the sink recovers the diagonal process matrix of w.

Converse (numerical only). If w is not a process function, the exclusivity property fails (Dourdent et al. 2026, Theorem 7); we have not proved that unitarity then fails in general, but numerically (code/check.py) every non-process function in the 2- and 3-party binary cases fails unitarity for random local unitaries. The "open/closed" contrast is the point: U is a bijection for every w; closing the loop is unitary exactly when w is consistent.

Checks. code/check.py enumerates all 12 binary 2-party and 744 binary 3-party process functions, verifies $||MM^\dagger - 1|| < 1e\text{-}13$ for Haar-random local unitaries (with and without qubit ancillas) and for ternary 2-party examples, and verifies that non-process functions fail. Lean status is in lean/STATUS.md.

2. From unitarity to validity

Section 1 shows that the lift is *pure* in the sense of Araújo et al. (unitaries in, unitary out). Appendix A derives full process validity from this (any local CPTP maps, local and shared/entangled ancillas, instruments) using Stinespring dilation. Appendix B covers input and output alphabets of different sizes. Appendix C treats stochastic classical processes: mixtures of process functions are purifiable, but a non-deterministic extremal point of the Baumeler–Wolf polytope provably is not (exact certificate).

3. Backward causation, before the formalism

The linguistic objection to backward causation is that a cause is, by definition, earlier than its effect. Dummett argued in 1954 and again in 1964 that this is a stipulation about the word, not a discovery about the world. Black's bilking argument is the better objection. If an earlier event is supposed to be the effect of a later one, an agent who sees the earlier event can intervene so as to prevent the later one. Either the agent cannot intervene, which wants an explanation, or the later event was not necessary for the earlier one. Lewis's reply splits the modal: one can, relative to the local facts and the laws, and one cannot, relative to the whole past. That dissolves a verbal paradox. It does not say which histories the laws admit.

General relativity makes the question physical. Gödel's 1949 solution has closed timelike curves. Morris, Thorne and Yurtsever showed that a traversable wormhole, if one could be held open, can be converted into a time machine by relative motion of the mouths. The Cauchy problem on the resulting spacetime is the grandfather paradox in differential equations. Friedman, Morris, Novikov, Thorne and collaborators proposed, in 1990, that only self-consistent solutions occur. Echeverria, Klinkhammer and Thorne then studied a hard-sphere billiard ball on a wormhole. For every "dangerous" initial trajectory they examined, one aimed so that the ball would knock its younger self off course, they found at least one self-consistent continuation, and many initial data admit several, some infinitely many. They did not prove that consistent solutions exist for all initial data, but they found no case without one. Carlini, Frolov, Mensky, Novikov and Solodukhin derived a version of self-consistency from stationarity of the action in a model, and found the same underdetermination. Novikov's principle removes inconsistent solutions. It does not choose among consistent ones. Earman's survey of the classical problem remains the right warning: a consistency condition that is imposed after the dynamics is not a dynamics.

4. Three quantum replies, and why none is the criterion

Deutsch's 1991 model asks for a fixed point of the partial trace around the curve. In finite dimension a fixed point exists, so no particular action is forbidden, and the grandfather paradox becomes a mixed state. The cost is nonlinearity. The model clones unknown states. Aaronson and Watrous showed that the computational power is PSPACE. Bennett, Leung, Smith and Smolin argued that the power is an artefact of demanding a fixed point for a distribution that an ordinary preparation would not produce. Tolksdorf and Verch showed that the Deutsch condition can be met to arbitrary precision in quantum field theory on a spacetime with no closed timelike curve at all. A Deutsch fixed point is not diagnostic of a loop.

Lloyd, Maccone and collaborators replace the fixed point by post-selection, the P-CTC model. Inconsistent branches are the ones that fail the post-selection. The grandfather paradox is resolved by the experiment not happening. Process functions sit inside this class: the event list appears conditional on the post-selection succeeding. That is a simulation. It is not an account of why the inconsistent branch was never a physical option. Post-selection is a filter on samples, of the same shape as a measure-zero axiom.

The process-matrix formalism of Oreshkov, Costa and Brukner is the third reply, and the one this note uses. A process is a map from local instruments to probabilities, required to give a probability for every choice of instruments, with no global causal order assumed. Classical deterministic processes in that class are process functions. Baumeler and Wolf described the polytope. Three parties suffice for a violation of a causal inequality. The Lugano function, found by Araújo and Feix and studied by Baumeler and Wolf,

```
w(a,b,c) = (not b and c, not c and a, not a and b),
```

is the standard witness. Each party's input depends on the other two outputs. The dependence graph is a cycle. Every deterministic intervention has exactly one fixed point. Two parties are not enough: the twelve binary two-party process functions are all causally ordered. Tobar and Costa extended the characterisation to any number of parties.

5. What the fixed-point clause is doing

The clause is an attempt at the criterion the filters do not give. A map from outputs to inputs is admitted only when every local function, freely chosen, composes with it to give exactly one fixed point. No fixed point is the grandfather case: the intervention has nowhere to land. More than one is the bootstrap: the loop underdetermines its own contents. The freedom is the content of the no-new-physics principle in Baumeler, Costa, Ralph, Wolf and Zych. Any operation possible in an ordinary region remains possible in a region that does not itself contain the closed curve. Consistency is not allowed to forbid the operation. It is allowed only to constrain the global solution.

Dourdent, Leitherer, Boghiu, Simonov, Kunjwal and Acín have since said the same thing without quantifying over interventions. A list of events is the event list of a process function exactly when it is complete and pairwise exclusive. If any two of several questions can be answered jointly, so can all of them. That is a multipartite form of Specker's principle. It is a constraint on the process, not an extra axiom that paradoxical histories have measure zero. Cyclic causation is not the enemy. Cyclic signalling is.

6. Reversibility, and the quantization question

Reversibility is not free on the original alphabet. The Lugano function is two-to-one. Of the 256 binary two-party maps, twelve are process functions and none equals its input-output reverse. Baumeler, Costa, Ralph, Wolf and

Zych, Theorem 2, restore reversibility by a source, a region with trivial input, and a sink, a region with trivial output. The extended process can be read backwards. The form used here is the permutation unitary

```
U |o, e⟩ = |w(o) + e, o⟩.
```

The inverse reads the sink as the output string and the source as the difference between the input and w(o). A bijection of a finite set is a unitary. A unitary on a fixed basis is not yet a quantum process. Parties must be able to insert instruments that are not diagonal in that basis. A Hadamard is the test case. If the induced map from source to sink ceases to be trace-preserving, the classical consistency clause has not lifted, and quantum theory needs an extra filter. If it remains trace-preserving for every instrument, the fixed-point clause was already the quantum consistency clause.

Daher Ahmed and Kunjwal (arXiv:2610.00579, 30 September 2026, ref. 24) state as Conjecture VII.1: "Any process function can be purified to a unitary process." They support it numerically and prove it for unitaries with mutually exclusive control conditions (MECC; their Theorem VII.1), and under a second sufficient condition, unambiguity. They note that the bare permutation unitary of the reversible extension may fail to be a valid process. The argument below is that it does not fail. As far as we can tell, it settles Conjecture VII.1 for all process functions with finite alphabets, and Appendix F extends it to countable alphabets (Hilbert spaces ℓ^2). Earlier special cases are the Lugano process (AFNB 2017, Section 7, below) and an n-party family of AF/BW-type processes, for which Araújo, Guérin and Baumeler (PRA 96, 052315 (2017), Appendix B, ref. 37) prove validity of the coherent purification. Araújo, Feix, Navascués and Brukner had already written down, in 2017, a purification of the Lugano process by exactly this construction (the standard $|x,y\rangle \to |x, y + f(x)\rangle$ trick, credited there to Baumeler and Wolf); a routed-circuit reconstruction is due to Vanrietvelde, Ormrod, Kristjánsson and Barrett. Baumeler, Gilani and Rashid (2022) proved that the diagonal (dephased) process matrix of every process function is valid, and remarked, without a separate proof for the coherent operator, that the reversible extensions are therefore unitarily extensible. The contribution claimed here is a short general proof for the coherent permutation unitary, for every process function.

7. Time symmetry and retrocausality

Price has argued that a time-symmetric ontology for quantum theory should be retrocausal, on the assumption that the quantum state is real. Leifer and Pusey replaced that assumption with lambda-mediation: correlations between a preparation and a later measurement are mediated by the ontic state of the system. No retrocausality, operational time symmetry, and lambda-mediation then imply a timelike Bell factorization, which sequential measurements violate. Maudlin's reply is that the operational time-reverse of an experiment is not always itself an experiment of the same kind. The no-go is conditional.

The dilation in this note is adjacent to that argument, not a solution of it. A process function that violates a causal inequality already has each party's input depending on another party's output. The later setting is an argument of the earlier input. Lambda-mediation, in the strict past-screening sense, fails because of the cycle, not because a retrocausal hidden variable was added by hand. Read forwards, the source is an input and the sink is an output. Read backwards, they exchange roles, and the inverse of the permutation unitary is the reversed process. The objection that the bare Lugano function is not an involution on its own three bits is an objection to refusing the source and the sink. Whether the dependence is the retrocausality Price asked for, or only an operational time-reverse, is a reading of the same operator. The mathematics does not choose the reading. It does remove one cheap reply: one cannot say that the cyclic classical model dies when instruments become unitary.

8. What this does not settle

Embeddability is untouched. A unitary process on a finite alphabet is not a solution of Einstein's equation, and it is not a local Hamiltonian flow on a wormhole. The billiard has the wrong multiplicity. Post-selection realises the event list conditional on the post-selection succeeding. The theorem says the list has a unitary dilation. It does not say the dilation is a spacetime.

Purifiability in the sense of open quantum problem 43, whether every extensibly causal process is purifiable, is related but not identical. The theorem puts every process function, including those that violate causal inequalities, inside the unitarily extendible fragment. It does not classify processes that are not deterministic classical functions.

Freedom is not settled. Nothing here decides whether an agent whose output is an argument of an earlier input has a choice. The fixed-point clause says the choice, if made, completes uniquely. It does not say the choice was open. Whether this is an adequate reply to Black depends on whether consistency conditions may rule out interventions, or only rule out histories given the interventions. The note takes the second reading: consistency rules out histories given the interventions, never the interventions themselves (Section 5), and the formalism is built for it.

The combinatorial lemma is finite for any fixed alphabet and is the piece an attacker has to break. The linear algebra after it is row orthogonality. See lean/STATUS.md for exactly what is and is not machine-checked.

9. Status: what is proved about purifiable classical processes

Former conjecture. A classical process is purifiable if and only if it is a mixture of process functions (a "PF blend").

Theorem 9.1 (= H.12.1) [proved]. The "if" half holds (C.1). The "only if" half is false: there is a valid three-party binary classical process that is purifiable and lies outside conv(PF).

What supports Theorem 9.1, in decreasing order of independence:

- *Exact paper proof* (H.12, code/stochastic/cyclic/switchboard/c1/exact_cex.py). Exact arithmetic in Q(zeta_8): unitarity of the boards, the Pauli rule of H.8.1, validity under all 64 deterministic interventions, and the facet value 1/4 - (3/16) sqrt 2 < 0. Purity then follows from the paper proofs of H.7.1, H.8.1 and H.8.2.
- *Independent re-derivation* (verify_h12/verify.py, verify.log), written from the paper text only. It checks purity directly through an exact multi-affine criterion over 125 slot combinations, with no use of H.7.1 or H.8. It re-enumerates the 744 PFs by brute force over 8^8 maps and uses its own rational separating inequality, value 1 - (3/4) sqrt 2 < 0, together with an infeasible membership LP. It also runs 1,200 random float trials (residual ≤ 2.4e-15) with a perturbed control.
- *Lean 4 proof* (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/PFUL/Counterexample.lean, CounterexampleData.lean; lean/STATUS.md Round 6). The statement `purification_conjecture_false : ∃ p, Valid p ∧ Purifiable p ∧ p ∉ convexHull ℝ PFset` is proved. The only axioms are propext, Classical.choice and Quot.sound. There is no `sorry` and no `native_decide`; the finite computations use `decide +kernel`. Purity is proved for all finite ancillas and local unitaries (`isPure_Vsb`), validity for all stochastic local interventions (`valid_pcl`), and non-membership through the facet functional (`pcl_not_mem_convexHull`). **Framework link and infinite ancillas (Rounds 9–13; H.12.3, H.19,**

H.20). The theorem is restated with process-matrix definitions only (`purification_conjecture_false_choi`). `Valid p` is equivalent to AFNB validity of the diagonal process matrix W_p under all CPTP local operations with finite ancillas (`isValidPM_Wcl_iff`). `IsPure V` is equivalent to unitarity of the link product of $|V\rangle\rangle\langle\langle V|$ with local unitaries (`isPure_iff_unitaryLink`). $|Vsb\rangle\rangle\langle\langle Vsb|$ is a valid and pure process matrix (`isPurePM_choiMat_Vsb`). The deterministic valid process matrices are exactly the process functions (`isValidPM_Wcl_pfPoint_iff`). The Switchboard is pure with ancillas in arbitrary Hilbert spaces (`isPureHilbert_Vsb`) and valid under normal CPTP local channels on countable ancillas (`valid_normalCPTP_Vsb`). **Former formal gaps (a)–(d), closed in Lean in Round 13 (H.20; lean/STATUS.md Round 13; standard axioms only).**

- (a) *Infinite-ancilla link product* [PROVED (Lean)]. `IsValidPMInf` and `IsPurePMInf` let the local Choi kernels and unitary kernels live on ancilla types of any cardinality. `isValidPMInf_iff : IsValidPMInf W ↔ IsValidPM W` holds for every finite W, and `isPurePMInf_iff σ : IsPurePMInf W ↔ IsPurePM W` whenever each party's input and output types are in bijection (σ). The counterexample is restated with these predicates (`purification_conjecture_false_choiInf`). *Caveat:* the link product is entrywise, on kernels whose finite sections are PSD and whose partial traces converge unconditionally; it is not an operator identity for non-trace-class Choi operators (H.20.4).
- (b) *Finite purity implies Hilbert purity, every V* [PROVED (Lean)]: `isPureHilbert_of_isPure`, and `isPure_iff_isPureHilbert`, `isPure_iff_isUnitaryKer` (H.19.4, H.20.1).
- (c) *AFNB Theorem 2* [PROVED (Lean), with hypotheses]: `isPurePM_iff σ hPF W : IsPurePM W ↔ IsValidPM W ∧ ∃ U, IsUnitaryM U ∧ W = choiPM U`, for $I_k \simeq O_k$ and $|P| = |F|$ (H.20.2).
- (d) *Normal CPTP validity without countability* [PROVED (Lean)]: `isNormalCPTP_iff_kraus_any`, `valid_normalCPTP_Vsb_any` (H.20.3).

Remaining caveats [OPEN as stated]. (1) An operator-level link product for Choi operators that are not trace class; the kernel form of (a) is what is proved. (2) AFNB Thm 2 for unequal local input/output dimensions, and its converse for $|P| \neq |F|$. (3) The joint space $C^P \otimes K_1 \otimes K_2 \otimes K_3$ is modelled as any Hilbert space with a basis indexed by $P \times \prod \kappa_k$, because Mathlib has no completed Hilbert tensor product; the local spaces $C^2 \otimes K_k$ are now Mathlib's tensor product (`isPure_qubitTensor`, H.20.5). (4) Automatic boundedness of positive trace-preserving maps on the trace class (the normality hypothesis of `IsNormalCPTP`) is still assumed (H.20.6). (Round 15, H.22.4: Mathlib's spectral theorem for compact self-adjoint operators is available, so this is unformalised rather than obstructed.) (Round 16, H.23.2: **closed** in Lean, `PFUL.TraceClass.IsCPTP.isNormalCPTP`; caveat (4) no longer applies.) None of these affects Theorem 9.1.

None of this has been peer reviewed.

Where the gap lives. It needs three parties (Appendix G), a purification with no operator-first party (H.6), and boards that are neither commuting nor two-term (H.8.4, H.10.6). The H.12 machine has all three features.

This section is a map of the current status. Labels follow the appendices: **[proved]**, **[certified exact]** (rational certificate, not Lean), **[numerical]**, **[cited]**. Proofs live in the appendices and are not restated here.

Proved.

- *Process functions lift* (Section 1, Appendix A). Every process function lifts to a unitary process. The core identity and the validity chain are machine-checked in Lean in finite dimensions (PFUL.induced_unitary; PFUL.Choi.validity_package). Countable alphabets: Appendix F (PFUL.Countable.induced_unitary_l2). Continuous alphabets (F.5): measure preservation for every measurable process function and unitarity for point-map local unitaries (all local unitaries if w is causal, or if w is finitely controlled, F.5.9, or countably controlled, F.5.10) are proved in the paper, with the combinatorial core in Lean (PFUL.Continuous); for uniform limits of countably controlled w the closed loop is a canonical isometry (F.5.11), and it is unitary for activation-controlled w with arbitrary measurable amounts (F.5.12). Unitarity in general is open.
- *Blends lift* (C.1). Every mixture of process functions is purifiable, and convex combinations of purifiable processes are purifiable. This is the "if" half of the former conjecture.
- *Classical version* (D.6). A classical process is classically reversibly purifiable iff it is a PF blend. Together with H.12 this shows that quantum purifiability does add something: the quantum purifiable set strictly contains the classical one.
- *Two parties* (Appendix G, Theorem G.1). Every bipartite valid classical process, with any finite alphabets, is a blend of causally ordered process functions. So for two parties purifiable = PF blend = valid; the gap of H.12 needs three parties. This is known in substance [cited: Oreshkov-Costa-Brukner 2012, Suppl.; Baumann-Brukner 2016].
- *Three parties, a party last* (Theorem H.1). If some party's output influences nothing, the process is a PF blend.
- *Three parties, causally separable* (Theorem H.2). If some party is first and every conditional bipartite process is valid, the process is a PF blend. So every classically causally separable three-party process is a blend of causally ordered process functions, so no gap can occur on that class.
- *Three parties, a party first in the purification* (Lemma H.6.1, Theorem H.6.2). If some purification of W has a party whose input is prepared from the source alone (operator-level first: V factorises through that party's input), then every conditional bipartite process is valid and purifiable, and W is a PF blend. So a purifiable process outside the hull can only have purifications in which every party's input is influenced by some party output. Lugano has no purification with an operator-first party.
- *Switchboard structure* (H.8). The H.7.1 purity conditions are equivalent to a Pauli-span condition, $K_{o,o'}$ in the span of the operators trivial on some party whose output changed, which is the operator form of exclusivity. Checked in exact arithmetic. Ancillas add no conditions, so H.7.1 is full purity. Operator-first and operator-last parties are read off K. Monomial or commuting switchboards give PF blends for every source state (H.8.1-H.8.5).
- *Attacks on (C1)* (H.10). Two natural routes are closed. No twirl that preserves p can reduce to the commuting case, and the degree-2 (Shor) relaxation in the board entries is vacuous. Exhaustive check: pairwise exclusivity is equivalent to being a PF for three binary parties (744). Two-term boards $X^{w1(o)}$ $\exp(i\,t\,X^{d(o)})$ are classified exactly (39,512 non-trivial pairs, 34,304 with non-commuting projectors).
- *Toward (C2)* (H.11). Input copying preserves purity. Generalized switchboards (extra sink F') obey the block-wise Pauli rule. (C2) reduces to whether the sink can be made to record o on every source state (open).
- *Robustness, trivial halves* (I.1-I.3). Being eps-close to a blend implies being eps-close to purifiable. A quantitative converse would have been equivalent to the conjecture, and is therefore false (H.12). In family C the machine residual bounds the operator purity defect.
- *Structure of purifications* (D.1, D.2, D.5). The sink records (o, i) orthogonally. Constraints on the fixed source state are vacuous. Validity under quantum-controlled interventions holds for every classical process.

Certified exact non-purifiable. E_{ex1}, and vertex orbits 7 and 50 (one of which contains E_{ex1}): exact inertia certificates (C.2; code/stochastic/cert). So the purifiable set, while larger than conv(PF), is still a proper subset of the valid classical processes.

Settled negatively (routes that provably do not work).

- *Hidden source label* (D.3/D.4). The single-classical-label strengthening D.3 is false: a causal circuit is an exact counterexample.
- *Fixed-source certificates* (D.8). No certificate that uses only the fixed source sector can rule out purification of any classical process.
- *Marginally-first reduction* (H.5). Purifiability plus "party A's input marginal is output-independent" does not force valid conditionals. The operator-level version does (H.6). An exact counterexample is a 4-term PF blend. So H.2 cannot be extended this way to E_{ex1} and orbits 7, 8, 50, even though all of them are marginally first in some party (H.1 numerics).
- *Form-based certificates for orbits 8/10/20* (C.5). Every linear or block-Hermitian combination of the constraint forms tried stalls at lambda_16 ~ +1e-4. Adding the Gram normalisation provably adds nothing. The obstruction is non-convex. The earlier estimate that "about half" of the open orbits are certifiable by the current pipeline is **withdrawn**.
- *Moment relaxation* (Appendix E). The degree-2 relaxation is feasible for E_{ex1}, so it is weaker than single-form inertia.
- *Degree-4 single-vector certificates for orbit 8* (C.6) [numerical]. Random 67-dim (even 60-dim) subspaces of V_W, with the radical removed, contain jointly isotropic vectors (loss 1e-9 to 2e-7, against a baseline of 0.1). So the C.5 degree-4 proposal fails for random L, and full-frame level-2 Lasserre is about 3.4e6 in size. No paid compute was used.
- *Single-vector determinantal bound for orbit 8* (H.2 route B) [numerical]. The jointly isotropic cone contains vectors with rank K(u) of about 51-55, so the bound gives only dim ≤ ~28-32, not < 16.

Numerical observations (not proof; recorded before H.12 and partly read at the time as support for the conjecture, which H.12 shows they were not).

- *GPU sweep* (C.4). None of the 49 remaining sampled non-deterministic vertex orbits lifted. Best residuals were 12.97-59.35; the same code reaches 1e-16 on Lugano.
- *Isotropic dimension* (C.5). For orbits 8, 10 and 20, constraint-isotropic subspaces appear to exist up to dimension ~10 and fail by 12. A purification needs 16.
- *Facets* (D.7). Facet orbit 82 is violated by E_{ex1} and by all 51 sampled non-deterministic vertex orbits.
- *Boundary* (D.8). Along Lugano → E_{ex1}, purifiability appears to stop where the PF hull does.
- *Two-term boards* (H.10.4). All 237 symmetry classes, 7 values of t and all 29,344 facets give operator facet values ≥ -1.7e-14. So they lie in conv(PF) for every source state, including the non-commuting ones. No counterexample. Float64, not exact.
- *Switchboard robustness* (H.8, I.4). Minimising the exact purity residual R at prescribed facet-82 violation v always gave $R \geq 0.31\, v^2$, i.e. violation ≤ 1.79 sqrt(R): 108 runs, v from 0.01 to 0.9. No counterexample in family C was found by this local search; H.12 lies in family C, so the floor is withdrawn (Appendix I).
- *Unitary-side hunt* (H.3). Optimising unitaries for purity, classicality and facet violation found no purifiable process outside the hull (the H.12 example needed the restriction to X-type boards). From Lugano, facet violation of ~0.01 costs a purity residual of 0.1-2.4.

Refuted / superseded (Oct 22 2026). The only-if half of the conjecture and the Switchboard conjecture (C1) are false (H.12.1). The Appendix I floor $R \geq 0.31\ v^2$ was a local-optimisation artefact and is withdrawn. Evidence items above that were read as support for the conjecture (C.4, D.7, D.8, H.3, H.7, the Switchboard robustness item) remain true as statements about what was found, not as evidence for it.

Proved (Oct 22, later). *Coset-transport theorem* (H.10.6): X-type boards whose class-constant selections are all PFs give PF blends for every source state, with an explicit decomposition. Exhaustive exact check: **all two-term boards are PF blends**. *Recording* (H.11.4): a coherent-control purification shows that o need not be recorded on every source state.

10. Conclusion, interpretation, and open problems

What purity singles out. For process functions purity is automatic (Section 1): fixed-point consistency already guarantees a unitary dilation. For classical processes in general it is a genuine restriction, since E_{ex1} and orbits 7 and 50 are valid but not purifiable (C.2). But it is not the restriction "mixture of deterministic consistent loops". The purifiable classical processes form a convex set strictly between conv(PF) and the valid polytope (C.3, H.12). Classically, reversible purification gives exactly conv(PF) (D.6). So the extra processes are a quantum effect. A coherent superposition of board operations, none of which is a classical bijection, yields classical statistics that no mixture of process functions reproduces.

No operator-first party is needed, and none is allowed. H.6 shows that if any party is first at the operator level in some purification, the process is a PF blend. Every purifiable non-blend must therefore be "cyclic all the way down": in every purification, each party's input depends on some party's output. The H.12 machine is of this kind (operator-first residuals 0.31 / 0.25 / 0.31, complete causal graph). The gap is not produced by an exotic ingredient such as a party acting before the loop. It comes from the loop itself.

The two-party contrast. With two parties every valid classical process is a blend of causally ordered process functions (Appendix G), so valid = purifiable = conv(PF). The separation first appears at three parties, the smallest setting in which process functions without causal order (Lugano) exist.

Interpretation (philosophical, not a result). Read a process function as a deterministic consistent time loop. Before H.12, the hoped-for reading was that every reversible quantum loop with classical statistics is an ignorance mixture of such loops: chance in a loop would only be ignorance of which loop obtains. H.12 shows this reading fails. Quantum reversibility admits classical loops whose chance is not ignorance over deterministic loops, though it still excludes some classically consistent ones (E_{ex1}). The earlier version of this paragraph assumed the conjecture. It is superseded, as is its claim that reversibility excludes basic chance from loops; D.4's caveat about contextual "which-loop" variables no longer bears on the main question.

Open problems.

1. *Characterise the purifiable set.* Is it a polytope, or even closed? What are its extreme points? Are vertex orbits 8, 10, 20 and the other 46 sampled orbits that are numerically non-purifiable (C.4, C.5) truly non-purifiable? Exact certificates exist only for orbits 7 and 50.
2. *Minimal counterexamples.* Find the smallest facet violation and the fewest non-PF board terms. Which facet orbits can be violated? The H.12 example uses facet 1741 of the normaliz list. What is the reach of X-type boards? The H.12 boards reach L1 distance 0.828 = 2(sqrt 2 - 1) from conv(PF) at their best source state [numerical]. Are three-term boards enough? *Update (H.17.17, H.26.1):* no. In the per-class-pair model

every admissible ≤3-term board is a PF blend, so four terms per outcome is the minimum (H.13.2 shows four suffice). Of the 23 never-crossed facet orbits, orbit 92 is positivity (H.17.5), twelve are crossed by time-reversed PF lifts (H.22.2), and ten remain open (item 7). *Update (Round 21, H.28):* three more (26, 30, 31) are crossed by PF phase boards, so 15 are crossed and seven remain open. *Update (Round 22, H.29):* the counts are unchanged. Lemma H.29.2a shows that on the time-reversed PF lifts the minimum sits at extreme points (phase boards, or rank 2 for four-block parties). An exact search over all 34 components of valid three-qubit phase processes, 8 of them new, crosses none of the seven. *Update (Round 23, H.30):* the counts are unchanged, but the seven are now PROVED to hold on every non-Lugano phase component and on time-reversed lifts on single-block rules (Theorem H.30.2).

3. *Other scenarios.* Larger alphabets, more parties, unequal alphabets (Appendix B), the countable case (Appendix F), and which causal-inequality violations the new processes reach.
4. *Close the remaining formal caveats* (Section 9, (1)–(4)). Gaps (a)–(d) were closed in Round 13 (H.20). What is left is an operator-level link product for Choi operators that are not trace class, AFNB Thm 2 for unequal local dimensions, a completed Hilbert tensor product for the joint space, and automatic boundedness of positive trace-preserving maps (closed in Round 16, H.23.2).
5. *Structure of purifications.* The reduction (C2) of a general three-party purification to Switchboard form (H.11) is open, and so is any facet description of the purifiable set derived from purity.
6. *Spacetime realisations.* Both counterexamples now have explicit circuits on time-delocalised subsystems and valid routed graphs (H.18, H.21): they are the frame-rotated time reverses of the Lugano process and of its √X variant. Open: how far H.12 can violate the causal inequality y_A (now known to lie in [−1.15861, −0.70580], H.21.8, H.22.1, H.23.3 and H.26.2), and realisations with more than three parties. *Update (H.26.3):* within the deterministic-output projective family the optimum lies in [−0.7060707, −0.7058022] (PROVED by exact SOS certificates for all 64 output patterns). Over all instruments only [−1.15861, −0.70580] is known.
7. *Open items at a glance (status Oct 26 2026, after Round 23).* Each item is OPEN unless marked.
    - *The seven open facet orbits* 28, 54, 57, 66, 69, 75 and 81 (960 facets). Whether any purifiable process crosses them is OPEN. Round 21 crossed three of the former ten (26, 30, 31) with PF phase boards, which are a subfamily of time-reversed PF lifts, and certified each crossing exactly with two independent checkers (Theorem H.28.1, PROVED). Partial results on the seven: forward PF lifts satisfy them in any dimension (Theorem H.27.1, PROVED with exact LP certificates). Phase boards on all refined PFs, general time-reversed lifts on all 20 refined PFs, basin hopping and a limited instrument/mixed-wiring search find no crossing (H.28.2, NUMERICAL). *Round 22 (H.29):* there is an exact validity criterion for pure processes with a classical future record (PROVED). On the H.27.2 family the facet minimum is attained at extreme points, which are PF phase boards for parties with at most three blocks (Lemma H.29.2a, PROVED with a CITED rank bound). The rank-2 extreme points on the six four-block rules and all 34 components of valid three-qubit phase processes were searched exactly (both searches reproduce orbits 26 and 30). Neither crosses the seven (NUMERICAL). Penalty-based COPP and phase searches failed validation. *Round 23 (H.30):* all ten H.27 orbits, the seven included, hold on every valid three-qubit phase process outside the 8 Lugano-type components and on all time-reversed PF lifts on the 12 single-block rules (Theorem H.30.2, PROVED by exact LP certificates from two independent checkers, via the statistics span of Lemma H.30.1). The phase-process classification is now exact (H.30.3, PROVED). What remains OPEN is the Lugano-type families (phase components and time-reversed lifts on the 8 Lugano-type rules) and all pure processes outside the families studied. Still not done: a purity-based SDP/SOS bound on the Lugano families, and a validity-preserving search near the −1/6 points (the penalty version failed validation, H.30.4).

- *Global optimum of y_A for H.12.* OPEN. Within the deterministic-output projective family of H.26.3 the value lies in [−0.7060707, −0.7058022] (PROVED). Over all instruments, [−1.15861, −0.70580] (H.26.2, H.25.2).
- *Conjecture F.5.7 beyond activation-controlled w.* OPEN. Unitarity of the canonical isometric closed loop for general uniform limits, such as Lipschitz w (F.5.11), is also OPEN. Proved cases: causal, finitely controlled, countably controlled and activation-controlled w (F.5.9, F.5.10, F.5.12).
- *Items 1, 3, 4 and 5 above* are unchanged.
- *Caveat.* The exhaustive searches (H.17.13–H.17.16c, H.26.1) and the certificate generators are ordinary Python. They are not formally verified, and none of this has been peer reviewed. The class bound and Lemma H are in Lean (H.17.17).

Appendix A. Unitarity under local unitaries implies validity

Definitions (AFNB 2017, Sec. 2). A process with source P, sink F and parties k is an operator $W \geq 0$ on $P \otimes F \otimes \prod_k (I_k \otimes O_k)$. For local maps $A_k : L(I_k \otimes X_k) \to L(O_k \otimes Y_k)$, the induced map is the link product $G_A = W * (A_1 \otimes ... \otimes A_n)$, a map $L(P \otimes X) \to L(F \otimes Y)$ with $X = \otimes_k X_k$ and $Y = \otimes_k Y_k$. W is *valid* if G_A is CPTP whenever every A_k is CPTP, for all finite-dimensional local ancillas X_k, Y_k. W is *pure* (their Definition 1) if G_A is unitary whenever every A_k is unitary. Their Theorem 2 says W is pure iff $W = |U\rangle\rangle\langle\langle U|$ for a unitary U. For pure Choi vectors the link product composes operators: if $A_k(\text{rho}) = V_k \text{ rho } V_k\dagger$, then $G_A(\text{rho}) = M \text{ rho } M\dagger$, where M is the operator of Section 1.

Claim. $W = |U\rangle\rangle\langle\langle U|$ with U the permutation lift of a process function w is a valid process.

Step 1 (local unitaries). By the Theorem of Section 1, G_A is conjugation by a unitary M whenever every A_k is conjugation by a unitary V_k. This holds for any ancilla dimensions with $|I_k||X_k| = |O_k||Y_k|$. (Machine-checked, both sides, including the dimension count: `PFUL.induced_mul_conjTranspose`, `PFUL.induced_conjTranspose_mul`, `PFUL.induced_unitary`; see lean/STATUS.md.)

Step 2 (local CPTP maps, via Stinespring). Let $A_k : L(I_k\ X_k) \to L(O_k\ Y_k)$ be CPTP. Stinespring dilation gives an isometry $S_k : I_k\ X_k \to O_k\ Y_k\ E_k$ with $A_k(\text{rho}) = \text{Tr}_{E_k}[S_k \text{ rho } S_k\dagger]$. Pad the input with E'_k of dimension $|O_k||Y_k||E_k|$ and the output with E''_k of dimension $|I_k||X_k|$. The two sides then have equal dimension, and the isometry $\text{psi} \otimes |0\rangle \to (S_k \text{ psi}) \otimes |0\rangle$, defined on the $|0\rangle$-slice, extends to a unitary $V_k : I_k\ X_k\ E'_k \to O_k\ Y_k\ E_k\ E''_k$ by completing orthonormal bases. So $A_k(\text{rho}) = \text{Tr}_{E_k\ E''_k}[V_k\ (\text{rho} \otimes |0\rangle\langle 0|_{E'_k})\ V_k\dagger]$. The ancillas E', E, E'' never enter U, and the link product is multilinear and commutes with appending fixed states and with partial traces on systems it does not contract. Hence

$$G_A(\text{rho}) = \text{Tr}_{E\ E'',[}\ M\ (\text{rho} \otimes |0\rangle\langle 0|_{E'})\ M\dagger\ ],$$

where M is the operator of Step 1 for the unitaries V_k, with enlarged local ancillas $X_k\ E'_k$ and $Y_k\ E_k\ E''_k$. Appending a state, a unitary conjugation and a partial trace are each CPTP, so G_A is CPTP.

Step 3 (shared and entangled ancillas). An ancilla R that is shared between parties, or entangled with any outside system, is covered by complete positivity. The joint state lives on P X R; $G_A \otimes \text{id}_R$ is CPTP because G_A is; outputs are normalised states, and every probability that a later measurement on F Y R assigns is non-negative and

sums to 1. Pre-shared entanglement between laboratories is the special case in which part of X_j and part of X_k start in an entangled state supplied through the source. It is also covered, because Step 2 already allows arbitrary input states on $P \otimes X$.

Step 4 (instruments). Let $\{A_k^{a_k}\}$ be CP maps summing to a CPTP map A_k. The link product of positive operators (Choi operators) is positive, so each $G_a = W * \otimes_k A_k^{a_k}$ is CP. Multilinearity gives $\sum_a G_a = G_A$, which is CPTP by Step 2. Then $p(a) = \mathrm{Tr}\, G_a(\mathrm{rho}) \geq 0$ and $\sum_a p(a) = 1$ for every input rho. This is the validity condition of Oreshkov, Costa and Brukner, applied to the process seen by the parties once the source is prepared and the sink discarded. Fixing the source in $|0\rangle$ and tracing the sink yields $W_w = \sum_o |o\rangle\langle o|_O \otimes |w(o)\rangle\langle w(o)|_I$, the classical process matrix of w.

So purity gives validity with no further assumption. The only input specific to process functions is Step 1.

Lean (finite dimensions). All four steps are machine-checked, standard axioms only.

- *Step 1, isometries:* `PFUL.induced_isometry`. If every local map is an isometry ($V_k^\dagger V_k = 1$, not necessarily square), then $M^\dagger M = 1$. It rests on the column identity with constant row sums (`PFUL.Column.sum_prod_eq_prod`).
- *Step 2, Stinespring:* `PFUL.krausDilP_isometry` and `PFUL.ptrace_krausDil`. Any Kraus family has the isometric dilation $V = \sum_j K_j \otimes |j\rangle$, which reproduces the channel. `PFUL.Choi.kraus_of_choi` gives a Kraus family from any PSD Choi matrix (spectral theorem), complete when the map is TP.
- *Step 3, ancillas:* `PFUL.valid_kraus` (with `PFUL.valid` for unitaries). For any joint density matrix of source and ancillas (entangled or shared), the global output and the sink state are density matrices.
- *Step 4, instruments:* `PFUL.valid_instrument`. Outcome-conditioned sink states are PSD and sum to a density matrix, so the probabilities sum to 1.
- *Process-matrix form:* `PFUL.Choi.procMat` defines $W = |U\rangle\rangle\langle\langle U|$. `PFUL.Choi.born_eq_trace` shows $\mathrm{Tr}[W (\mathrm{rho} \otimes 1_F \otimes \otimes_k C_k)^T] = \mathrm{Tr}[M\, \mathrm{rho}\, M^\dagger]$. `PFUL.Choi.bornC_eq_one` gives the AFNB/OCB normalisation = 1 for every source state and all local CPTP Choi matrices.
- *Ancillas, converse, Choi's theorem:* `PFUL.Choi.born_anc_eq_one` and `bornC_anc_eq_one` give the Choi-form normalisation with party ancillas (local maps $I_k X_k \to O_k Y_k$, ancilla state folded into the source state). `PFUL.Choi.procMat_posSemidef` shows W is PSD. `PFUL.Choi.afnb_iff_density` shows AFNB normalisation is equivalent to the density-matrix condition. `PFUL.Choi.isCP_iff_choi` is Choi's theorem (CP iff PSD Choi matrix), so CP is a theorem rather than a definition.

Bookkeeping: `PFUL.Choi.bornAnc_eq_one` needs no structure on the ancilla types. `PFUL.Choi.bornSplit_eq_one` and `PFUL.Choi.afnb_iff_density_split` use exactly the index layout of `ValidWith`. `PFUL.Choi.validity_package` bundles unitary validity, Kraus-channel validity and AFNB normalisation in one theorem. Infinite dimensions (countable alphabets). The unitary layer there is `PFUL.Countable.induced_unitary_l2`. Mathlib has no trace-class or Hilbert-Schmidt operators on

infinite-dimensional Hilbert spaces, so the project builds them against its pinned Mathlib (`lean/PFUL/TraceClass.lean`, no `sorry`, standard axioms only). Hilbert-Schmidt operators have a basis-independent norm (`PFUL.TraceClass.hsSq_indep`). The trace class is the span of products A†B of Hilbert-Schmidt maps. Its trace Tr T = $\Sigma\langle e_i, T\, e_i\rangle$ converges for every Hilbert basis to the same value (`hasSum_trace`). It is linear (`traceL`), cyclic against bounded operators (`trace_comp_comm`), nonnegative on positive operators (`trace_nonneg`), gives $\mathrm{Tr}|x\rangle\langle y| = \langle y, x\rangle$ (`trace_rankOne`), is invariant under isometric conjugation (`trace_conj`), and obeys $|\mathrm{Tr}\, T| \le \|T\|_1 < \infty$ with $\|T\|_1$ = sup over $\|C\| \le 1$ of $|\mathrm{Tr}(CT)|$ (`enorm_trace_le_traceNorm`, `traceNorm_ne_top`). The trace class is a two-sided ideal (`comp_mem_left`, `comp_mem_right`). The partial trace over J is defined on $H \otimes \ell^2(J)$, realised as $\ell^2(J; H)$, and on $\ell^2(I \times J) \cong \ell^2(J; \ell^2(I))$ (`l2ProdEquiv`). It is the unique trace-class operator with $\mathrm{Tr}(\mathrm{Tr}_J(T)\, C) = \mathrm{Tr}(T\, (C \otimes 1))$ for all bounded C (`trace_ptrace_comp`, `ptrace_unique`, `trace_ptraceR_comp`). It is linear, preserves positivity and the trace (`ptrace_add`, `ptrace_smul`, `ptrace_isPositive`, `trace_ptrace`), and sends $|x\otimes y\rangle\langle x'\otimes y'|$ to $\langle y', y\rangle|x\rangle\langle x'|$ (`ptrace_rankOne_tensor`). With these, `PFUL.Countable.valid_density_l2` restates validity on countable alphabets in trace form. For every density operator ρ on ℓ^2(sources × input ancillas), entangled ancillas included, the output ΦρΦ† of the unitary from `induced_unitary_l2` and the sink state $\mathrm{Tr}_Y(\Phi\rho\Phi^\dagger)$ are density operators, so Tr = 1. The Choi form $\mathrm{Tr}[W(M_A \otimes M_B \otimes \ldots)] = 1$ is also formalised for countable alphabets (`lean/PFUL/BornPairing.lean`). There neither W nor a local Choi operator is trace class (a channel's Choi operator has partial trace equal to the identity), so the pairing is not a trace of a product of trace-class operators. Instead $W = |U\rangle\rangle\langle\langle U|$ is kept as the family of its row vectors u_r, with entries $u_r(c) = \mathrm{conj}\, M(r, c)$ and $M(r, c) = \prod_k V_k(\ldots)$ (`rowVec_apply`). The pairing with an input density operator ρ is the series $\Sigma_r \langle u_r, \rho\, u_r\rangle$ over sink outcomes r = (o, y), which is the limit of its finite truncations; in finite dimensions it is exactly the Born rule $\mathrm{Tr}[W(\rho \otimes 1 \otimes \bigotimes C_k)^T]$ (`PFUL.Choi.born_eq_trace`). `PFUL.Countable.valid_born_l2` proves that this series has nonnegative terms, converges unconditionally to 1, and equals $\mathrm{Tr}[\mathrm{Tr}_Y(\Phi\rho\Phi^\dagger)]$ from `valid_density_l2`. `PFUL.Countable.valid_kraus_l2` (`lean/PFUL/KrausL2.lean`) extends this to arbitrary local channels with countably many Kraus operators: $V_k(o, y)(i, x) = \langle o|K_y|i, x\rangle$ with the Kraus index y as output ancilla, so completeness $\Sigma_y K_y^\dagger K_y = 1$ is orthonormality of the columns of V_k (an isometry, not a unitary). The induced operator is then an isometry (`induced_isometry_l2`); its columns are orthonormal by a polarization argument that reduces the Gram identity to the unit-column theorem (`induced_gram`). For every density operator ρ, ΦρΦ† and $\mathrm{Tr}_Y(\Phi\rho\Phi^\dagger)$ are density operators, and the Born pairing converges to 1. The polar decomposition is formalised for every bounded operator (`lean/PFUL/Polar.lean`). With $|T| = \sqrt{(T^\dagger T)}$ (Mathlib's continuous functional calculus), there is a partial isometry V, isometric on the closure of the range of |T| and zero on its orthogonal complement, with T = V|T|, V†V the projection onto that closure, and V†T = |T| (`PFUL.Polar.polar`, `adjoint_partialIso_comp`, `adjoint_partialIso_comp_self`). For trace-class T, |T| is trace class and $\|T\|_1 = \mathrm{Tr}|T|$ (`absOp_mem`, `traceNorm_eq_trace_abs`). Conversely, T is trace class iff $\Sigma_i \langle e_i, |T|\, e_i\rangle$ converges in some Hilbert basis (`mem_traceClass_iff`). V is a partial isometry, VV†V = V (`IsPartialIsometry`, `isPartialIsometry_partialIso`). The decomposition is unique: if T = WA with A positive, W isometric on the range of A and zero on its orthogonal complement, then A = |T| and W = V (`polar_unique`). A self-contained, Mathlib-style version of the polar decomposition, with no project dependencies, is in `lean/MathlibPR/PolarDecomposition.lean`. The trace-class files are universe-polymorphic: a Hilbert space H may live in any universe `Type u`, with Hilbert-Schmidt factors and basis index types in the same universe. The countable-alphabet theorems (`valid_density_l2`, `valid_born_l2`,

`valid_kraus_l2`) are universe-polymorphic too, as are the finite-alphabet combinatorial files. Trace-class operators are compact (`PFUL.TraceClass.isCompactOperator_of_mem`, via Hilbert-Schmidt operators as norm limits of finite-rank truncations), and every trace-class T has a Schmidt decomposition (`PFUL.Polar.schmidt`): a Hilbert basis v of eigenvectors of |T| with eigenvalues $s_n \geq 0$, vectors u_n orthonormal where $s_n \neq 0$, $T\,x = \Sigma\, s_n \langle v_n, x\rangle u_n$, and $\Sigma\, s_n = \mathrm{Tr}|T| = \|T\|_1$. For a local channel given by its Kraus kernel, the Choi kernel $J(o,a;o',a') = \Sigma_y\, V(o,y)(a)\ \mathrm{conj}\ V(o',y)(a')$ converges, satisfies the trace-preservation condition $\Sigma_o\, J(o,a;o,a') = \delta_{aa'}$, and is positive semidefinite on every finite section (`PFUL.Countable.choiKernel_tp`, `choiKernel_psd`, `lean/PFUL/ChoiL2.lean`). Conversely, every kernel on countable alphabets whose finite sections are positive semidefinite and which satisfies the trace-preservation condition is the Choi kernel of a Kraus kernel over a countable Kraus index with $\Sigma_y\, K_y^\dagger K_y = 1$, so `valid_kraus_l2` applies to every such Choi-specified channel (`PFUL.Countable.exists_kraus_of_choi`, `lean/PFUL/ChoiConverse.lean`; Mathlib's Moore–Aronszajn reproducing-kernel Hilbert space, then Gram–Schmidt over an enumeration).

`PFUL.TraceClass.IsCPTP` is a standalone predicate for maps on trace-class operators: they preserve the trace class, are linear there, preserve the trace, and $\Phi \otimes \mathrm{id}_Z$ preserves positivity for every finite ancilla Z. Every Stinespring/Kraus channel $\rho \mapsto \mathrm{Tr}_J(V\rho V^\dagger)$, with V an isometry and J any Kraus index, satisfies it (`isCPTP_stinespring`, `lean/PFUL/CPTP.lean`), and CPTP maps send density operators to density operators (`IsCPTP.isDensity`). Finite-rank operators are dense in the trace class in trace norm (`PFUL.TraceClass.exists_finiteRank_traceNorm_lt`). `IsNormalCPTP` adds trace-norm boundedness (continuity) to `IsCPTP`, and on countable ℓ^2 a map is normal CPTP iff it is a Kraus channel $\rho \mapsto \mathrm{Tr}_Y(U\rho U^\dagger)$ over a countable Kraus index (`PFUL.Countable.isNormalCPTP_iff_kraus`, `lean/PFUL/KrausNormal.lean`). The proof takes the Choi kernel of the map (positive by complete positivity, trace preserving), factors it by `exists_kraus_of_choi`, and extends agreement from the matrix units $|a\rangle\langle a'|$ to the whole trace class by trace-norm continuity (`eq_of_rankOne_basis`). The kernel-form channel of `valid_kraus_l2` is identified with the abstract Stinespring channel (`krausChannel_eq_stinespring`), so validity holds for arbitrary normal CPTP local channels on countable alphabets (`PFUL.Countable.valid_normalCPTP_l2`). For the commuting Switchboard case of H.8.4, the linear-algebra core is formalised in finite dimensions (`PFUL.Switchboard.commuting_blend`): if the rank-one projectors commute with those of a reference orthonormal basis, p_φ is a convex mixture of deterministic records, one per basis vector. That each record is a process function is not formalised. The Schmidt series also converges in trace norm, with $\|T - \Sigma_{n\in F}\, s_n |u_n\rangle\langle v_n\|_1 \leq \Sigma_{n\notin F}\, s_n$ (`PFUL.Polar.schmidt_traceNorm`). The H.12 counterexample is formalised in finite dimensions (`PFUL.Counterexample.purification_conjecture_false`): the Switchboard is pure against all finite local ancillas and unitaries (`isPure_Vsb`), its induced process is valid under all stochastic local interventions (`valid_pcl`), and it violates an inequality satisfied by every process function on three binary parties, $L(p) = (32 - 24\sqrt{2})/128 < 0$, so it lies outside their convex hull; the finite checks are kernel-evaluated by `decide +kernel` without `native_decide`. The counterexample's own definitions are linked to the general framework: its process-function predicate is exactly `PFUL.Countable.IsProcessFunction` of the bit-string form (`PFUL.Counterexample.isPF_iff`), every point of the process-function hull is valid by the general column identity (`valid_pfPoint`, `valid_of_mem_convexHull`), and the theorem is restated with the general definition (`purification_conjecture_false'`). Infinite-dimensional ancillas are covered in Lean: the loop is unitary against ancillas of any cardinality and against local operations given only as unitary kernels, with no boundedness assumed (`PFUL.Counterexample.isUnitaryKer_Vsb`,

`isUnitaryAll_Vsb`, `purification_conjecture_false_unitaryKer`; Round 11). For continuous alphabets the combinatorial core of F.5 is formalised (`PFUL.Continuous.tau_bijective`, `fiber_const`, `tauInv_apply`, c_{indep}, any cardinality), and so is the measure-theoretic step: for finitely many parties with standard Borel abelian groups carrying σ-finite right-invariant measures (Haar measure, Lebesgue measure on ℝ, the circle, counting measure), τ is measure preserving for every measurable process function, causal or not (`PFUL.Continuous.tau_measurePreserving`, with `tau_measurePreserving_real` and `tau_measurePreserving_circle`; `lean/PFUL/ContinuousMeasure.lean`). Its inverse is Borel (`tauInv_measurable`, Lusin–Souslin). The closed loop $(U\psi)(o) = \varphi(o)\psi(o - w(o))$ with any measurable unit-modulus phase φ is a unitary of L^2 (`PFUL.Continuous.closedLoop_unitary`, built from a Koopman unitary and a phase unitary; `lean/PFUL/ContinuousUnitary.lean`). The counterexample's purity is tied to the process-matrix form: `compose V A` depends on V only through its Choi vector $|V\rangle\rangle$, and the Switchboard's $W = |\mathrm{Vsb}\rangle\rangle\langle\langle \mathrm{Vsb}|$ is Hermitian with $W^2 = (\mathrm{Tr}\, W)W$ (`PFUL.Counterexample.compose_eq_link`, `compose_congr_choiVec`, `Vsb_pure_choi`; `lean/PFUL/ChoiLink.lean`). The process-matrix framework itself is formalised in finite dimensions (`lean/PFUL/ProcessMatrix.lean`; H.19.1). CPTP local operations are given by their Choi matrices (`IsCPTPChoi`, equivalent to `PFUL.Choi.IsCP` plus trace preservation by `isCPTPChoi_choiOf_iff`). The link product is defined in indices, and valid and pure process matrices are defined following AFNB (`IsValidPM`, `IsPurePM`). The counterexample is restated in these terms (`PFUL.Counterexample.purification_conjecture_false_choi`; `lean/PFUL/CounterexampleChoi.lean`). Purity with ancillas in arbitrary Hilbert spaces, and validity under normal CPTP local channels on countable ancillas, are in `lean/PFUL/CounterexampleHilbert.lean` (H.19.3, H.19.5).

Appendix B. Unequal input and output alphabets

Nothing in Section 1 needs $|I_k| = |O_k|$.

- $U : O \otimes P \to I \otimes F$, with $P = \prod I_k$ and $F = \prod O_k$, maps $|o,e\rangle$ to $|w(o)+e, o\rangle$. Both sides have dimension $\prod |I_k||O_k|$, and U is a permutation of basis states, so U is unitary for every w. Only I_k needs a group structure ($Z_{|I_k|}$); O_k is an arbitrary finite set.
- The exclusivity Lemma and its proof never compare I_k with O_k.
- A party with $|I_k| \neq |O_k|$ cannot apply a unitary $I_k \to O_k$. Its most general deterministic operation is a CPTP map, or a unitary with ancillas, $I_k\, X_k \to O_k\, Y_k$ with $|I_k||X_k| = |O_k||Y_k|$. The Theorem is stated in exactly that generality (and so is the Lean theorem, whose local types I k, O k, X k, Y k are independent). The Gram computation gives $M M^\dagger = 1$, and M is square because $\dim(P\, X) = \prod |I_k||X_k| = \prod |O_k||Y_k| = \dim(F\, Y)$. Appendix A then applies verbatim.

What holds. For any finite input and output alphabets, with any sizes, the permutation lift of a process function is a pure and valid process. **What is not covered here.** Infinite alphabets (countable ones are treated in Appendix F; continuous ones remain open, and Baumeler et al. 2019 also treat continuous variables), and lifts built from a different bijection than U.

Appendix C. Stochastic classical processes

Question. Does every logically consistent classical process admit a unitary extension, in the sense of AFNB purifiability? The process may be stochastic, not just a deterministic process function.

What is known (verified sources).

- Baumeler and Wolf (NJP 18, 013036 (2016), https://arxiv.org/abs/1507.01714) show the classical processes form a polytope. With two binary parties it has 12 extremal points, all deterministic. With three binary parties it has 710,760 extremal points, of which only 744 are deterministic, i.e. process functions. The rest are "proper mixtures" of logically inconsistent deterministic processes. One explicit example is $E_{ex1} = (C + \bar{C})/2$, the uniform mixture of the circular identity channel C ($x_1 = a_3$, $x_2 = a_1$, $x_3 = a_2$) and its bitwise negation $\bar{C}$.
- Araújo, Feix, Navascués and Brukner (Quantum 1, 10 (2017), https://arxiv.org/abs/1611.08535) define purifiability (their Definition 3). Their Theorem 4 is an exact criterion, and Section 5 gives a necessary condition, $\dim V_W \geq \operatorname{rank} W$.
- Baumeler, Gilani and Rashid (Quantum 6, 673 (2022), https://arxiv.org/abs/2104.06234) assert unitary extensibility for process functions only, via reversible embeddings, without a separate proof.
- Daher Ahmed and Kunjwal (https://arxiv.org/abs/2610.00579) conjecture that process functions are purifiable. Tobar and Costa (CQG 37, 205011 (2020), https://arxiv.org/abs/2001.02511) treat reversible deterministic dynamics.
- I found no source that claims to settle purifiability of the non-deterministic extremal points.

C.1 Proposition (proved). Every convex mixture of process functions is purifiable.

Proof. Let $W = \sum_j p_j W_{w_j}$. Take source $P' = C^J \otimes P$ and sink $F' = C^J \otimes F$, and define $U|o, e, j\rangle = |w_j(o) + e\rangle_I |o, j\rangle_{F'}$. With local unitaries inserted, the induced operator is the block sum $\oplus_j M_j$. Each M_j is unitary by the Theorem of Section 1, so the process is pure. Feed $\sum_j \sqrt{p_j}|j\rangle \otimes |0\rangle$ into P'. This is a fixed pure state, equivalently $|0\rangle$ followed by a unitary that is absorbed into U. Then trace out F'. Because the sink keeps a copy of j, the cross terms vanish and the result is $\sum_j p_j W_{w_j} = W$. ∎

The control register must enter through the source and leave through the sink. If it is not handed to the sink, the coherence between branches survives, and the result is no longer the classical mixture. Hence the whole deterministic-extrema polytope of Baumeler and Wolf is purifiable. This covers every two-party classical process with binary inputs and outputs, since there all extremal points are deterministic.

C.2 E_{ex1} is not purifiable (exact certificate). Scripts are in code/stochastic/.

Reduction. In AFNB Theorem 4 the auxiliary sink F' behaves as a party with trivial output. Every term of the projector $L_V^{\perp}$ therefore traces out and replaces F'. Write $w_i = \Sigma_k |w_{i,k}\rangle|k\rangle_{F'}$ and define X_i by $X_i |p_k\rangle = \sqrt{E_{p_k}} |w_{i,k}\rangle$. The conditions become $L_3^{\perp}(X_i \Lambda X_j\dagger) = 0$ for all i, j, with $\Lambda = \operatorname{diag}(1/E)$ on the support. Here $L_3^{\perp}$ is the ordinary three-party projector on 64×64 matrices, and $X_0 = W$. This takes seconds instead of tens of minutes, and it reproduces the full computation ($\dim V_W$ 27 for E_{ex1} and 56 for Lugano).

Certificate.

- E_{ex1} is logically consistent and is a vertex of the three-party binary polytope (active-constraint rank 64 of 64). Hence it is not a mixture of process functions.

- rank W = 16. Exact integer arithmetic (python-flint) gives dim $V_W = 27$.
- One explicit integer combination of the constraint functionals (code/stochastic/exact.py, cert_phi.npy) gives a sesquilinear form on V_W. Its symmetric part has exact inertia (13 positive, 13 negative, 1 zero), computed by rational congruence elimination.
- The span of $w_0, ..., w_{15}$ is a 16-dimensional subspace on which this form must vanish, so it is totally isotropic for the symmetric part. But a totally isotropic subspace has dimension at most $1 + \min(13, 13) = 14 < 16$. So no purification exists.
- An independent numerical check agrees. A gradient search for purifications reaches residual $8 \cdot 10^{-14}$ for Lugano (which is purifiable), but stalls at 79.7 for E_{ex1}.

C.3 Purifiable set and the (former) conjecture. The control-register argument of C.1 works for any purifiable processes, not just process functions. So the purifiable classical processes form a convex set containing the hull of the process functions. We conjecture they are exactly that hull:

Conjecture (refuted, H.12.1). A classical process is purifiable iff it is a mixture of process functions. The "if" half is C.1; the "only if" half is false.

Provenance. The "if" half was asserted earlier by Baumeler, Gilani and Rashid (Quantum 6, 673 (2022), ref. 27): every mixture of process functions embeds into a reversible process function, and is therefore "unitarily extensible". As far as we found, the "only if" half had not been stated in print before this note, and no counterexample was known. A related open question is Kunjwal and Oreshkov's (arXiv:2307.02565, ref. 36): can correlations from unitarily extendible process matrices be antinomic? The refutation here does not settle it; see H.13.5.

Evidence so far.

- 40,000 random LP vertices of the three-party binary polytope gave 39,354 deterministic vertices and 646 non-deterministic ones. These fall into 51 orbits under party permutations and local input/output relabellings (code/stochastic/reps.json). Ranks are 15–23.
- AFNB's necessary condition $\dim V_W \geq \text{rank } W$ holds for all 51 orbits (nec_partial.json), so on its own it decides nothing. $\dim V_W$ ranges from 27 to 256.
- Exact certificates of non-purifiability exist for the 2 orbits with $\dim V_W = 27$, one of which contains E_{ex1} (exact2.py, cert_phi_7.npy, cert_phi_50.npy).
- For the other 49 orbits ($\dim V_W \geq 82$) the random-form isotropy test was inconclusive. The GPU gradient search of C.4 found no purification for any of them (best residual ≥ 12.97). This is numerical evidence only.
- No purifiable non-mixture has been found. That is weak evidence, because the large cases are untested.
- All 1,488 mixtures $(q + E_{ex1})/2$ and $(q + 4\,E_{ex1})/5$, with q one of the 744 process functions, lie outside the process-function hull (LP check). They are untested candidates for non-extreme counterexamples.

C.4 GPU sweep over the 49 open orbits (numerical evidence, not proof).

- Method: code/stochastic/gpu/gpusearch.py ran on one RTX 3090. For each orbit it made 64 random restarts of batched L-BFGS in float32 on the reduced Theorem 4 residual, then polished in float64.
- Validation: the same code finds Lugano's purification (residual 1.2e-16) and stalls at 79.676 on E_{ex1}, which is certified non-purifiable.

- Result: no orbit reached the 1e-10 threshold. The best residuals range from 12.97 (orbit 40) to 59.35. Every orbit stalled far from zero.
- Interpretation [superseded by H.12]: this is consistent with the conjecture that none of the 49 non-deterministic vertex orbits is purifiable. But a local search can miss solutions, so it is not a proof. Only orbits 7 and 50 (C.2) have exact certificates.

orbit	rank	dim V_W	best residual (float64)	restarts
0	15	124	20.12	64
1	16	176	13.03	64
2	15	156	15.62	64
3	15	156	15.49	64
4	16	128	21.93	64
5	16	160	12.98	64
6	16	144	18.48	64
8	16	82	35.84	64
9	16	112	27.06	64
10	16	82	34.75	64
11	16	128	21.72	64
12	16	112	26.91	64
13	16	196	12.97	64
14	16	144	18.49	64
15	16	168	13.02	64
16	15	156	19.57	64
17	15	164	15.82	64
18	16	160	13.02	64
19	16	160	12.97	64
20	16	82	35.32	64
21	16	128	21.73	64
22	16	164	18.44	64
23	16	172	12.99	64
24	16	112	26.78	64
25	16	136	21.76	64
26	16	128	21.88	64
27	16	144	18.5	64
28	15	124	20.12	64
29	16	144	18.51	64
30	16	168	13.02	64
31	16	160	13.02	64
32	21	160	49.61	64
33	16	164	18.46	64
34	20	174	35.72	64
35	16	160	13.02	64
36	16	160	12.97	64
37	16	160	12.98	64
38	22	176	48.56	64
39	21	146	59.35	64
40	16	196	12.97	64
41	16	204	13.01	64

orbit	rank	dim V_W	best residual (float64)	restarts
42	16	172	12.99	64
43	22	224	25.58	64
44	21	160	50.3	64
45	21	174	41.12	64
46	20	166	34.6	64
47	23	248	42.74	64
48	21	172	37.9	64
49	23	256	29.02	64

C.5 Exact-certificate attempt for the dim V_W = 82 orbits 8, 10, 20 (Oct 21 2026). Status labels: orbits 7, 50 (and E_{ex1}) **[certified exact]**; all 49 orbits in the C.4 table **[numerical only]**. No new certificate was obtained.

- Earlier single-form runs (20 time-boxed rounds per orbit, `cert/results_cpu/status.jsonl`) and block forms with k = 2 (`cert/better/NOTES.md`) found no certificate. The best bound was 20.5 > r = 16.
- New numerical probe (`cert/isodim.py`, logs in `cert/better/isodim*.log`; 8 CPU threads, 2 restarts x 600 Adam steps per size). It asks for the largest complex subspace of V_W that is totally isotropic for all constraint forms, ignoring the Gram and fixed-vector conditions. Isotropy loss at dimension 8 / 10 / 12: orbit 8: 1.3e-3 (3.7e-6 after 2,500 steps) / 0.22 / 0.68 (14: 1.46; 16: 2.34); orbit 10: 1.5e-5 / 1.3e-5 / 0.55; orbit 20: 2.0e-6 / 2.6e-4 / 0.53. So isotropic subspaces seem to exist up to dimension about 10 and to fail by 12. That is far below r = 16, which is consistent with non-purifiability, but it is numerical only.
- Why the linear certificate families fail. A Hermitian combination H of the constraint forms certifies only if n+(H) + n0(H) < 16, i.e. n-(H) ≥ 67 of 82. The searches plateau at lambda_16(H)/||H|| ~ +1e-4. Adding the Gram normalisation C^H G C = tr(W) I does not help: G is PSD, so n+(H + muG) ≥ n+(H) for mu > 0, and the extended test certifies nothing the plain test cannot. The fixed vector c0 lies in the common radical (NOTES item 3). So the gap between the isotropic dimension (~10) and r (16) is invisible to every linear or block-Hermitian form tried. It is a genuinely nonlinear (non-convex) obstruction. A sound exact certificate would need, e.g., a degree-4 Positivstellensatz showing that some 67-dim subspace of V_W contains no nonzero jointly isotropic vector, or a determinantal argument (rank K(u) > 66 on the jointly isotropic cone). Neither has been set up: an unreduced degree-4 SDP has ~10^4-size blocks, which is beyond this box (8 cores, 15 GB) and far beyond the per-orbit budget. The larger orbits (dim V_W 112-256) face the same obstruction with a larger gap, so the estimate that about half are certifiable by the current pipeline is not supported.

C.6 Degree-4 certificates for orbit 8 (Oct 22 2026) [numerical obstruction; no certificate; no paid compute used]. C.5 proposed a degree-4 Positivstellensatz: exhibit a subspace L of V_W of dimension 67 that contains no nonzero jointly isotropic vector. That would rule out an isotropic 16-plane, since 16 + 67 > 82. The degree-2 (form-based) version provably fails (C.5). Before renting hardware I tested whether any certificate of this shape can exist.

- *Radical.* The common radical of the 4096 constraint forms (as sesquilinear forms on V_W, orbit 8) has dimension exactly 1 (c0; smallest singular values 0.81, 0.81, 2e-14). So work in R^perp (dim 81). (cert/cone67c.py)

- *Probe.* For Haar-random L in R^perp, minimise the isotropy loss f(u) = ||L3perp(X(u) Lam $X(u)^H$)||^2 over unit u in L (Adam, then L-BFGS). The baseline for random unit u is min 0.078, median 0.108.
  - d = 67: minimum 1.9e-9 (cone67c_orbit8.log). An earlier run without removing the radical gave 1.3e-8 (cone67b_orbit8.log).
  - d = 60: minimum 2.3e-7 (cone60c_orbit8.log).
- *Reading [numerical].* The loss falls 7-8 orders of magnitude below baseline. So random subspaces of dimension 67, and even 60, contain (numerically) jointly isotropic vectors outside the radical. A certificate "L has no isotropic vector" of any degree cannot exist for such an L, because it would be a proof of a false statement. The set of isotropic directions is large: it meets random subspaces of codimension at least 21 in R^perp. This matches H.2, which found tangent dimension about 27-31 on the cone. The forms are real quadratic (sesquilinear), so the complex projective dimension theorem does not apply, and I have not proved that *every* 67-dim L meets the cone. A specially chosen L is not excluded by this probe. But no construction of one is known, and random choice fails.
- *The remaining degree-4 route is out of reach by size.* Level-2 Lasserre on the full frame problem (16 x 82 complex, i.e. 2,624 real unknowns) has a moment matrix indexed by monomials of degree ≤ 2: about 3.4 x 10^6 rows. That is far beyond any $60 machine. Quotienting by the U(16) frame symmetry leads to the projector relaxation of Appendix E (degree 2 in P = degree 4 in the frame). That relaxation is already feasible for E_{ex1}, so it is weaker than single-form inertia and cannot certify orbit 8.
- *Spend.* Because both degree-4 formulations are ruled out (one numerically, one by size and by the E_{ex1} control), no instance was rented. **Paid compute used: $0.** Existing vast.ai CLI credentials were found on the box and left untouched. **No certificate for orbit 8. Status unchanged: [numerical only].**

Proof idea for "only if" (not completed). A purification U restricted to classical permutation instruments gives a unitary M for every reversible local classical operation. One would like to show that M's action on basis states then decomposes into permutations, giving a deterministic decomposition. We have not proved this. E_{ex1} shows the classical consistency of W alone is not enough.

Answer. Not every classical process admits a unitary extension: E_{ex1} (and one other vertex orbit) provably does not. Mixtures of process functions do. Whether those are the only ones was the conjecture above; H.12.1 shows they are not.

Appendix D. Purifications of classical processes: the physics route

Status labels: **[proved]**, **[conjecture]**, **[gap]**. Nothing here proves the conjecture. (Written before H.12, which refutes it.)

Setting. A purification of a classical process W (diagonal; equivalently a stochastic map p(i|o) on the joint classical inputs i and outputs o of the parties) is a unitary V : P ⊗ O → F ⊗ I together with a fixed source state |psi⟩ in P such that (i) W = Tr_F of the Choi vector of V(|psi⟩ ⊗ .), and (ii) for every choice of local operations (unitaries with ancillas) the induced map P ⊗ ancillas → F ⊗ ancillas is unitary (AFNB 2017). Write V|psi, o⟩ = $\sum_i$ |i⟩ ⊗ $|v_{o,i}\rangle$ with $v_{o,i}$ in F.

Lemma D.1 [proved]. $\langle v_{o',i'} \mid v_{o,i}\rangle$ = $delta_{o\ o'}$ $delta_{i\ i'}$ p(i|o). Proof. The Choi matrix of the induced channel O → I is $\sum_{o,o'}$ |o⟩⟨o'| ⊗ Tr_F[V|psi,o⟩⟨psi,o'|V†], whose ((o,i),(o',i')) entry is $\langle v_{o',i'}|v_{o,i}\rangle$. W is diagonal with diagonal entries p(i|o). QED. Consequence: the sink holds a perfect record of the pair (o,i): the normalised vectors $f_{o,i}$ =

$v_{o,i}$/sqrt(p(i|o)) (over the support of W) are orthonormal, so dim F ≥ |supp W| = rank W = r (the same r as in AFNB Thm 4). Checked numerically on the source-sink lift of Lugano (code/stochastic/physics/lemma_d1_check.py).

Lemma D.2 [proved; negative]. Conditions (i)-(ii) restricted to the source state |psi⟩ impose nothing beyond W being a classical process. For classical deterministic interventions with input copies, o = f(i) (+) a with the input i copied to a private ancilla, the output for ancilla value a is $\sum_i |i\rangle_{anc} \otimes \text{sqrt}(p(i|f(i)+a))\ f_{f(i)+a,\,i}$; by D.1 these are orthogonal for a ≠ a' and have total norm $\sum_i p(i|f(i)+a) = 1$ (logical consistency). Hence any non-purifiability (e.g. E_{ex1}, orbits 7 and 50) must come from the action of V on source states orthogonal to |psi⟩. Any proof of the conjecture would have had to use those states (moot after H.12). This is where proposal (2) breaks down: the "which-function" label lambda cannot come from a basis of the span of |psi⟩ alone.

Where proposal (2) fails [gap]. The intended argument: under each intervention the global map is a generalised permutation conditioned on a source label lambda; expanding $|\text{psi}\rangle = \sum_{\text{lambda}} c_{\text{lambda}} |\text{lambda}\rangle$ gives W = sum $|c_{\text{lambda}}|^2\ W_{w_{\text{lambda}}}$. Three gaps: (a) Unitarity under local unitaries does not obviously make V, restricted to classical party inputs, a generalised permutation. D.1 gives orthogonality only for the fixed |psi⟩, and only after tracing the party wires through W. (b) Even when it holds for each intervention f separately, the label lambda may depend on f (no single basis of P works for all f). Ruling this out is exactly the noncontextuality-type step that is missing. (c) Coherences in |psi⟩ across labels: they vanish from W by D.1, but they constrain V on psi-perp, see (b).

Conjecture D.3. If V purifies a classical process, there is an orthonormal basis {lambda} of P such that $V|\text{lambda}, o\rangle = \text{phase} * |w_{\text{lambda}}(o)\rangle \otimes |g_{\text{lambda}}(o)\rangle$ for functions w_{lambda}, with g_{lambda} injective on outputs. D.3 implies the conjecture: each w_{lambda} must then be a process function, since V must stay unitary under classical interventions restricted to the source state |lambda⟩, and by Baumeler-Wolf that means a unique fixed point. D.3 holds for our source-sink lifts. It has not been tested on the non-permutation purifications found by the optimiser (Lugano, App. C); that test is the next step. A counterexample to D.3 that is still a mixture would refute only D.3, not the conjecture.

D.4 Conjecture D.3 is false (update, Oct 10 2026) [proved, exact counterexample]

Write $G_{i,o} = V_o\dagger\ (Pi_i \otimes 1_F)\ V_o$ on P, where $V_o|s\rangle = V|s,o\rangle$. D.3 is equivalent to: all $G_{i,o}$ are projectors that commute pairwise (their common eigenbasis is the label basis lambda). Counterexample: a causally ordered circuit (code/stochastic/physics/d3_counterexample.py). Party A has trivial input and output oA. The source is P = m ⊗ a. Apply H^{oA} to m, CNOT m → a, send m to B's input, and route (oA, oB, a) to the sink. V is a permutation-and-Hadamard circuit of unitaries in a fixed causal order, so it is a valid unitary process. With psi = |00⟩ the process is classical: $p(iB|oA=0) = \text{delta}_{iB,0}$ and p(iB|oA=1) = 1/2. Lemma D.1 holds: W is diagonal. W is a mixture of process functions ($w_{\text{lambda}}(oA) = \text{lambda}*oA$). But the G's are Z-projectors for oA=0 and X-projectors for oA=1. They do not commute (commutator norm 1/2), so no source basis works. Restricting to psi does not help either: psi = |00⟩ is an eigenvector of the oA=0 projectors only.

Consequence. Gap (b) is real. Even for causal processes, the "which-function" randomness is generated contextually, by measuring the quantum source in a basis that depends on earlier outputs. So no argument that extracts a single classical label from the source can work, and unitarity under all local unitaries does not force one. The mixture conclusion still holds here for a different reason: every causally ordered classical process is a mixture of causal deterministic ones. A proof of "purifiable ⇒ mixture of process functions" therefore has to show directly

that W lies in conv(PF), for example that purifiability implies every facet inequality of the PF polytope. It cannot go through a source-label decomposition. Status at the time: the conjecture was open; D.3 is refuted. The conjecture itself was later refuted (H.12.1).

D.5 The hull route (Oct 10 2026)

Proposition D.5 [proved]: validity under quantum-controlled interventions is automatic, so it cannot be the criterion. Let W be any classical process, including E_{ex1} and all 49 open orbits. Let the parties apply arbitrary local instruments, coherently controlled by a shared ancilla that may be entangled across parties. Then the probabilities are normalised. Reason: W is diagonal, so it dephases every party's input and output. The effective intervention is then a classical joint behaviour q(o|i) produced from a shared quantum state by local operations, so q is non-signalling. Every non-signalling behaviour is an affine (not necessarily convex) combination of local deterministic ones. The normalisation $\sum_{i,o} p(i|o)\, q(o|i)$ is affine in q and equals 1 on every local deterministic q (logical consistency), so it equals 1 for all such q. Positivity is termwise. So the proposed test "valid under quantum-controlled interventions" holds for every classical process. It cannot separate E_{ex1} from PF mixtures, and step (3) of the plan is moot. Purifiability is strictly stronger only because of its unitarity (reversibility) requirement.

Proposition D.6 [proved, sketch]: classical-reversible purifiability ⇔ mixture of PFs. Call W classically purifiable if it is the marginal, for a random source value lambda, of a classical reversible process: a bijection (lambda, o) → (i, sink) that stays a bijection P → F under every deterministic local intervention. For a fixed lambda this is a deterministic process. Bijectivity of the composite map under every intervention f forces exactly one consistent execution: zero leaves the source value with no image, and two collide by counting. So each w_{lambda} is a process function (Baumeler-Wolf 2016), and $W = \sum_{lambda} p(lambda)\, W_{w_{lambda}}$. The converse is the source-sink construction with a random source. Hence **the conjecture was equivalent to: a classical process that is quantum-purifiable is already classically purifiable.** D.4 shows the quantum purification itself need not be classical (its labels are contextual), so this has to be argued at the level of W.

Facets of the PF hull [computation]. The 744 process functions (3 parties, binary) span a 37-dimensional affine space. Facet enumeration results are recorded below. Each facet that some open orbit violates is a candidate inequality that purifiability would have to imply. Full facet enumeration was not done: pycddlib does not build on the box, and 744 vertices in dimension 37 may have very many facets. Instead, sep.py finds by LP a separating inequality of the PF hull (box-normalised, $|f| \le 1$): E_{ex1} and orbit 7 violate one by 6.0, orbit 8 by 4.0, and a PF mixture by 0, as expected. These inequalities are not reduced modulo the affine hull or by symmetry, so their supports carry no meaning yet. **No inequality has been derived from purifiability. The conjecture remained open at this point; H.12.1 later refuted it.** Next steps: enumerate facets with lrs/normaliz or by symmetry-adapted LP, then try to derive one facet class from Theorem 4 (isotropy) together with Lemma D.1.

D.7 Facets of the PF hull: partial (Oct 10 2026)

Tools. lrslib 7.3 builds from source with gcc (no make, no GMP on the box; hybrid 64/128-bit plus built-in MP arithmetic). normaliz and PANDA were not installed: there is no make/cmake, conda or sudo on the box. The full enumeration with lrs (744 vertices in the 37-dim span, `facets/pf.ext`) produced no output in 5 minutes, not even from `estimates`, because the input is highly degenerate. **No facet count or runtime estimate yet.** A double description or symmetry-exploiting code (normaliz, PANDA with the 384-element symmetry group) on a rented multi-core CPU is the natural next step; its cost is unknown until a short benchmark is run.

Facets found by polar LP (`facets/facetlp.py`). Each LP optimum was checked to be a facet: its tight PFs have affine rank 36. Facets are classified up to the 384 symmetries (party permutations and input/output relabelings; all 384 preserve the PF set). Over E_{ex1} and the 51 sampled non-deterministic vertex orbits, the optimal separating facets fall into **8 classes**. Class 0 (418 tight PFs) is violated by E_{ex1} and 24 orbits, including orbit 8. Class 2 (418) covers orbits 7, 50 and 15 others; classes 1, 3-7 cover the rest. The class-0 facet, written with joint inputs i and outputs o (bits of parties A, B, C):

```
p(000|000) ≤ p(000|001) + p(010|001) + p(000|100) + p(010|110) +
p(011|111)
```

E_{ex1} gives 1/2 > 0. Combinatorial content for a process function w: if w(000) = 000, then w(001) is 000 or 010, or w(100) = 000, or w(110) = 010, or w(111) = 011.

Derivation from purifiability: not achieved. A natural attempt: use Lemma D.1 to read p(i|o) as squared norms of orthogonal sink vectors, then try to show the class-0 inequality follows from unitarity under suitable superpositions of the five interventions involved. This has not been carried through and is not claimed.

D.7 update: complete facet list (normaliz, Oct 10 2026)

Run: normaliz 3.8.9 (`-c -x=32`) on a rented 32-core vast.ai CPU instance, about 1.9 h, about $0.27 in total; the instance was then destroyed. Input `facets/pf.in` (744 PFs in 37 independent coordinates of p(i|o); all test points lie in the same affine span). Output `facets/pf.out.gz`.

The 3-party binary PF hull has exactly 29,344 facets, in 93 orbits under the 384-element symmetry group (`facets/classify.py`, `classes_full.json`). Orbit sizes: 384 (66 orbits), 192 (17), 128 (2), 96 (5), 64 (3). The 8 LP classes of D.7 are all among them: LP classes 0, 1, 2 are full orbits 82, 83, 84 (418 tight PFs); classes 3-6 are orbits 42, 38, 37, 41 (238); class 7 is orbit 91 (436).

Violations. E_{ex1} violates 24 of the 93 facet orbits, orbit 7 violates 53, orbit 8 violates 41, and every test point violates at least one. **Facet orbit 82, the class-0 inequality of D.7 p(000|000) ≤ p(000|001)+p(010|001)+p(000|100)+p(010|110)+p(011|111), is violated by E_{ex1} and by all 51 sampled non-deterministic vertex orbits** (by some member of the facet's orbit). So this single inequality class separates every sampled non-deterministic vertex from the PF hull. Proving it from purifiability is the natural next target. Status: facet list exact (normaliz); the derivation from purifiability is open.

D.8 Toward deriving facet orbit 82 from purifiability (Oct 10 2026): not proved

Sanity checks. Lugano and all PF mixtures satisfy every PF-hull facet, by construction. E_{ex1} violates orbit 82 (D.7).

Proposition D.8 [proved, negative]: no certificate built from the fixed source state alone can work. The proposal was an SDP over Gram matrices of sink vectors, with the source in |psi⟩ and parties applying arbitrary local unitaries (with ancillas, e.g. Hadamard superpositions of deterministic interventions). All such Gram data is a linear function of W. Inner products between outputs for ancilla inputs a, a' are $\mathrm{Tr}[W (M_a \otimes M_{a'}\dagger \ldots)]$. Unitarity on the psi-sector (orthonormal outputs for orthonormal ancilla inputs) follows from validity of W under the local operations that prepare the ancilla in a, a', (a+a')/sqrt2 and (a+ia')/sqrt2. By D.5 every classical process, including

E_{ex1}, is valid under all such operations. So these constraints are satisfiable by E_{ex1}, and any SDP over psi-sector Gram data is feasible for it: no dual certificate exists. (This strengthens D.2 from classical to arbitrary local interventions.) Any derivation of the facet must use V on source states orthogonal to psi. In AFNB Thm 4 terms, that is the non-convex isotropic-subspace condition, the same obstruction met in the certificate work (App. C). **The facet has not been derived; no certificate was found.**

Numerical boundary test (`physics/boundary.py`, `boundary.json`). On $x_t = (1-t)$ Lugano + $t\, E_{ex1}$, the PF hull is left at $t_h \sim$ 2e-7: Lugano is a vertex and this direction exits the hull at once. The full purification search (gpusearch, float64, 8 restarts) finds no purification at t = 0.02 (best residual 52.2; rank 19, dim V_W 88) or at t = 0.2 (60.1); the same code reaches about 1e-13 on Lugano itself. This was read as consistent with the conjecture [superseded by H.12], since the purifiable set appears to end where the PF hull does along this line. It is numerical evidence, not a proof. Generalisation to other facet orbits: not attempted, since no certificate exists to generalise.

D.9 Facet orbit 82 from purifiability: reductions and a negative result (Oct 22 2026): not proved

Status labels: **[proved]**, **[proved, exact]** (rational arithmetic), **[failed]**. The derivation of facet orbit 82 from purifiability is still open. Code: code/stochastic/physics/d9/ (f82_exact.py, log f82_exact.log).

D.9.1 The facet orbit, exactly [proved, exact]. The images of p(000|000) ≤ p(000|001)+p(010|001)+p(000|100)+p(010|110)+p(011|111) under the 384 symmetries are 384 distinct inequalities. In exact rationals: every one of the 744 PFs satisfies all 384 (maximum value 0), with 418 tight PFs per member. E_{ex1} violates 48 members, each by 1/2. Every one of the 51 sampled vertex orbits (reps.json, entries rounded to the exact rationals they represent) violates at least one member. The maximum violation is 1/2, except orbits 32, 34, 38, 39 and 43-49, where it is 1/3. Members violated per orbit range from 1 (orbits 2, 3, 13, 19, 37, 40) to 48 (orbit 50). This turns the D.7 numerical claim into an exact one.

D.9.2 Where facet 82 is already proved [proved]. Facet 82 holds for every purifiable W that has a purification with an operator-first party (H.6.2), or that has a W-level last party (H.1). In both cases W is a PF blend. So a purifiable W violating facet 82 has only purifications in which every party's input has a parent among the party outputs (H.6). This adds nothing to H.6; it only states the facet consequence.

D.9.3 Averaging the validity identity gives nothing [proved, negative]. The idea was to average the purity identity M M^dag = 1 over Haar (or 2-design) local unitaries, which gives linear and quadratic constraints, and then derive facet 82 by a small SOS in the 37 diagonal variables. This cannot work for constraints read on the fixed source state psi. Each such constraint is a polynomial in the numbers ⟨psi, a|M^dag ... M|psi, a'⟩ for local operations and ancilla states, possibly averaged. By D.8 these numbers are linear in W. Their values are forced by validity of W under local operations with ancillas, and by D.5 every valid classical W, E_{ex1} included, is valid under all of them. Each such identity is therefore satisfied by E_{ex1}, and so is any Haar or design average of products of these numbers. No degree-2 (or any degree) certificate in the diagonal variables alone can be built from them. Constraints that use V on psi-perp involve the off-diagonal blocks of the full Choi vector on P and F. Eliminating those blocks is the AFNB Thm. 4 isotropy problem, which is non-convex (C.5). Also, the purifiable set is convex (C.3). So any diagonal-only necessary condition that implies facet 82 implies it only through its supporting hyperplanes, and a quadratic inequality has no advantage over a linear one. The proposed numerical test (idea 4) is moot for psi-sector constraints. **[failed: idea (3) is vacuous in its psi-sector form]**

D.9.4 Where the attempt stopped.

- D.8's failure point is unchanged. A derivation must use V on source states orthogonal to psi, where the only known exact handle is single-form inertia (C.2). That handle fails for every orbit with dim $V_W \geq 82$ (C.5).
- The cyclic route (H.6, idea 2) needs a structure theorem for unitary processes whose BLO causal graph has every party influenced, for example "each input is a routed function of the other outputs and the source". BLO 2021 leave cyclic structure open, and I found no such theorem. No constraint on the diagonal was derived from cyclicity. The cyclic purification search (code/stochastic/cyclic/, future H.7) is separate work and was not touched.
- No new exact non-purifiability certificate was obtained. Status: facet 82 is proved for the purifiable W covered by H.1 and H.6. For the rest it is open.

Appendix E. Symmetry-reduced moment relaxation (negative result)

Stabilisers in the 384-element group of party permutations and input/output relabelings: E_{ex1} and orbit 50: 48; orbit 7: 16; orbits 8 and 20: 8; Lugano: 6; orbits 10 and 46: 4; 11 orbits: 2; 34 orbits: 1. Symmetry helps most where certificates already exist, and not at all for most open orbits.

Relaxation. Variables P (m x m) and Y (m^2 x m^2), Hermitian, with Y standing for P ⊗ P and F the swap. A rank-r projector onto a totally isotropic subspace satisfies $Y \geq 0$, $0 \leq P \leq I$, tr P = r, Tr_2 Y = rP, $Tr_2(YF) = P$ (from $P^2 = P$), $P \otimes I - Y \geq 0$ and $Tr_1[(Q_t \otimes 1)YF] = P\, Q_t\, P = 0$ for every form. So infeasibility would certify non-purifiability, for complex subspaces. The constraints are covariant under the stabiliser, so symmetry reduction would be legitimate.

Result: too weak. For E_{ex1} (m = 27, r = 16) the unreduced problem is small enough to solve directly by cyclic projections (code/stochastic/rep/pocs.py). The solver was checked on controls: it reaches feasibility at r = 1, 2, 4, and a 4-dim isotropic subspace exists numerically. At r = 16 the relaxation is feasible with strict margins: min eig Y = 0.13, eig P in [0.58, 0.63], min eig of $P \otimes I - Y$ = 0.019. P is close to (16/27)·I. E_{ex1} is non-purifiable and certified by single-form inertia, so this relaxation is strictly weaker than the inertia test. Symmetry-reducing it is pointless. Stronger convex certificates would need higher moment levels or must encode rank.

Algebraic geometry (assessed, infeasible by size). Solving the Theorem 4 system directly (real quadratic, since the forms are sesquilinear) means 352 real unknowns and 23,552 equations for E_{ex1}, and about 2,112 unknowns and 100,352 equations for orbit 8. Total-degree homotopy continuation would track about 2^{352} and 2^{2112} paths, and proving that no solution exists is the hard case. Gröbner bases are far out of reach. Symmetry does not reduce the unknowns, and sub-problems with small r are uninformative because non-existence first appears near r = 15-16 (code/stochastic/alggeom/SIZE_ESTIMATES.md).

Appendix F. Infinite and continuous alphabets (draft)

Literature (verified). Giacomini, Castro-Ruiz and Brukner extend the process-matrix framework to continuous-variable systems. Naive infinite-dimensional process matrices are singular, and they use a phase-space (Wigner) representation instead (New J. Phys. 18, 113026 (2016); https://arxiv.org/abs/1510.06345). The Baumeler-Wolf polytope work is for finite alphabets (https://arxiv.org/abs/1507.01714). The fixed-point characterisation of logical consistency (Baumeler and Wolf, https://arxiv.org/abs/1511.05444) and the 2025 flow-of-causal-structures paper

(Phys. Rev. Research, doi:10.1103/jsmm-tq72) work with discrete alphabets. We found no treatment of process functions on infinite alphabets, or of their unitary lifts.

Setting. Finitely many parties. Each input alphabet I_k is a countable set carrying a group structure (e.g. Z), and the outputs O_k are countable. Hilbert spaces are l^2 of these sets. A process function has a unique fixed point for every choice of local functions, exactly as before.

F.1 [proved] The lift is unitary. $U|o,e\rangle = |w(o)+e, o\rangle$ is a bijection of basis states, with inverse $(i,f) \to (f, i - w(f))$. So it is a unitary on l^2, in any cardinality.

F.2 [proved] Matrix elements and rows. Let $V_k : I_k \otimes X_k \to O_k \otimes Y_k$ be unitaries, with X_k, Y_k countable ancilla bases (they may be shared or entangled across parties; unitarity is a property of the operator, so product bases suffice). Closing the loop with U gives matrix elements whose defining sum over (o, i) has exactly one nonzero term. So no convergence question arises: $\langle f,y|M|e,x\rangle = \langle f,y|\ V\ |w(f)+e, x\rangle$, with $V = \otimes_k V_k$. Define $u_{f,y} := \sum_{e,x} \mathrm{conj}(\langle f,y|M|e,x\rangle)\ |e,x\rangle = T_{-w(f)}\ V\dagger\ |f,y\rangle$, where T_a translates the source register by a. Each $u_{f,y}$ is a unit vector. For $f \neq f'$, the exclusivity lemma gives a party k with $f_k \neq f'_k$ and $w_k(f) = w_k(f')$, so $\langle u_{f,y}|u_{f',y'}\rangle$ has the factor $\langle f_k,y_k|f'_k,y'_k\rangle = 0$. For $f = f'$ and $y \neq y'$ the factor is $\langle y|y'\rangle = 0$. Hence $\{u_{f,y}\}$ is an orthonormal set, and M†, defined on the basis by $|f,y\rangle \to u_{f,y}$, extends to an isometry. So M is a bounded operator with $M\ M\dagger = 1$. Only basis vectors and the standard extension of an isometry from an orthonormal basis are used; no strong limits are needed.

The exclusivity lemma holds for any cardinality. If $s \neq s'$ and no such k existed, then $w_k(s) \neq w_k(s')$ whenever $s_k \neq s'_k$. Choose local functions with $f_k(w_k(s)) = s_k$ and $f_k(w_k(s')) = s'_k$ (and f_k constant if $s_k = s'_k$). Both s and s' are then fixed points, a contradiction. Only two values of each f_k are prescribed.

F.3 [proved] M is unitary (the column side, F.4 in the earlier draft). An orthonormal set $\{u_{f,y}\}$ is complete iff $\sum_{f,y} |\langle e,x|u_{f,y}\rangle|^2 = 1$ for every basis vector $|e,x\rangle$ (Parseval). Now $\sum_{f,y} |\langle f,y|V|w(f)+e,x\rangle|^2 = \sum_f \prod_k q_k(f_k \mid w_k(f))$, where $q_k(o|i) := \sum_{y_k} |\langle o,y_k|V_k|i+e_k, x_k\rangle|^2$. For each i, $q_k(.|i)$ is a probability distribution on O_k, because V_k is unitary (its columns are unit vectors). Draw the local functions $f_k(i)$ independently, with law $q_k(.|i)$, for every k and i: a countable product of probability spaces. For a fixed o, the event $\{f_k(w_k(o)) = o_k \text{ for all } k\}$ has probability $\prod_k q_k(o_k|w_k(o))$. By Tonelli, $\sum_o \prod_k q_k(o_k|w_k(o)) = E[$ number of fixed points of $o \to f(w(o))\ ] = 1$, since every deterministic choice of local functions has exactly one fixed point. Hence each column has norm 1, the set is complete, and $M\dagger\ M = 1$. **Every process function on countable alphabets (inputs carrying a group structure) lifts to a unitary process: U is unitary and so is every induced map.** This argument also gives a dimension-free proof in the finite case. *Machine-checked in Lean for finite alphabets:* `PFUL.Column.sum_prod_eq_one` (the fixed-point averaging identity, over any commutative ring), `PFUL.induced_colnorm` (unit columns), and `PFUL.induced_conjTranspose_mul_of_colnorm` ($M^H\ M = 1$ from orthonormal rows plus unit columns, with no dimension count). Standard axioms only. For countable alphabets, the column identity and unit column norms are machine-checked too: `PFUL.Countable.tsum_prod_eq_one` ($\mathbb{R}\geq 0\infty$ sums, via the product measure `Measure.infinitePi`; inputs of any cardinality) and `PFUL.Countable.induced_colnorm`. Row orthonormality (`PFUL.Countable.induced_rows`, using the factorisation lemma `PFUL.Countable.hasSum_pi_prod`) and the assembly are machine-checked as well: `PFUL.Countable.induced_unitary_l2` gives a linear isometric equivalence between the ℓ^2 spaces whose matrix is M. So in Lean M is unitary for countable alphabets. Exclusivity gives orthogonal rows, and logical consistency under stochastic interventions gives unit columns.

The earlier draft's special cases (permutation interventions; causally ordered w) are now corollaries. The earlier remark that two-party process functions are causal still holds for any cardinality, by the two-fixed-point argument: first w_k is independent of o_k, then w_A and w_B cannot both be non-constant. That remark is no longer needed. No counterexample search is needed either, because F.3 rules out proper co-isometries.

F.5 Continuous alphabets (Oct 23 2026) [definitions; proved; open where marked].

Setting. Finitely many parties. Each $I_k = O_k = G_k$ is a second-countable locally compact abelian group (R, the circle U(1), R^d, or any countable group) with Haar measure λ_k. These are standard Borel spaces and λ_k is σ-finite. Write $G = \prod G_k$ and $\lambda = \otimes \lambda_k$.

Definition F.5.1 (measurable process function). A Borel map $w : G \to G$ is a measurable process function if, for every family of Borel maps $f_k : G_k \to G_k$, the map $o \mapsto f(w(o))$ has exactly one fixed point. (Every argument below uses only translations, constant maps and two-valued maps, which are Borel. So this is equivalent to asking the same for all maps f_k, measurable or not.)

Three candidate definitions of "the closed loop", compared.

- (a) **Point maps.** Restrict the local operations to unitaries that act on points: $V\,\psi(o) = u(o)\,\psi(g(o))$, with $g : O_k \to I_k$ a Borel bijection with Borel inverse that is non-singular (preserves null sets), and $|u|^2 = d(\lambda \circ g)/d\lambda$. By the classical theorem that automorphisms of L^∞ of a standard measure space come from non-singular point maps (not re-proved here), these are exactly the unitaries that carry multiplication operators to multiplication operators. They are the continuous analogue of monomial (phase × permutation) matrices, and include translations, phase multiplications (momentum kicks), reflections, squeezes $\psi(o) \mapsto \sqrt{a}\,\psi(ao)$, and any measurable rearrangement. For them the kernel $V(o,i) = u(o)\,\delta(i - g(o))$ can be evaluated on the graph $i = w(o)+e$, and the countable formula $M(o,e) = \prod_k V_k(o_k, w_k(o)+e_k)$ becomes the operator $(M\psi)(o) = u(o)\,\psi(t(o))$, where $t(o) = g(o) - w(o)$. This is canonical: no choice is made.
- (b) **Direct integrals / disintegration.** One writes $L^2(G) = \int^{\oplus} \mathbb{C}\, d\lambda$ and asks V_k to be decomposable. Decomposable unitaries are multiplication operators, which are the special case g = id of (a). A general V_k does not respect the fibres, so the disintegration does not define M; the useful content of (b) is contained in (a).
- (c) **Limits of discretisations.** Take $M = \lim M_n$ along refining finite partitions, using F.3 for each M_n. Every M_n is unitary, but we found neither a proof that the limit exists nor a proof that it is independent of the partitions for general V_k. Without that, (c) is not yet a definition.
- (d) **Circuits, for causal w.** When w is causally ordered, close the loop as a circuit. Apply the first party's V, then a controlled translation $C = \int^{\oplus} |o\rangle\langle o| \otimes T_{w_k(o)}\, d\lambda(o)$ (a direct integral of unitaries, hence unitary), then the next party, and so on. This works for **all** local unitaries and ancillas.

Choice. We adopt (a) for general measurable process functions and (d) as its extension to all local unitaries when w is causal. They agree where both apply (both reduce to the same composition of point maps), and both reduce to the matrix formula of F.2 when every G_k is countable with counting measure. Option (a) is the largest class on which the defining formula of F.2 makes sense without choices, because it needs the kernel of V_k on a null set (a graph). Option (c) remains a programme.

Lemma F.5.2 [proved; Lean, any cardinality: `PFUL.Continuous.tau_bijective`, `fiber_const`, `tauInv_apply`, `c_indep`]. Let w be a process function on groups G_k (no measure needed) and τ(o) := o − w(o). (i) τ is a bijection. Its inverse sends a source value e to the fixed point for local translations i ↦ i + e_k. (ii) If τ(o) and τ(o') agree at every party other than a, then $w_a(o) = w_a(o')$. (iii) Hence $\tau^{-1}(e)_a = e_a + c_a(e_{-a})$, with an offset c_a that does not depend on e_a. Proof of (ii): otherwise take $f_a(x) = o_a$ if $x = w_a(o)$ and o'_a otherwise, and $f_k(i) = i + \tau(o)_k$ for k ≠ a. Then o and o' are two distinct fixed points.

Theorem F.5.3 [proved, paper; Lean: `PFUL.Continuous.tau_measurePreserving`] (measure preservation, causal or not). For every measurable process function w, τ is a measure-preserving Borel automorphism of (G, λ). Proof, by induction on the number n of parties.

- n = 1: by (ii), w is constant, so τ is a translation.
- n > 1: fix a party a. For each value x of o_a, the function $w_{-a}(x, \cdot)$ is a process function on the other n−1 parties (set $f_a \equiv x$). So by induction τ^x(o') := o' − w_{-a}(x, o') is a measure-preserving bijection of G_{-a}, and τ(o)_{−a} = $\tau^{o_a}(o_{-a})$.
- Let σ(o) = (o_a, τ(o)_{−a}). σ is a Borel bijection, so its inverse is Borel (Lusin–Souslin). σ preserves λ by Tonelli: $\lambda(\sigma^{-1}B) = \int \lambda_{-a}((\tau^{\wedge}x)^{-1}B_x)\, d\lambda_a(x) = \int \lambda_{-a}(B_x)\, d\lambda_a(x) = \lambda(B)$.
- $\tau\circ\sigma^{-1}(x, e') = (x - w_a(\sigma^{-1}(x,e')), e')$. By (ii), w_a is constant on each set {τ(o)_{−a} = e'}. So $\tau\circ\sigma^{-1}(x, e') = (x - c_a(e'), e')$ with c_a Borel, a fibrewise translation, which preserves λ by Tonelli and the translation invariance of Haar measure.
- Hence $\tau = (\tau\circ\sigma^{-1})\circ\sigma$ preserves λ. ∎ *Lean.* `tau_measurePreserving` proves F.5.3 for finitely many parties, each G_k a standard Borel abelian group (MeasurableAdd, MeasurableSub_2) with a σ-finite right-invariant measure μ_k, and λ = ∏ μ_k. Corollaries cover ℝ with Lebesgue measure (`tau_measurePreserving_real`) and the circle ℝ/T℃ (`tau_measurePreserving_circle`). The Lean proof follows the paper: split off party a with `MeasurableEquiv.piEquivPiSubtypeProd`, apply the induction hypothesis to the reduced process inside a skew product (`MeasurePreserving.skew_product`, which is Tonelli), then apply the shear (x, e') ↦ (x − c(e'), e'), whose offset is independent of x by `fiber_const`. The Borel inverse comes from `Measurable.measurableEmbedding` (Lusin–Souslin). This is the measure-theoretic replacement for the countable "expected number of fixed points = 1" identity: (ii) says that the fixed-point count is forced to 1 one party at a time, and Tonelli integrates the parties out in turn.

Corollary F.5.4 [proved, paper] (measure-preserving local bijections; the earlier open case). Let the local operations be measure-preserving Borel bijections f_k (with Borel inverses $g_k = f_k^{-1}$). Then the closed-loop map e ↦ s(e) (the unique fixed point of o ↦ f(w(o)+e)) preserves measure, in the causal and the non-causal case alike. Proof: $s^{-1}(o) = g(o) - w(o) = \tau_{w'}(g(o))$ with $w' = w\circ g^{-1}$. Relabelling outputs locally preserves the process-function property, so w' is a measurable process function. Then apply F.5.3. ∎

Theorem F.5.5 [proved, paper] (unitarity in class (a)). For every measurable process function w and every family of point-map unitaries $V_k \in$ (a) (with or without point-map ancillas; append the ancilla coordinates as extra groups on which w does not act), the closed-loop operator (Mψ)(o) = u(o) ψ(g(o) − w(o)) is unitary on $L^2(G)$. Proof: $\int |u(o)|^2\, |\psi(\tau_{w'}(g(o)))|^2\, d\lambda(o) = \int |\psi(\tau_{w'}(x))|^2\, d\lambda(x) = \|\psi\|^2$. The first step is the change of variables x = g(o), using $|u|^2$ = Jacobian of g; the second is F.5.3. M is surjective, with inverse ψ ↦ (ψ / u)∘t^{-1}. ∎

Lean, Round 11 [PROVED, Lean]. Multiplication by $\sqrt{\rho}$ is an isometry $L^2(\rho\lambda) \to L^2(\lambda)$ for every measurable $\rho \geq 0$, zeros allowed (`PFUL.Continuous.densityIsoₗᵢ`). Hence, for every measurable map g with $g_*(\rho\lambda) = \lambda$ (not assumed injective), $\psi \mapsto \varphi \cdot \sqrt{\rho} \cdot (\psi \circ g)$ is an isometry (`closedLoop_isometry`), and it is unitary when g is a Borel bijection and $\rho \neq 0$ only almost everywhere (`closedLoop_unitary_ae`). In Jacobian form, on a finite-dimensional real space with Haar measure: if g is measurable, injective and differentiable (within s) on a conull Borel set s whose image is conull, then $\psi \mapsto \varphi \cdot \sqrt{|\det g'|} \cdot (\psi \circ g)$ is an isometry, even if det g' vanishes on a set of positive measure (`closedLoop_jacobian_isometry`). If g is moreover a Borel bijection with $\det g' \neq 0$ almost everywhere, it is unitary (`closedLoop_jacobian_unitary_ae`). This covers piecewise-smooth bijections such as the threshold lifts of the Lugano function, which are not differentiable on the cell boundaries. Two remarks [PROVED, paper]. (i) If $\det g' = 0$ on a set Z of positive measure, the isometry is not onto, since every vector in its range vanishes a.e. on Z; so "unitary $\iff$ $\det g' \neq 0$ a.e." in this setting. (ii) The conull-image hypothesis (Lusin's property (N) for the exceptional set) cannot be dropped: an increasing singular homeomorphism of [0,1] (for example the inverse of Minkowski's question-mark function) is differentiable a.e. with derivative 0 a.e. and carries a null set onto a conull set. "Local diffeomorphism" is read here as a bijection that is a diffeomorphism off a null set. A local diffeomorphism that is not injective (a k-fold cover) gives $\|M\psi\|^2 = \Sigma$ over preimages, so M is not an isometry; such maps are not point-map unitaries and are outside (a). *Lean (translation class with phases).* `PFUL.Continuous.closedLoop_unitary`: for every measurable process function w and every measurable φ with $|\varphi| = 1$, there is a linear isometric equivalence U of $L^2(\prod G_k, \prod \mu_k)$ with $(U\psi)(o) = \varphi(o)\psi(o - w(o))$ almost everywhere. This is the case g = id, u = φ (pure translations decorated with phases). General point maps g with a Jacobian factor are not in Lean; they reduce to this case by the change of variables x = g(o). Thus the open lift U is unitary (F.1, measure-preserving), and every induced map is unitary for point-map local operations, for every measurable process function.

Theorem F.5.6 [proved, paper] (causal w, all local unitaries). With definition (d), M is a product of unitaries, so it is unitary for all local unitaries and ancillas.

Open (non-causal w, general local unitaries). For a non-causal measurable process function (for example the Lugano function lifted to $\mathbb{R}^3$ by threshold sets, which is a measurable process function with piecewise-translation τ) and local unitaries outside class (a), such as a Fourier transform, we have no canonical definition of the closed loop in general (Round 14: Proposition F.5.9 gives one, with convergent discretisations, whenever w depends on the outputs only through finitely many cells, which includes this example; Round 16: Proposition F.5.10 extends this to countably many cells; Round 17: Proposition F.5.11 gives a canonical isometric limit for uniform limits of these). Here is why. A non-causal w admits no circuit (d): circuits are causally ordered, and the Lugano statistics violate a causal inequality. And the formula of (a) needs the kernel of V_k on a null set. *Conjecture F.5.7:* for every measurable process function and all local unitaries, the discretisations of (c) converge strongly to a unitary that is independent of the partitions and extends (a) and (d). Supporting evidence (heuristic, not a proof): every discretisation is unitary (F.3), and the limit exists in the two classes where we can compute it, (a) and (d).

Proposition F.5.8 [PROVED, paper] (F.5.7 for causal w). Fix countable partitions P_n of each G_k into cells (for $\mathbb{R}$, the grids $h_n\mathbb{Z} + [0, h_n)$ with $h_n \to 0$ along a refining sequence), let E_n be the conditional expectation onto the step functions of P_n (so $E_n \to 1$ strongly), and let $V_{k,n}$ be unitaries of E_n L^2 with $V_{k,n}E_n \to V_k$ and $V_{k,n}E_n \to V_k$ strongly. Let w_n be cell-valued process functions, causal in the same order as w, with $w_n \to w$ λ-a.e. Then the discretised closed loops M_n E_n (F.3) converge strongly to the circuit closed loop M_(d) of (d). In particular the limit exists and does not depend on the partitions or on the approximating $V_{k,n}$, w_n. Proof. For causal w_n the matrix formula of F.2 equals the circuit product (apply $V_{1,n}$, then the controlled translation C_n by $w_{1,n}$, then $V_{2,n}$,

…); this is the countable case of F.5.6. A product of a fixed number of uniformly bounded, strongly convergent sequences converges strongly to the product of the limits. So it suffices that $C_n \to C$ strongly, where $(C\psi)(o, x) = \psi(o, x - w_k(o))$. For $\psi \in C_c$, $\|(C_n - C)\psi\|^2 = \int \|T_{w_\{k,n}(o)\}\psi(o,\cdot) - T_{w_k(o)}\psi(o,\cdot)\|^2 \, d\lambda(o)$. The integrand tends to 0 pointwise by strong continuity of translation and is bounded by $4\|\psi(o,\cdot)\|^2$, so dominated convergence applies. C_c is dense and $\|C_n\| = 1$, so $C_n \to C$ strongly. ∎ *Consequence.* F.5.7 holds for causal w with any discretisation scheme of this kind, and the limit equals (d). For a Fourier-type V_k (the Fourier transform on $L^2(\mathbb{R})$, or on a compact group) the proposition applies as soon as unitary grid approximants $V_{k,n}$ with $V_{k,n}E_n \to V_k$ and $V_{k,n}E_n \to V_k$ strongly are fixed. We did not verify that a particular scheme (for example centred, rescaled discrete Fourier transforms) has this property, so for Fourier-type local unitaries with causal w the conclusion is conditional on that approximation step [PROVED modulo the approximation hypothesis; not in Lean]. For general non-causal w, F.5.7 remains **OPEN**; Proposition F.5.9 below settles the finitely controlled case, and F.5.10 (Round 16) the countably controlled case, and F.5.11 (Round 17) gives a canonical isometric limit for uniform limits of countably controlled w; F.5.12 (Round 18) proves unitarity for activation-controlled w. The argument above fails at its first step: a non-causal w_n has no circuit form, so M_n is not a fixed-length product of strongly convergent factors, and the F.3 unitaries M_n are not known to have uniformly convergent matrix entries. We found no counterexample either.

Proposition F.5.9 [PROVED, paper; numerical sanity check `embed/f59_check.py`*] (F.5.7 for finitely controlled w, causal or not).* Call a measurable process function w *finitely controlled* if each G_k has a finite Borel partition into nonempty cells $Q_k = \{Q_{k,c} : c \in C_k\}$ such that every $w_k(o)$ depends only on the cell labels $c(o) = (c_1(o_1), \ldots, c_n(o_n))$; write $w_k(o) = \omega_k(c(o))$, which takes finitely many values. The Lugano function lifted to $\mathbb{R}^3$ by threshold sets (F.5.7) is finitely controlled. For every family of unitaries V_k on $L^2(G_k) \otimes K_k$ (ancillas allowed, Fourier transforms included) put $M := \Sigma_\{c \in C\} \otimes_k P_{k,c_k} V_k S_{\omega_k(c)}$, where $P_{k,c}$ multiplies by the indicator of $Q_{k,c}$ on the output and $(S_a \psi)(i) = \psi(i - a)$ translates the input. Then: (i) M is unitary. (ii) M is canonical and extends the earlier definitions. On countable alphabets its kernel is the F.2 formula $\prod_k V_k(o_k, w_k(o) + e_k)$, because exactly one c (namely c(o)) contributes at each o. For point maps it is $(M\psi)(o) = u(o)\, \psi(g(o) - w(o))$, definition (a). For causal w it is the circuit (d), since each controlled translation of (d) is $\Sigma_c P_c \otimes S$. (iii) Discretisations converge. Take grids that refine every Q_k and are invariant under the finitely many translations $\omega_k(c)$, and unitary approximants with $V_{k,n}E_n \to V_k$ and $V_{k,n}E_n \to V_k$ strongly (the hypothesis of F.5.8). Then the F.3 matrices M_n have the same finite-sum form, and $M_n E_n \to M$ strongly, because M_n is a finite sum of products of uniformly bounded, strongly convergent sequences. So for these schemes the limit exists, is unitary, and does not depend on the scheme. *Proof of (i).*

- *Rows (M M* = 1).* $M M^* = \Sigma_\{c,c'\} \otimes_k P_{k,c_k} V_k S_{\omega_k(c)} S_{\omega_k(c')}^* V_k^* P_{k,c'_k}$. Let $c \neq c'$. Choose points $o \in c$ and $o' \in c'$ with $o_k = o'_k$ whenever $c_k = c'_k$. The exclusivity lemma (F.2) applied to w gives a party k with $o_k \neq o'_k$, so $c_k \neq c'_k$, and with $\omega_k(c) = \omega_k(c')$. That factor is then $P_{k,c_k} P_{k,c'_k} = 0$. The diagonal terms sum to $\otimes_k \Sigma_c P_{k,c} = 1$.
- *Columns (M* M = 1).* $M^* M = \Sigma_c \otimes_k F_k(\omega_k(c), c_k)$, where $F_k(a, c) := S_a^* V_k^* P_{k,c} V_k S_a$. For each a this is a projection-valued measure on C_k, but the $F_k(a, \cdot)$ for different a need not commute, so F.3's probabilistic argument does not apply directly. Instead, write each family as an operator-weighted mixture of deterministic functions. Let A_k be the finite range of ω_k, with $m = |A_k|$ and $r = |C_k|$, and for each

function f : $A_k \to C_k$ put $G_{k,f} := r^{1-m} \Sigma_{a \in A_k} F_k(a, f(a)) - (m-1)\, r^{-m} \cdot 1$. A direct count gives $F_k(a, c) = \Sigma_{f : f(a) = c} G_{k,f}$ and $\Sigma_f G_{k,f} = 1$. These G need not be positive; only linearity is used. Then $M^* M = \Sigma_{f_1,\ldots,f_n} (\otimes_k G_{k,f_k}) \cdot \#\{c \in C : c_k = f_k(\omega_k(c)) \text{ for all } k\}$. The cell map ω inherits the fixed-point property from w: given f_k, choose representatives $r_k(c) \in Q_{k,c}$ and Borel maps $F_k(i) = r_k(f_k(i))$ for $i \in A_k$ (arbitrary elsewhere). Then $c \mapsto r(c)$ is a bijection from the fixed points of $c \mapsto f(\omega(c))$ onto those of $o \mapsto F(w(o))$, and there is exactly one of the latter. So every count equals 1, and $M^* M = \otimes_k \Sigma_f G_{k,f} = 1$. ∎

Remarks. The column identity $\Sigma_c \otimes_k F_k(\omega_k(c), c_k) = 1$ is the operator form of the fact that a classical process function is a valid process for arbitrary local instruments. That fact is standard for finite dimensions (Araújo, Feix, Navascués, Brukner 2017, arXiv:1611.08535; Section 2 and Appendix A here). What is new here is the elementary decomposition argument, which needs no dimension count and so applies with infinite-dimensional local spaces. The check script verifies the following [NUMERICAL]: the lifted Lugano function on Z_4^3 (cells are halves, translations by 2) has a unique fixed point for 3,000 random local maps; M equals the F.2 matrix exactly and is unitary to 2.1e-15 with DFT ⊗ Haar and with Haar local unitaries (ancilla dimension 2); and the column identity holds to 2.2e-16 for random non-commuting projective families (commutator norms about 0.35). *Scope.* F.5.9 settles F.5.7 for every finitely controlled w, causal or not, including the threshold-lifted Lugano function with Fourier-type local unitaries, under the same approximation hypothesis as F.5.8 and with grids adapted to the cells. **Still OPEN:** non-causal w whose dependence on the outputs is not finitely controlled (for example, a non-causal w that depends continuously on the outputs), and discretisation schemes whose grids do not refine the cells. For these, M_n is not a fixed finite sum, and we have no uniform control. *(Round 16: the countably controlled case is settled by F.5.10 below; the remaining open case is w that is not countably controlled.)*

Proposition F.5.10 [PROVED, paper; numerical sanity check `embed/f510_check.py`] (Round 16: F.5.7 for countably controlled w, causal or not). Call a measurable process function w *countably controlled* if each G_k has a countable Borel partition $Q_k = \{Q_{k,c} : c \in C_k\}$ into nonempty cells such that every $w_k(o)$ depends only on the cell labels c(o); write $w_k(o) = \omega_k(c(o))$. Finitely controlled (F.5.9) is the special case of finite C_k, but now ω_k may take infinitely many values. For every family of unitaries V_k on $L^2(G_k) \otimes K_k$ (ancillas allowed, Fourier transforms included) put $T_c := \otimes_k P_{k,c_k} V_k S_{\omega_k(c)}$ for $c \in C = \prod C_k$. Then: (i) The series $M := \Sigma_c T_c$ converges strongly, and M is unitary. (ii) M is canonical and extends (a), (d), F.2 and F.5.9, for the same reasons as F.5.9 (ii): exactly one c contributes at each o. (iii) Discretisations converge. Take grids that refine every cell $Q_{k,c}$ and are invariant under every translation $\omega_k(c)$, and unitary approximants with $V_{k,n} E_n \to V_k$ and $V_{k,n} E_n \to V_k$ strongly (the hypothesis of F.5.8). Then $M_n E_n \to M$ strongly. *Proof.* Write $P_c := \otimes_k P_{k,c_k}$. These are orthogonal projections with $\Sigma_c P_c = 1$ strongly (a product of countable projection-valued measures).

- *M is a well-defined co-isometry.* For $c \neq c'$, the exclusivity lemma (F.2; it only uses representatives $o \in c$, $o' \in c'$, so countably many cells are fine) gives a k with $c_k \neq c'_k$ and $\omega_k(c) = \omega_k(c')$, so $T_c T_{c'}^* = 0$. Hence the vectors $T_c^* x$ are mutually orthogonal, and $\|T_c^* x\| = \|P_c x\|$ because S and V are unitary. So $\Sigma_c T_c^*$ converges strongly to an isometry; call it M^*, and let M be its adjoint ($\|M\| = 1$, $M M^* = 1$). Since $P_c T_{c'}^* = 0$ for $c' \neq c$, one gets $P_c M = T_c$, so $M = \Sigma_c P_c M = \Sigma_c T_c$ strongly. This is (i)'s convergence claim.
- *M*M = 1 (columns), without any decomposition into deterministic functions.* $M^* M = M^*(\Sigma_c P_c) M = \Sigma_c T_c^* T_c = \Sigma_c \otimes_k F_k(\omega_k(c), c_k)$ strongly, with $F_k(a, c) = S_a^* V_k^* P_{k,c} V_k S_a$ as in F.5.9. Take a product unit vector $\varphi = \otimes_k \varphi_k$. For each k and each a, $p_k(c \mid a) := \langle \varphi_k, F_k(a, c)\, \varphi_k \rangle$ is a probability distribution on the

countable set C_k, because $\Sigma_c F_k(a, c) = 1$ strongly. So $\langle \varphi, M M \varphi \rangle = \Sigma_c \prod_k p_k(c_k \mid \omega_k(c))$. *Draw independent random functions $f_k : A_k \to C_k$ with $f_k(a) \sim p_k(\cdot \mid a)$, independently over k and a (a countable product of probability measures). By independence, $\prod_k p_k(c_k \mid \omega_k(c)) = Pr[c_k = f_k(\omega_k(c))$ for all k], so by Tonelli $\langle \varphi, M M \varphi \rangle = E[\#\{c : c = f(\omega(c))\}]$.* As in F.5.9, choosing representatives $r_k(c) \in Q_{k,c}$ turns the fixed points of $c \mapsto f(\omega(c))$ bijectively into the fixed points of $o \mapsto F(w(o))$ with $F_k = r_k \circ f_k$ (Borel, since A_k is countable), and there is exactly one. So $\langle \varphi, (M M - 1)\varphi \rangle = 0$ *for every product vector. The form $(\varphi_1, \ldots, \varphi_n; \chi_1, \ldots, \chi_n) \mapsto \langle \otimes \varphi_k, (M M - 1) \otimes \chi_k \rangle$* is sesquilinear in each pair (φ_k, χ_k) separately, so polarising one pair at a time shows that it vanishes identically. Product vectors span a dense subspace, and $M M - 1$ *is bounded, so* $M M = 1$. ∎(i)

- *(iii).* Grids that refine the cells and are invariant under the translations give $M_n E_n = \Sigma_c P_c \otimes_k V_{k,n} S_{\omega_k(c)} E_n$. Applied with the discretised data, (i) shows that M_n is unitary on $E_n L^2$, so $\|M_n E_n \psi\| = \|E_n \psi\| \to \|\psi\| = \|M\psi\|$. Weak convergence: for χ, ψ and any finite $F \subset C$, $\langle \chi, M_n E_n \psi \rangle = \Sigma_{c \in F} \langle P_c \chi, \otimes V_{k,n} S_{\omega_k(c)} E_n \psi \rangle + \langle (1 - P_F) \chi, M_n E_n \psi \rangle$, with $P_F = \Sigma_{c \in F} P_c$. Each of the finitely many terms converges to its limit with V_k, and the tail is at most $\|(1 - P_F)\chi\| \|\psi\|$ uniformly in n, and likewise for M. So $\langle \chi, M_n E_n \psi \rangle \to \langle \chi, M\psi \rangle$. Weak convergence plus convergence of the norms gives strong convergence. ∎ *Remarks.* (1) The column argument is simpler than the one in F.5.9 and replaces it: non-commutativity of the $F_k(a, \cdot)$ is harmless because only expectations in product states are needed, and those are classical stochastic local maps. This is the same principle behind the finite-dimensional fact that a classical process function is a valid process for arbitrary local instruments (Araújo, Feix, Navascués, Brukner 2017, arXiv:1611.08535) [CITED]. The new points are the countable cell structure, the strong-convergence bookkeeping and the polarisation step. (2) *A non-causal example that is countably controlled but not finitely controlled.* [PROVED] On $\mathbb{Z}^3$ put $\omega_A(c) = [c_B \text{ even}, c_C \text{ odd}] \cdot (2c_B + 1)$, $\omega_B(c) = [c_C \text{ even}, c_A \text{ odd}] \cdot (2c_C + 1)$, $\omega_C(c) = [c_A \text{ even}, c_B \text{ odd}] \cdot (2c_A + 1)$. This is Lugano on parities, with unbounded odd translation amounts. It is a process function on $\mathbb{Z}^3$: for local maps f_k put $u_k = f_k(0)$. A fixed point either has all inputs 0, which needs Lugano(parity(u)) = 0, or has exactly one non-zero input, say A's. That needs u_B even and u_C odd, and then $c_A = f_A(2u_B + 1)$ is forced, and the other two Lugano conditions hold automatically. Exactly one of these four parity conditions holds for every parity triple, so the fixed point is unique. It is non-causal (its parity reduction is Lugano). Then $w(o) := \omega(\lfloor o \rfloor)$ on $\mathbb{R}^3$ is a measurable process function, because the fixed points of $o \mapsto f(w(o))$ correspond bijectively to those of $c \mapsto \lfloor f(\omega(c)) \rfloor$. It is countably controlled by the unit intervals, and it is not finitely controlled because w_A takes infinitely many values. Grids $h_n\mathbb{Z}$ with $1/h_n \in \mathbb{N}$ satisfy (iii). `f510_check.py` [NUMERICAL] confirms exactly one fixed point for 3,000 random local maps on the window $[-40, 40]^3$: 719/782/746/753 fixed points of the types "all inputs 0" / A / B / C. *Scope.* F.5.7 now holds for every countably controlled w, causal or not, under the approximation hypothesis of F.5.8 and with grids adapted to the cells and translations. **Still OPEN:** non-causal w that is not countably controlled. Examples are w that depends continuously and non-trivially on the outputs, or that takes uncountably many values, and schemes whose grids do not refine the cells. For these the series form is not available.

Proposition F.5.11 [PROVED, paper] (Round 17: uniform limits of countably controlled process functions; canonical isometric closed loop). Let every $G_k = \mathbb{R}^{d_k}$, and let w be a measurable process function that is a uniform limit of countably controlled process functions w_n: $\|w_n - w\|_\infty \to 0$. Here each w_n has its own countable cells, and the sup is over all outputs and coordinates. For local unitaries V_k on $L^2(G_k) \otimes K_k$, let M_n be the closed loop of

w_n (F.5.10). Then: (i) M_n converges strongly to an isometry M. (ii) M does not depend on the approximating sequence. Interleave two sequences to see this. M equals the F.5.10 closed loop when w is itself countably controlled. (iii) M is unitary if and only if $M_n^* \to M^*$ strongly. Equivalently, the vectors $M_n\varphi$ *are tight in momentum for every* φ*, i.e.* $\|(1 - \Pi_K) M_n\varphi\| \to 0$ as $K \to \infty$ uniformly in n, where Π_K is the projection onto all momenta in $[-K, K]$. *Proof.* (i) Fix n, m and take the common refinement of their cells. This is again countable, and it does not change M_n or M_m. On a cell c, write $a_c = \omega_n(c)$, $b_c = \omega_m(c)$ and $\Delta_c = a_c - b_c$, so $|\Delta_c| \le \varepsilon := \|w_n - w_m\|_\infty$. Let ψ be band-limited, with all momenta in $[-K, K]$. Such vectors are dense in $L^2(\prod G_k) \otimes K$, and on them $S_\Delta = \exp(-\Delta\cdot\nabla) = \sum_\alpha (-\Delta)^\alpha \partial^\alpha/\alpha!$ converges in norm, with $\|\partial^\alpha \psi\| \le K^{|\alpha|}\|\psi\|$. Write $\mathrm{mult}(\Delta^\alpha)$ for multiplication by $\Delta(o)^\alpha$ on the output side; since P_c commutes with it, $P_c\,\mathrm{mult}(\Delta^\alpha) = \Delta_c^\alpha P_c$. Projecting onto each cell then gives $(M_n - M_m)\psi = \sum_c P_c V S_{b_c}(S_{\Delta_c} - 1)\psi = \sum_{\alpha\neq 0} (1/\alpha!)\,\mathrm{mult}((-\Delta)^\alpha)\, M_m\, \partial^\alpha \psi$. So $\|(M_n - M_m)\psi\| \le \sum_{\alpha\neq 0} \varepsilon^{|\alpha|} K^{|\alpha|}/\alpha!\, \|\psi\| = (e^{N\varepsilon K} - 1)\|\psi\|$, with $N = \sum_k d_k$. Hence $(M_n\,\psi)$ is Cauchy on a dense set. The M_n are unitary, so they converge strongly to a contraction M, and since $\|M\psi\| = \lim \|M_n\psi\| = \|\psi\|$, M is an isometry. (iii) If M is unitary, then $\|M_n\varphi - M\varphi\| = \|\varphi - M_n\, M\varphi\| \to \|\varphi - M\, M\varphi\| = 0$. Conversely, if $M_n^* \to M^*$ strongly, then $M\,M^* = \lim M_n\, M_n^* = 1$. For the tightness criterion, write $\xi_c := S_{-b_c} V^*\, P_c\, \varphi$. By F.5.10 these vectors are mutually orthogonal. The same expansion gives $M_n\varphi - M_m\varphi = \sum_c (S_{-\Delta_c} - 1)\,\xi_c$. Its Π_K-part equals $\sum_{\alpha\neq 0} (1/\alpha!)\,\partial^\alpha\, \Pi_K\, M_m^*\, \mathrm{mult}(\Delta^\alpha)\,\varphi$ (up to signs), with norm at most $(e^{N\varepsilon K} - 1)\|\varphi\|$. Its $(1 - \Pi_K)$-part equals $(1 - \Pi_K)(M_n^* - M_m^*)\varphi$. ∎ *Example [PROVED].* For any measurable $h_k : \mathbb{R}^2 \to \mathbb{R}$, put $w_A(o) = [\lfloor o_B \rfloor \text{ even}, \lfloor o_C \rfloor \text{ odd}]\cdot h_A(o_B, o_C)$, and similarly for B and C with the cyclic Lugano pattern. This is a non-causal process function. The proof of F.5.10 Remark (2) applies verbatim: the activation conditions are exclusive, and the amounts h_k play no role in uniqueness. For uniformly continuous, non-constant h_k it is not countably controlled (w_A takes uncountably many values), and it is the uniform limit of the countably controlled process functions obtained by rounding the arguments of h_k to the dyadic grid $2^{-n}\mathbb{Z}$. So F.5.11 gives a canonical isometric closed loop for every local unitary. *Scope.* Existence of a canonical isometric limit is PROVED for uniform limits of countably controlled w. **Unitarity of the limit in general, and w that are not such uniform limits (for example, with discontinuous dependence on the outputs on a non-null set that no countable partition captures), remain OPEN.** The obstruction is now localised: an approximating sequence of unitaries whose adjoints leak momentum to infinity. We know of no example where this happens. *Literature.* Continuous-variable process matrices were introduced by Giacomini, Castro-Ruiz and Brukner (New J. Phys. 18, 113026, 2016); we know of no prior treatment of closed loops for continuous-variable process functions with non-point-map local unitaries. The band-limited Taylor estimate is standard (entire vectors for the momentum operator, Nelson's analytic-vector theorem).

Proposition F.5.12 [PROVED, paper] (Round 18: activation-controlled process functions with arbitrary measurable amounts; unitary closed loop, F.5.7 holds). Let every $G_k = \mathbb{R}^{d_k}$. Call a measurable process function w *activation-controlled* if three conditions hold.

- *Regions.* The output space is partitioned into countably many Borel product regions $R = \prod_j R_j$, and each region has at most one *active* party $\kappa = \kappa(R)$.
- *Amounts.* The active party's own output is unconstrained, $R_\kappa = G_\kappa$. Every inactive party $j \neq \kappa$ gets a constant amount $w_j(o) = \omega_j(R)$ on R. The active party gets $w_\kappa(o) = h_R(o_{-\kappa})$, where h_R is an arbitrary measurable function of the other outputs.
- *Hypotheses.* (E) For $R \neq R'$ there is a party j that is inactive in both, with $R_j \cap R'_j = \varnothing$ and $\omega_j(R) = \omega_j(R')$. (S) The *skeleton* w^0, obtained by setting every h_R to 0, is a process function. It is countably

controlled, with cells given by the common refinement of the R_j.

For local unitaries V_k on $L^2(G_k) \otimes K_k$, let D_R be the decomposable operator on $L^2(G_{-\kappa}; L^2(G_{-\kappa}) \otimes K)$ with fibres $D_R(o_{-\kappa}) = V_{-\kappa}\, S_{h_R(o_{\{-\kappa})}}$, a measurable field of unitaries (the identity if R has no active party). Put $U_R := D_R\, (\otimes_{\{j \neq \kappa\}} V_j\, S_{\omega_{j(R)}})$, and let Π_R be multiplication by 1_R. Then: (i) $M := \Sigma_R\, \Pi_R\, U_R$ converges strongly and is unitary. (ii) M is canonical. If $h_R^{(n)} \to h_R$ almost everywhere for every R, then $M_n \to M$ strongly. In particular, M is the strong limit of F.5.10 closed loops along step-function approximants of the h_R on dyadic boxes, which are countably controlled. M equals the F.5.10 loop when w is countably controlled, and the F.5.11 limit when the h_R are uniformly continuous.

Proof.

- *Rows.* D_R commutes with every multiplication operator in $o_{-\kappa}$, and U_R is unitary, so $\Pi_R\, U_R\, U_R^*\, \Pi_R = \Pi_R$.
  - For $R \neq R'$, take j from (E). On factor j, the middle operator $U_R\, U_{R'}^*$ is $V_j\, S_{\omega_j}\, S_{\omega_j}^*\, V_j^* = 1$.
  - D_R and $D_{R'}$ commute with multiplication by functions of o_j, because j is inactive in both.
  - Hence $\Pi_R\, U_R\, U_{R'}^*\, \Pi_{\{R'\}} = \Pi_R\, 1_{\{R'_j\}}(o_j)\, U_R\, U_{R'}^*\, \Pi_{\{R'\}} = 0$, because $R_j \cap R'_j = \varnothing$.
  - So the vectors $\Pi_R\, U_R\, \psi$, and likewise the ranges $U_R^*\, \Pi_R$, are mutually orthogonal, the series converges strongly, and $M\, M^* = \Sigma_R\, \Pi_R = 1$.
- *Columns.* $M^*M = \Sigma_R\, U_R^*\, \Pi_R\, U_R$, because the Π_R are disjoint.
  - Π_R depends only on $o_{-\kappa}$, because $R_\kappa = G_\kappa$, so it commutes with D_R. Hence $U_R^*\, \Pi_R\, U_R = (\otimes_{\{j \neq \kappa\}} V_j\, S_{\omega_j})^*\, \Pi_R\, (\otimes_{\{j \neq \kappa\}} V_j\, S_{\omega_j})$: **the amounts h_R drop out.**
  - The same identity holds for the skeleton, whose closed loop M^0 is unitary by F.5.10 under (S). So $M^*M = M^{0*}M^0 = 1$.
- *(ii).* Fibrewise, $S_{\{h^{(n)}(o)\}} \to S_{h(o)}$ strongly for almost every o. Dominated convergence in the direct integral gives $D_R^{(n)} \to D_R$ strongly. The series over R is uniformly controlled by the orthogonality in (i).
  - Step functions on dyadic boxes in $G_{-\kappa}$ approximate any measurable h_R almost everywhere, along a subsequence of an L^1_loc approximation of $\arctan h_R$. They keep the activation structure, so they are countably controlled and satisfy (E) and (S).
  - For uniformly continuous h_R, the dyadic roundings of F.5.11's example form one admissible sequence for F.5.11, so the F.5.11 limit is this M. ∎

Example [PROVED]. F.5.11's example qualifies for **any** measurable amounts h_k. The regions are the six activated parity patterns $(\cdot,0,1)$, $(1,\cdot,0)$, $(0,1,\cdot)$ and the two inactive cells (0,0,0) and (1,1,1). Condition (E) is the parity-level Lugano exclusivity: any two distinct patterns differ at a party inactive in both, and every inactive amount is 0. Condition (S) holds trivially, because the skeleton is $w^0 \equiv 0$. The column identity reduces to the polynomial identity $\tilde{e}_B\, \tilde{o}_C + \tilde{e}_C\, \tilde{o}_A + \tilde{e}_A\, \tilde{o}_B + \tilde{e}_A\, \tilde{e}_B\, \tilde{e}_C + \tilde{o}_A\, \tilde{o}_B\, \tilde{o}_C = 1$ in the commuting projections $\tilde{e}_j = V_j^*\, 1_{\{\lfloor o_j \rfloor \text{ even}\}}\, V_j$ and $\tilde{o}_j = 1 - \tilde{e}_j$. So the momentum-tightness condition of F.5.11 (iii) holds for this example, and its closed loop is unitary for every family of local unitaries, Fourier transforms included.

Scope. F.5.7 holds for every activation-controlled w, including amounts that are discontinuous everywhere and so are not uniform limits of countably controlled functions. **Still OPEN:**

- process functions in which, on some region, two or more parties' amounts vary with the outputs;

- process functions in which the active party's own output is constrained ($R_\kappa \neq G_\kappa$). There the amounts do not drop out of the column side.
- In particular, unitarity for a general uniform limit (F.5.11), e.g. a Lipschitz w, remains OPEN.

Literature. Direct integrals and decomposable operators: Dixmier, *Les algèbres d'opérateurs dans l'espace hilbertien* (1957); Reed–Simon IV, XIII.16. The finite-dimensional analogue, a classical process function controlling quantum operations coherently, is in Baumeler, Costa, Ralph, Wolf and Zych (Class. Quantum Grav. 36, 224002, 2019) and Araújo et al. (Quantum 1, 10, 2017).

Status. Proved (paper and Lean, finite and countable), for countable alphabets with a group structure on the inputs and finitely many parties: the lift is unitary under all local unitaries with ancillas (F.1-F.3). Continuous alphabets (F.5): definitions F.5.1 and (a)/(d) adopted. Measure preservation of the closed loop for every measurable process function, causal or not (F.5.3), and the measure-preserving-bijection case (F.5.4), are proved in the paper. Unitarity holds for point-map local unitaries (F.5.5), and for all local unitaries when w is causal (F.5.6). The combinatorial core (F.5.2) is machine-checked. F.5.3 is now machine-checked (`PFUL.Continuous.tau_measurePreserving`), as is F.5.5 for translations with phases (`closedLoop_unitary`). F.5.5 for general point maps is machine-checked (Round 10: `closedLoop_general_unitary`, `closedLoop_jacobian_unitary`; Round 11: a.e.-smooth bijections with a.e.-nonzero Jacobian, `closedLoop_jacobian_unitary_ae`, and an isometry with degenerate Jacobians, `closedLoop_jacobian_isometry`). Conjecture F.5.7 holds for causal w (Proposition F.5.8, paper), and for finitely controlled w, causal or not, including the threshold-lifted Lugano function (Proposition F.5.9, paper; Round 14), and more generally for countably controlled w (Proposition F.5.10, paper; Round 16). For uniform limits of countably controlled w on Euclidean output spaces the closed loop is a canonical strong limit and an isometry (Proposition F.5.11, paper; Round 17). For activation-controlled w, with one active party per region and arbitrary measurable amounts (including the continuous-amount Lugano family), it is unitary (Proposition F.5.12, paper; Round 18). Open: unitarity for general uniform limits (e.g. Lipschitz w with several output-dependent amounts per region), and w outside both classes, with general local unitaries such as a Fourier transform (Conjecture F.5.7 in that case).

Appendix G. Two parties: purifiable = PF blend, trivially (Oct 21 2026)

Theorem G.1 [proved]. Let $p(a,b|x,y)$ be a valid classical process on two parties A, B, with finite alphabets of any sizes: a, b are the inputs and x, y the outputs. Valid means $p \geq 0$ and $\sum_{a,b} p(a,b|f(a),g(b)) = 1$ for all functions f, g. Then p is a convex combination of deterministic causally ordered process functions. Each of these has one of two forms: a = a0 constant and b = h(x), or b = b0 constant and a = h(y).

Corollary G.2 [proved]. For two parties, the former purification conjecture of Section 9 holds (in contrast with three parties, H.12.1). Both sides are true for every valid classical process. Every such process is a mixture of process functions (G.1), so it is purifiable (C.1). Also, every bipartite process function is causally ordered: a 0/1 point that is a convex combination of 0/1 points equals one of them. So the two-party case says nothing about the open multipartite question. The separation between "classically consistent" and "reversibly realisable" starts at three parties, where E_{ex1} lives.

Proof of G.1. Write every function of (a,b,x,y) as a sum of components p_S, one for each subset S of {a,b,x,y}. The component p_S depends only on the variables in S, and its sum over any one variable in S is zero. (These are the products of "average" and "traceless" projections.)

Step 1 (linear constraints). Validity for deterministic f, g gives the same normalisation for stochastic local maps sigma(x|a), tau(y|b), by linearity. The quantity sum p sigma tau is affine in each argument, so its derivatives along traceless directions vanish.

- Second order: sum p delta(x|a) eps(y|b) = 0 whenever $\sum_x$ delta = 0 and $\sum_y$ eps = 0. Such products span all functions that are traceless in x and in y, so $p_S = 0$ whenever S contains both x and y.
- First order with tau uniform: sum p delta(x|a) = 0 for every delta with $\sum_x$ delta = 0. Summing over b and y keeps only S with b, y not in S, so $p_x = p_{ax} = 0$. Symmetrically, $p_y = p_{by} = 0$.

What survives is p = c + s + t, with c = p_∅ + p_a + p_b + p_{ab}, s = p_{bx} + p_{abx} and t = p_{ay} + p_{aby}. Here c(a,b) is the average of p over (x,y), so it is a probability distribution. Also $\sum_x$ s = $\sum_b$ s = 0 and $\sum_y$ t = $\sum_a$ t = 0. This is the diagonal case of the Oreshkov-Costa-Brukner term structure.

Step 2 (positive split). Let m1(a,b) = -min_x s(a,b,x) and m2(a,b) = -min_y t(a,b,y). Both are ≥ 0 because s and t have mean zero. Evaluating p ≥ 0 at the minimising x and y gives c ≥ m1 + m2. Choose c1 ≥ m1 and c2 ≥ m2 with c1 + c2 = c, and put U = c1 + s and V = c2 + t. Then U, V ≥ 0 and p = U + V. Since $\sum_b$ s = 0, U(a,b|x) has total mass q = sum c1 for every x, and its A-marginal $\sum_b$ c1(a,b) does not depend on x. So U/q = r(a) r(b|a,x) is a classical A-before-B process. By the same argument, V/(1-q) is a B-before-A process.

Step 3 (deterministic decomposition). r(a) r(b|a,x) = $\sum_{a0}$ r(a0) $\text{delta}_{a,a0}$ $\sum_h$ prod_x r(h(x)|a0,x) $\text{delta}_{b,h(x)}$, where h ranges over the functions X → B. Each term is a = a0, b = h(x). Under any interventions it has exactly one consistent history, a0, f(a0), h(f(a0)), so it is a process function. The same holds for the B-before-A part. ∎

Literature [cited].

- Oreshkov, Costa and Brukner (Nat. Commun. 3, 1092 (2012), Supplementary) prove that the bipartite process matrices diagonal in fixed bases are causally separable. Their proof is the quantum version of Step 2.
- Baumann and Brukner (arXiv:1601.06620) extend this to inputs diagonal and outputs arbitrary. They note that it fails for three parties (Baumeler, Feix and Wolf, PRA 90, 042106 (2014)).
- For two binary parties, Baumeler and Wolf (2016) report that all 12 vertices of the classical polytope are deterministic (Appendix C). G.1 is the general-alphabet version.

G.1 itself is therefore known in substance. Combining it with C.1 to settle the two-party purification statement is immediate. I did not find a source that states the purification version explicitly. Steps 1-3 are included so that the note is self-contained. Suggested wording for Section 9: "For two parties the conjecture holds, because every bipartite classical process is causally separable [OCB 2012, Suppl.; see also Baumann-Brukner 2016] and hence a mixture of causally ordered process functions (Appendix G)."

Numerical check [numerical]. The script is code/stochastic/bipartite/vertices.py. For each alphabet size it samples LP vertices of the bipartite classical-process polytope (300 random objectives) and checks that each vertex is 0/1. It also checks 50 averages of 4 random vertices for membership in conv(PF) by LP.

($\lvert A_{in}\rvert$,$\lvert A_{out}\rvert$,$\lvert B_{in}\rvert$,$\lvert B_{out}\rvert$)	process functions	distinct vertices found	non-deterministic	outside conv(PF)
(2,2,2,2)	12	12	0	0/50
(3,2,2,2)	24	24	0	0/50
(2,3,2,2)	20	20	0	0/50
(3,3,2,2)	36	36	0	0/50
(2,2,3,3)	36	36	0	0/50
(3,2,3,2)	45	45	0	0/50

For larger alphabets, code/stochastic/bipartite/vertices_only.py does the vertex test alone (enumerating process functions is too costly there):

($|A_{in}|$,$|A_{out}|$,$|B_{in}|$,$|B_{out}|$)	LPs	distinct vertices found	non-deterministic
(3,3,3,3)	500	146	0
(4,2,4,2)	300	100	0
(2,4,2,4)	300	60	0

In every case the vertices found are exactly the process functions, as G.1 predicts. The (2,2,2,2) count of 12 matches Baumeler-Wolf.

Appendix H. Three parties: structural reductions, a determinantal probe, and a unitary-side search (Oct 21 2026)

Status labels: **[proved]**, **[numerical]**, **[cited]**, **[failed]**. The three-party conjecture was open when this appendix was written; H.12.1 refutes it. Code: code/stochastic/structural/.

Notation. Inputs a, b, c; outputs x, y, z; a classical process $p(a,b,c|x,y,z) \geq 0$ with $\sum_{a,b,c} p(a,b,c|f(a),g(b),h(c)) = 1$ for all local functions f, g, h. Any finite alphabets unless stated.

H.1 Route A: classes that reduce to Appendix G

Definitions. Party A is *last* if p does not depend on x. A is *marginally first* if $p(a|x,y,z) := \sum_{b,c} p$ does not depend on (x,y,z). A is *first with valid conditionals* if, in addition, for every a with $p(a) > 0$ and every x, the conditional $q_{a,x}(b,c|y,z) = p(a,b,c|x,y,z)/p(a)$ is a valid bipartite classical process. A process is *classically causally separable* if it is a convex combination of processes, each with some party first with valid conditionals. This is the diagonal (classical) analogue of the recursive definition of Wechs, Abbott and Branciard (NJP 21, 013027 (2019), Def. 5) and of Oreshkov-Giarmatzi's extensible causal separability [cited; the definitions were checked against arXiv:1807.10557. I have not checked that the classical specialisation with extensions reduces exactly to the one used here, so it is offered as an analogue].

Theorem H.1 [proved]. If some party is last, p is a mixture of process functions in which that party is last.

Proof. Say A is last. The B,C marginal $r(b,c|y,z) = \sum_a p$ is a valid bipartite process (take f arbitrary). By G.1, $r = \sum_l$ mu_l delta[(b,c) = $w_l(y,z)$], with each w_l a causally ordered bipartite process function. Put $t(a|b,c,y,z) = p/r$ where $r \rangle 0$, and any distribution elsewhere. Expand t as a product mixture of deterministic functions alpha(b,c,y,z), with weight prod_{args} t(alpha(args)|args). Then $p = \sum_{l,alpha}$ mu_l nu(alpha) delta[(b,c) = $w_l(y,z)$] delta[a = alpha(b,c,y,z)]. Each term is a process function: given g, h, the B,C part has one fixed point, and then a is determined. ∎

Theorem H.2 [proved]. If some party is first with valid conditionals, p is a mixture of process functions in which that party is first. Hence every classically causally separable 3-party process is a mixture of causally ordered process functions, and the purification conjecture holds on that class (both sides true, via C.1).

Proof. Say A is first. By G.1, $q_{a,x} = \sum_l$ mu(l|a,x) W_l, with W_l ranging over the finitely many bipartite causally ordered process functions. Then $p = \sum_{a0} p(a0) \sum_{\text{lambda: } X \to L}$ prod_x mu(lambda(x)|a0,x) delta[a = a0] $W_{\text{lambda(x)}}$(b,c|y,z). The term (a0, lambda) has a = a0, and then (b,c) given by the process function $W_{\text{lambda(x)}}$. Under interventions f, g, h, x = f(a0) is fixed, and $W_{\text{lambda(x)}}$ has exactly one fixed point, so the term is a process

function. ∎ The result extends to N parties by induction when the definition is recursive (the conditional (N-1)-party process is required to be separable). For N = 3, G.1 makes the bipartite recursion automatic.

Marginally first is not enough [proved]. $E_{ex1} = (C + C)/2$ is marginally first in every party: party 1's input is o_3 or its negation with probability 1/2 each, so it is uniform whatever the outputs are. Yet it is not a mixture of process functions (C.2). The conditional for a_1 is a3 = o2 + [o3 ≠ a1], a2 = o1 + [o3 ≠ a1] (mod 2). With the intervention o3 = h(a3), this has 0 or 2 fixed points, so it is invalid. The validity of conditionals carries the whole content.

Numerics [numerical] (classes.py, classes.json; 3 binary parties, 300 random LP objectives on each sub-polytope; every distinct vertex was tested for 0/1 and for membership in conv(744 PFs)):

sub-polytope	distinct vertices	non-deterministic	outside conv(PF)
A last	157	0	0
A first with valid conditionals	187	0	0
A marginally first	208	39	11

The first two rows agree with H.1 and H.2. Of E_{ex1} and the 51 non-deterministic vertex orbits, none is last or first-with-valid-conditionals in any party. 19 of them are marginally first in at least one party, including E_{ex1}, orbits 7 and 50 (all three certified non-purifiable), and orbit 8 (marginally first in parties 1 and 2).

Where Lugano sits [cited/proved]. The Lugano (Araújo-Feix / Baumeler-Wolf) process function violates a causal inequality (Baumeler, Feix, Wolf, PRA 90, 042106 (2014), arXiv:1403.7333) [cited]. So it is not causally separable. Directly: each input depends non-trivially on outputs of both other parties, so no party is marginally first, and every output is used, so no party is last [proved]. It lies outside every reducible class, but it is a process function. The interesting class is exactly conv(PF) minus the causally separable processes, together with the candidate non-hull processes, and the reductions say nothing about either.

Does purifiability add anything here? On the classes of H.1 and H.2, no: every valid process is already a PF mixture. The natural next statement would be "purifiable and marginally first imply valid conditionals". It would settle the conjecture for the 19 marginally-first orbits, including orbit 8. It is open [not proved]; H.5 shows the W-level version fails. D.2 and D.8 show it cannot follow from the source sector alone.

H.2 Route B: a determinantal bound for orbit 8 [failed, numerical]

Idea. If S is a jointly isotropic subspace (AFNB Thm 4, reduced as in C.2) and u is in S, then S lies in ker K(u), where $K(u)_{t,b} = Q_t(u, e_b)$ runs over the 196 linearly independent constraint forms of orbit 8 (m = dim V_W = 82). So dim S ≤ dim R + (82 - rank K(u)) for any isotropic u outside the common radical R (dim R = 1, spanned by c0). An exact proof would need rank K(u) ≥ 67 on the whole isotropic cone outside R. That is one determinantal variety (67-minors) with no real point on the cone, which can be checked algebraically in principle.

Probe (detprobe.py). Generic near-isotropic u (residual ~1e-7 to 1e-6) have numerical rank 81. But minimising the tail singular values of K(u) along the cone gives points whose spectrum drops from 1.6e-2 (sigma_50) to 3.4e-4 (sigma_55) and stays there down to sigma_66, with isotropy residual 2.5e-7. So, numerically, the cone contains u with rank K(u) of about 51-55. The single-vector bound then gives only dim S ≤ ~28-32, not < 16. The determinantal route with one vector cannot work for orbit 8. A flag version (rank conditions on pairs u, v in S) would be needed, and it is a much larger variety. Not attempted. Gröbner bases on a symmetric ansatz were not

attempted, because the stabiliser of orbit 8 has order 8 (App. E), too small to reduce the 82 complex unknowns per basis vector to a tractable size. **No exact proof for orbit 8.**

H.3 Route C: counterexample hunt from the unitary side [numerical, negative]

Parametrisation (hunt.py). $U = U0 \exp(iH)$ is a 64 x 64 unitary $O \otimes P \to I \otimes F$, with $P = F = C^8$ and source $|0\rangle$. The loss is a purity residual sum $||M M\dagger - 1||^2$ over random Haar local unitaries, with and without qubit ancillas, plus a penalty on the off-diagonal part of W (classicality), minus the value of a PF-hull facet from orbit 82 (D.7) under a random symmetry. A point with purity residual ~0, W diagonal and facet > 0 would be a purifiable process outside conv(PF).

- Random start (U0 = 1, 8 seeds x 20,000 Adam steps): purity was never reached. The final residual (20 fresh samples, qubit ancillas) was 10-172. The facet values there are meaningless, because W is not normalised. **[failed: the optimiser does not even find pure unitaries from random starts]**
- Start at the Lugano lift (exactly pure, facet image chosen tight = 0 at Lugano; 8 seeds): the search trades purity against violation. Final facet violation was 0.008-0.018 at purity residual 0.13-2.4 (ancilla samples) and off-diagonal mass 4e-5 to 7e-4. Not one run kept both residuals near 0 with positive violation.

This was read as consistent with the conjecture [superseded by H.12]: leaving the hull at a Lugano vertex costs purity at once, as in D.8's boundary test. It is local, small-sample evidence, not a proof. No counterexample was found.

H.4 Summary

- Proved: H.1 (some party last implies PF mixture) and H.2 (classically causally separable implies mixture of causally ordered PFs). On both classes every valid process is a PF blend, so no gap can occur there. Also proved: marginal "firstness" does not reduce (E_{ex1}).
- Settled negatively (H.5): purifiability plus marginal firstness does not force valid conditionals; a 4-term PF mixture is an exact counterexample.
- Failed: the single-vector determinantal bound for orbit 8 (numerically the cone has rank ~51-55 points), and the unitary-side counterexample search (no hit).

H.5 Purifiability plus "A marginally first" does not force valid conditionals [proved, exact counterexample] (Oct 21 2026)

Question. Does purifiable + (A marginally first) imply that every conditional $q_{a,x}(b,c|y,z)$ is a valid bipartite process? If so, H.2 would settle E_{ex1} and orbits 7, 8 and 50.

Answer: no, already for classically purifiable processes. Take three binary parties and

```
p(a,b,c|x,y,z) = (1/4) [a = b + c + y + z mod 2].
```

- p is a uniform mixture of 4 process functions $w_{beta,gamma}$: b = beta, c = gamma, a = beta + gamma + y + z. In each, B and C are first and A is last. So p is purifiable (C.1); A is even last (H.1).
- A is marginally first: p(a|x,y,z) = 1/2 for every a, x, y, z.

- The conditional $q_a(b,c|y,z) = (1/2)[b + c + y + z = a]$ is invalid. With the interventions y = b, z = c, $\sum_{b,c} q_a = 2$ for a = 0 and 0 for a = 1.

All of this is checked in exact rational arithmetic (code/stochastic/structural/margfirst_cex.py): the decomposition, validity of p, that the 4 maps are process functions, marginal firstness and the conditional sums. So the implication fails. No search was needed. Any statement of this form is false whenever some PF mixture is marginally first with invalid conditionals.

Where the naive proof breaks. The plan was to fix A's classical input and obtain a lift of the conditional. Marginal firstness is a property of the diagonal W only. In the purification (here the source-sink lift of a PF mixture), A's input register is computed downstream of B's and C's outputs. Its marginal is uniform only because the mixture is averaged over (beta, gamma). Fixing a is therefore post-selection on a variable that depends on y, z. Post-selection is not a unitary operation and does not preserve purity or even validity of what remains. A sound conditioning step needs A to be first *in the purifying unitary*: I_A must depend only on the source under every local intervention. That is a structural property of V, not of W. D.4 shows such structure cannot be read off W.

Consistency with E_{ex1} (3) [proved]. E_{ex1} is marginally first with invalid conditionals (H.1). Its non-purifiability rests only on the inertia certificate of C.2. H.5 shows that the invalid conditionals carry no evidence by themselves, since a purifiable process shares both features. The certificate is unaffected.

Consequence. Route A, in its W-level form, cannot reach the marginally-first orbits. A version that could survive: "if V purifies W and A is first *in V* (I_A independent of all party outputs, as an operator statement), then the conditionals of W are valid". This is proved in H.6 (Lemma H.6.1, Theorem H.6.2). It says nothing about E_{ex1} unless one also shows that every purification can be rearranged so that a marginally-first party is first in V. H.5 shows that rearrangement is impossible in general (in the example, A is last in the natural purification). So this line does not by itself settle the conjecture: it reduces it to purifications with no operator-first party (H.6).

H.6 Operator-level firstness forces valid conditionals [proved] (Oct 21 2026)

This is the operator-level variant left unproved at the end of H.5. Setting as in D: a purification of W is a unitary $V : P \otimes O \to F \otimes I$, with $O = O_A\, O_B\, O_C$, $I = I_A\, I_B\, I_C$ and a fixed source state $|psi\rangle$, such that closing the party slots with arbitrary local unitaries (with ancillas) always gives a unitary (AFNB 2017, Def. 3).

Definition (operator-level first). Party A is *first in V* if V factorises as

$$V = (V' \otimes 1_{I_A})\,(S \otimes 1_O), \quad S : P \to I_A \otimes R \text{ unitary}, \quad V' : R \otimes O_A \otimes O_B \otimes O_C \to F \otimes I_B \otimes I_C \text{ unitary},$$

up to reordering of wires. So I_A is prepared from the source alone, and A's output O_A enters only V', together with the leftover source R. Two other candidate definitions are equivalent:

- (no-signalling form) the channel $P \otimes O \to I_A$ obtained from V by tracing F, I_B, I_C does not depend on the O input. Its Choi operator is $J_{I_A\,P} \otimes 1_O / d_O$. The factorisation follows from Eggeling-Schlingemann-Werner (semicausal ⇒ semilocalizable, EPL 57, 782 (2002)) applied to the isometry V. The converse is immediate. [cited + proved]

- (causal-graph form) in the causal structure of the unitary process (Barrett-Lorenz-Oreshkov, Nat. Commun. 12, 885 (2021), Def. 4), with the source and sink as extra nodes, A has no parents among A, B, C. A's own output is included, so there is no self-loop. For unitaries, no influence from each of O_A, O_B, O_C separately implies no influence from O jointly. In the Heisenberg picture, V^dag (Z_{I_A} ⊗ 1) V commutes with the operator algebras of O_A, O_B and O_C, and these generate all operators on O. [proved]

Firstness is not a property of W: H.5 shows a marginally first party that is last in the natural lift. A weaker "process-level first" condition, that A's input is unaffected by other parties' instruments, is just marginal firstness for classical W. H.5 refutes the reduction under that weaker condition.

Lemma H.6.1 [proved]. Suppose A is first in a purification (V, psi) of a classical process p(a,b,c|x,y,z). Write $S|psi\rangle = \sum_a |a\rangle_{I_A} \otimes |r_a\rangle_R$. Then:

1. A is marginally first, with $p(a) = ||r_a||^2$.
2. For every a with p(a) > 0 and every x, the pair $(V', |r_a\rangle|x\rangle_{O_A} / ||r_a||)$ is a purification, in the sense of AFNB, of a diagonal bipartite process on B, C whose diagonal is exactly the conditional $q_{a,x}(b,c|y,z) = p(a,b,c|x,y,z)/p(a)$.
3. In particular every $q_{a,x}$ is a valid, purifiable bipartite classical process.

Proof.

- (Purity of V'.) Close the A slot with any unitary $U_A : I_A \otimes X_A \to O_A \otimes Y_A$ (one exists for suitable ancilla dimensions), and close B and C with arbitrary U_B, U_C. Because nothing upstream of I_A depends on any output, contracting the A wire is ordinary sequential composition:

  ```
  M = (M'_BC ⊗ 1_{Y_A}) (1_R ⊗ U_A ⊗ 1_{X_B X_C}) (S ⊗ 1_{X_A X_B X_C}),
  ```

  where $M'_{BC} : R \otimes O_A \otimes X_B \otimes X_C \to F \otimes Y_B \otimes Y_C$ is V' with B and C closed. M is unitary because V is pure. The two right-hand factors are unitary. So $M'_{BC} \otimes 1$ is unitary, and hence M'_{BC} is unitary. This holds for all U_B, U_C, so V', with source $R \otimes O_A$, is a pure bipartite process.

- (Diagonal and conditionals.) $V|psi,x,y,z\rangle = \sum_a |a\rangle_{I_A} \otimes V'|r_a,x,y,z\rangle$. The Choi entries of W are therefore $W[(a,b,c,x,y,z),(a',b',c',x',y',z')] = \langle V'(r_{a'},x',y',z')_{b'c'} \mid V'(r_a,x,y,z)_{bc}\rangle_F$, where _{bc} denotes the component with $I_B\ I_C = |b,c\rangle$. For a = a' and x = x', these are the entries of p(a) times the process matrix $W'_{a,x}$ of $(V', |r_a,x\rangle/||r_a||)$. W is diagonal, so $W'_{a,x}$ is diagonal with diagonal $p(a,b,c|x,y,z)/p(a) = q_{a,x}$. Summing the diagonal over b, c at y, z gives $\sum_{b,c} ||V'(r_a,x,y,z)_{bc}||^2 = ||r_a||^2$, which is item 1.

- (Validity.) The diagonal of a valid process matrix is a valid classical process: evaluate it on the measure-and-prepare channels b → g(b). Validity of $W'_{a,x}$ follows from purity (Appendix A). ∎

Where the H.5 obstruction went. With A's slot replaced by a SWAP to ancillas, the remaining B, C map from P ⊗ O_A to F ⊗ I_A is unitary for every pure process, whether or not A is first (checked numerically below). So the source-and-sink "open-A" bipartite process is always pure. The conditioning on x is harmless, since x is a source preparation. The conditioning on a is a sink post-selection. Firstness is exactly what moves the a-measurement

onto R, before V' acts, via S. Normalisation then comes for free (item 1). Without firstness, a is a sink outcome, and fixing it is the post-selection of H.5.

Theorem H.6.2 [proved]. Let W be a 3-party classical process (any finite alphabets). If some purification of W has some party first at the operator level, then W is a PF blend, indeed a blend of causally ordered process functions with that party first.

Proof. Lemma H.6.1 shows that the party is first with valid conditionals. Apply H.2, which uses G.1. ∎

N parties. Lemma H.6.1 holds verbatim and gives an (N-1)-party purifiable conditional. If the conditional purifications again have a first party, recursively, W is a blend of causally ordered PFs. For the conditional, that party has to be first in V' with the source state $|r_a,x\rangle$, so the recursion is on V', not on W. This includes the case where V has an acyclic causal structure in the BLO sense: a topological order supplies a first party at every level, and the order is inherited by V'. The 3-party case needs firstness only once, because G.1 handles every bipartite remainder. [proved for N = 3; for N > 3, proved under the recursive hypothesis, using the recursive form of H.2 stated after its proof]

Quantum remark. For a general (non-diagonal) W, the same proof gives a pure bipartite conditional. BLO Theorem 3 (every unitarily extendible bipartite process is causally separable) then makes W causally separable with A first. [proved modulo cited BLO Thm. 3]

Contrapositive (useful) [proved]. If W is not first-with-valid-conditionals in party k, then no purification of W has k first at the operator level. Consequences:

- Lugano is not marginally first in any party (H.1), so none of its purifications, not just the lift, has an operator-first party.
- None of E_{ex1} or the 51 sampled non-deterministic vertex orbits is first-with-valid-conditionals in any party (H.1 numerics). So a purification of any of them, if one exists, has no operator-first party. This includes orbit 8, which is marginally first in parties 1 and 2. For E_{ex1} and orbits 7 and 50 the statement is vacuous, since they have no purification at all (C.2).

What this leaves open. The conjecture was thereby reduced to purifications in which **every** party has a parent among the party outputs, i.e. every party's input is influenced by some output in V. Lugano-type lifts are like this: their causal graph is a 3-cycle. Theorem H.6.2 says nothing about a W whose only purifications are of this kind. That is the same class flagged as open in Section 9, now characterised at the operator level. A purifiable non-blend, if one exists, must be such a W: one with no first party and no last party in any purification. W-level lastness already gives H.1. Operator-level lastness is a stronger hypothesis, so it is covered too.

Numerics [numerical] (code/stochastic/structural/opfirst.py, log opfirst.log; C.1 lifts). The firstness residual is max $|J - \mathrm{Tr}_O J \otimes 1/d_O|$ for the channel $P \otimes O \to I_k$. Open purity is $||M\ M^\dagger - 1||_{max}$, with slot k replaced by a SWAP and the other two closed by Haar unitaries with qubit ancillas, worst of 5.

process	party	op-first residual	open-slot purity	marginally first	conditionals
Lugano	A, B, C	0.75 each	≤ 1.3e-15	no	n/a
H.5 blend	A	0.5 (not first)	8.9e-16	yes	invalid (sums 0, 1, 2)
H.5 blend	B	0 (first)	1.4e-15	yes	valid (all sums 1)
H.5 blend	C	0 (first)	1.1e-15	yes	valid

This is consistent with the lemma. In the H.5 lift, A is last and not operator-first, and its conditionals are invalid. B and C are operator-first, and their conditionals are valid, as H.6.1 requires. The open-slot map is unitary in every case, which confirms that the content of the lemma is the source-side relocation of the a-measurement.

Literature [cited, checked against arXiv:2002.12157v3 and quant-ph/0104027].

- Barrett, Lorenz and Oreshkov (2021) prove the two endpoints. If a unitary process has an acyclic causal structure, it is a comb (Thm. 4). Every unitarily extendible bipartite process is causally separable (Thm. 3). Their Thm. 6 is that reversibly extendible classical processes form the deterministic polytope, the classical analogue of D.6.
- They state that a unitarily extendible process need not be causally separable in general (AF process), and they leave open how cyclicity constrains extensions. I did not find the one-parentless-node conditioning lemma H.6.1, or Theorem H.6.2, stated there, in AFNB 2017, or in Wechs-Abbott-Branciard 2019. WAB's recursive definition of causal separability (first party, then a valid conditional) is the target property; they do not connect it to purifications. H.6.1 is elementary given those sources. It is offered as a short observation, not as a new technique. I did not do a full literature search beyond these papers.

H.7 Purifications with no operator-first party: a search beyond Lugano (Oct 22 2026) [numerical; two small proved statements]

Goal. By H.6, a purifiable process outside conv(PF) can only have purifications in which no party is operator-first. This section looks for such purifications with three binary parties and small source and sink, and asks whether any of them induces a classical process outside the hull. **No non-blend was found.** Code is in code/stochastic/cyclic/, with logs and .npy results there.

Tests applied to every purification found.

- *Purity:* max ||M M^dag - 1|| under fresh Haar local unitaries, with and without qubit ancillas.
- *Operator-first residual for each party:* the channel $P \otimes O \to I_k$ must be independent of O (common.opfirst).
- *Causal graph:* pairwise influence $O_j \to I_k$ through V (common.influence; an edge is drawn when the residual is > 1e-6).
- *Induced classical process:* p(i|o).
- *Hull test:* L1 distance to conv(744 PFs) by LP.
- *Lugano weight:* the minimal weight on the 64 Lugano-orbit PFs in any PF decomposition (LP with L1 slack 1e-7). Weight 0 means p is a blend of PFs that each have a constant component, i.e. classically causally separable (H.2).

Family A: single-PF lifts and phase variants [proved / numerical].

- In the lift of Section 1, $I_k = w_k(o) + e_k$, so party k is operator-first iff w_k is constant.
- Of the 744 binary PFs, exactly 64 have no constant component. They form one orbit under party permutations and bit flips, the Lugano orbit (orbit size 64 = 384/6) [exhaustive check, famA.py].
- So, among single-PF lifts, "no operator-first party" is the same as "Lugano-type".
- Phases: multiplying the lift by a source-only or sink-only phase keeps purity (residual ~2e-15), because these are local unitaries on P or F.
- A generic joint phase exp(i theta(o,e)) destroys purity (residual 0.61-0.68 for three random theta).

- Every pure phase variant induces the same diagonal p, the PF itself.

Family B: coherent blends of causal orders [proved]. Take the C.1 lift of a blend of three causally ordered PFs whose first parties are A, B and C respectively (PF indices 17, 145, 152 in pfs744.npy).

- In this purification no party is operator-first (residual 0.75 for each party).
- Every output is used, so no party is last.
- Yet W is a blend of causally ordered PFs.
- So "no operator-first party in V" does not imply that W is non-separable, and the structural guess "every purification with no first party is Lugano-like" is **false** as stated.
- The classical analogue (Barrett-Lorenz-Oreshkov 2021) is that cyclic causal structure does not imply causal nonseparability (their classical SWITCH remark).

Family C: output-dependent source unitaries ("noisy-PF" purifications). Source P = S ⊗ T and sink F = O ⊗ E', with S, T, O, E' each C^8:

$$V|o, s, t\rangle = \sum_e C_o[e, s]\ |e\rangle_I\ |o\rangle_F\ |e \text{ xor } t\rangle_F, \quad C_o \text{ in } U(8), \text{ one per joint output } o.$$

- V is unitary for any choice of the C_o.
- The sink records (o, i), so W is diagonal, with $p(i|o) = |C_o[i, 0]|^2$.
- Every classical p arises for some C_o; purity is the only constraint.
- The Lugano lift is the case $C_o = X^{w(o)}$.

Lemma H.7.1 [proved; numerically verified]. Family C is pure under local unitaries *without ancillas* iff, for all o ≠ o' and all delta in $\{0,1\}^3$, with $K = C_o\ C_{o'}$^dag, D = supp(o xor o') and S = D \ supp(delta):

$$\text{sum over } e_S \text{ of } (-1)^{|e_S|}\ K[e, e \text{ xor } delta] = 0 \quad \text{for every value of } e \text{ outside } S.$$

Proof. Rows (o,t') and (o',t'') of the induced M have inner product $\sum_e K[e, e \text{ xor } delta] \prod_k U_k[o_k,e_k]\ \text{conj}(U_k[o'_k, e_k \text{ xor } delta_k])$, with delta = t' xor t''. For o = o' this is $delta_{delta,0}$. For o ≠ o', the factor of party k, as U_k ranges over U(2), spans all of C^2 unless k is in D and $delta_k = 0$. In that case it spans only (1,-1), because the rows of U_k are orthogonal. The products of these spans give exactly the stated condition. ∎

lemmaC.py confirms the condition numerically:

C	violation
Lugano	0
random unitaries	1.58
polished solutions in the table below	3e-11 to 3.5e-9
rand_12 (polished only to 1.6e-6)	6.3e-6

With ancillas the condition is necessary. It is also sufficient: see H.8.2 (added Oct 22 2026).

Searches in family C [numerical]. Method: Adam on purity, using sampled local unitaries with and without qubit ancillas (famC.py), then L-BFGS polishing in float64 on a fixed batch of 12 samples (polish.py), then the tests above on fresh samples (characterize.py; charP.json, charP2.json, charL.json).

- Random starts: 11 seeds. 1 failed to become pure (rand_11, polish loss 224). 1 reached only purity 1.6e-6 (rand_12).
- Lugano-seeded starts (noise 0.3): 3 seeds.
- Facet-pushing runs (pure loss minus lambda times a random image of facet 82, lambda = 0.1, 0.3, 1): Lugano-seeded runs reached facet violation 0.89-1.0 only at purity residual 0.03-0.05 (famC_lug_*_{6,8,10}.log). None was pure. This is the same trade-off as H.3. The two random-start facet runs were invalid because of a since-fixed parametrisation bug (a non-Hermitian generator). Their logs were discarded.

solution	purity	op-first residual A/B/C	causal graph	first or last party at operator level	hull dist	min Lugano weight
rand_1	3e-11	0 / .52 / .46	A>B, A>C, B<→C	A first	0	0
rand_2	2e-10	.33 / .53 / .38	A<→C, A>B, C>B	B last	0	0
rand_3	2e-11	.23 / .22 / .63	A<→B, A>C, B>C	C last	0	0
rand_12	1.6e-6	.68 / .42 / 0	A<→B, C>A, C>B	C first	7e-7 (noise)	n/a
rand_13	6e-10	.46 / .24 / 0	C>A, C>B, B>A	C first, A last	0	0
rand_14	5e-10	.56 / .18 / .30	B<→C, B>A, C>A	A last	0	0
rand_15	1.4e-10	.67 / .55 / .73	**complete (all 6 edges)**	**none**	0	**0**
rand_16	2e-11	.67 / 0 / .50	B>A, B>C, A<→C	B first	0	0
rand_17	2e-11	.24 / .44 / .21	A<→C, A>B, C>B	B last	0	0
rand_18	3e-10	.47 / .48 / 0	A<→B, C>A, C>B	C first	0	0
lug_21	5e-10	.75 / .72 / .72	**complete**	**none**	0	**0.93**
lug_22	7e-11	.71 / .72 / .72	**complete**	**none**	0	**0.87**
lug_23	7e-11	.73 / .72 / .74	**complete**	**none**	0	**0.90**

Reading [numerical].

1. Every pure solution found induces a p inside conv(PF), at LP distance 0. **No counterexample.**
2. The rows with an operator-first party are consistent with H.6. An operator-last party (its output influences no input) makes p independent of that output, so H.1 applies. 9 of the 10 random-start pure solutions have a first or a last party.
3. **New: no first and no last party, separable W.** rand_15 is a purification with a complete (maximally cyclic) causal graph, no operator-first and no operator-last party. Its p needs Lugano weight 0, so it is a blend of causally ordered PFs. Together with family B, this shows that the open class "no operator-first party" contains many purifications of causally separable processes.
4. **New: genuinely non-separable continuous family near Lugano.** The Lugano-seeded solutions are pure, are not phased permutations (their C_o are generic unitaries, so not of D.3 form), and have a complete causal graph. Their p needs Lugano weight 0.87-0.93: non-separable, but a PF blend.
5. **Structural guess refuted.** "Every no-first-party purification is Lugano-like up to local unitaries" is false: family B is an exact counterexample, and rand_15 is a numerical one.

Names. The gentle version (graded.md, Section 58e) uses informal names: the Ring (the 64 Lugano-orbit single-PF lifts of family A), the Chorus (family B), the Switchboard (family C) and the Shadows (lug_21-23).

What remained open. The conjecture on the class (refuted there by H.12.1) of purifications with neither an operator-first nor an operator-last party.

- Within family C, Lemma H.7.1 turns no-ancilla purity into linear conditions on the products C_o $C_{o'}$^dag. A proof that these conditions, together with the ancilla conditions, force p into conv(PF) would settle family C. Attempted in H.8: the ancilla conditions are implied (H.8.2), and the hull question is still open.
- Family C has source dimension 64 and records (o, i) in the sink. General purifications can have larger sources and need not have this form (D.4).
- These searches cover a small, structured slice. They are local and few: 13 pure solutions in total.
- **Running jobs:** none. All runs completed or were stopped; the logs are in code/stochastic/cyclic/.

H.8 The Switchboard lemma: Pauli form, ancillas, and what is and is not forced (Oct 22 2026) [proved parts; hull question numerical]

Task: do the purity conditions of Lemma H.7.1 force the induced p into conv(PF) (37-dim, 744 vertices)? **Answer (at the time): not settled; H.12.1 later answered no.** The conditions are equivalent to full purity, so this is the conjecture restricted to family C (answered negatively by H.12.1). A numerical search (108 runs) found no counterexample, and the trade-off between violation and purity residual is quadratic (Appendix I). What is proved: H.8.1-H.8.5. Code: code/stochastic/cyclic/switchboard/.

Notation. Write $U_o := C_o$ (8x8 unitary, rows indexed by the input string $e = (e_A, e_B, e_C)$), $K_{o,o'} := U_o\, U_{o'}$^dag, and D(o,o') := supp(o xor o'). For a unit source vector phi in S put psi_o := U_o phi. Then $p_{phi}(i|o) = |\langle i|psi_o\rangle|^2$, and psi_o = $K_{o,o'}$ psi_{o'}. The source column s = 0 of H.7 is phi = $|0\rangle$. The H.7.1 conditions do not mention phi, so every phi gives a purification.

H.8.1 Pauli form [proved; exact check]. For o ≠ o', the H.7.1 conditions on K = $K_{o,o'}$ hold iff every Pauli coefficient $c_{a,b}$ = Tr[(X^a Z^b)^dag K]/8 vanishes for strings that are non-identity on every party of D. Equivalently,

$$K_{o,o'} \text{ in } A_D := \text{sum over } k \text{ in } D \text{ of } (1_k \otimes L(C^4)),$$

the linear span (not the union) of the operators that act trivially on at least one party whose output changed. *Proof.* K[e, e xor delta] = $\sum_b c_{delta,b}$ (-1)^{b.(e xor delta)}. On S we have $delta_S = 0$, and sum over e_k of $(-1)^{e_k}$ $(-1)^{b_k e_k}$ equals 2[b_k = 1]. So the signed sum over e_S equals $2^{|S|}$ times the sum, over the b with $b_S = 1$, of $c_{delta,b}$ $(-1)^{b_\{S^c}$. (e xor delta)_{S^c}}. As e_{S^c} varies, this is a Fourier transform in b_{S^c}. It vanishes for every e_{S^c} iff $c_{delta,b} = 0$ whenever $b_S = 1$, with S = D \ supp(delta). That is, X^delta Z^b is forbidden iff, at every k in D, $delta_k = 1$ or b_k = 1. ∎ *Exact check* (pauli_exact.py, rational arithmetic with python-flint): for all 7 nonempty D the two families of functionals have equal rank and equal joint rank. The ranks are 48 / 36 / 27 for |D| = 1 / 2 / 3, so the allowed spaces have dimensions 16 / 28 / 37. The stored H.7 solutions satisfy both forms to the same precision (pauli.py). *Sanity check.* For a process function, $U_o = X^{w(o)}$ and K = X^{w(o) xor w(o')} is a single Pauli. It is allowed iff $w_k(o)$ =

$w_k(o')$ for some k in D, which is the exclusivity lemma of Section 1. So H.8.1 is the operator-valued version of exclusivity, with a span in place of a union.

H.8.2 Ancillas add nothing in family C [proved]. Family C is pure under local unitaries with arbitrary finite ancillas iff it is pure without them, iff H.8.1 holds. This settles the question left open after H.7.1. *Proof.* With ancillas, rows of M are labelled (o, t', y). The row inner product is $\sum_e K[e, e \text{ xor } delta] \prod_k N_k(e_k)$, with $N_k(e) = \sum_x U_k[(o_k,y_k),(e,x)]$ conj $U_k[(o'_k,y'_k),(e \text{ xor } delta_k, x)]$. As in H.7.1, N_k spans C^2 unless $(o_k,y_k) \neq (o'_k,y'_k)$ and $delta_k = 0$, in which case it spans (1,-1). The parties with $(o_k,y_k) \neq (o'_k,y'_k)$ form a set D' that contains D. If o = o', then K = 1 and every condition holds trivially. If o ≠ o', the condition for D' is a further signed sum of the condition for D, because S' = D' \ supp(delta) contains S. So it is implied. ∎ So the 13 H.7 solutions are pure with ancillas exactly, not just numerically.

H.8.3 Causal structure, read off K [proved]. In family C:

- (no self-influence) $K_{o,\, o \text{ xor } e_j}$ in 1_j ⊗ U(4) for every o and j;
- O_j influences I_k (BLO sense) iff some $K_{o,\, o \text{ xor } e_j}$ acts non-trivially on k;
- party k is operator-first iff every $K_{o,o'}$ acts trivially on k, i.e. $U_o = (1_k \otimes R_o)\, U_0$;
- party j is operator-last iff $K_{o,\, o \text{ xor } e_j}$ is a scalar for every o. *Proof.* The Heisenberg pull-back of an observable A on I is $\sum_o |o\rangle\langle o| \otimes G_o(A)$, with $G_o(A) = \sum_x U_o\text{^dag } A^{(x)}\, U_o \otimes X\text{^}x$ on T. Here $A^{(x)}$ is the part of A whose matrix entries connect e to e xor x. The register T and the sink record o make the pull-back block diagonal in o. Independence of o_j for every A supported on I_k means that $U_o\text{^dag sigma_k } U_o$ is the same for o and o xor e_j for every Pauli sigma_k. Equivalently, K commutes with every Pauli on k, so it is trivial on k. For lastness take A on all of I; then K commutes with everything, so it is a scalar. The first item is H.8.1 with |D| = 1. Operator-first follows by composing along edges of the cube $\{0,1\}^3$. ∎ So "no first and no last party" means: every party k has some cube edge whose transition acts on k, and no direction j has only scalar transitions.

H.8.4 Monomial switchboards are PF blends for every source state [proved]. If every $U_o\, U_0\text{^dag}$ is monomial (a permutation matrix times a diagonal phase), or more generally if the rank-one projectors $P_{o,i} := U_o\text{^dag } |i\rangle\langle i|\, U_o$ all commute, then p_{phi} is in conv(PF) for every phi. *Proof.* Commuting rank-one projectors that sum to 1 over i, for each o, are the projectors onto one common orthonormal basis $\{b_j\}$: $P_{o,i} = |b_{j(o,i)}\rangle\langle b_{j(o,i)}|$. For phi = b_j the induced p is 0/1. It is valid by Appendix A, since b_j is a legitimate source state (H.8.1 does not mention phi). A 0/1 valid classical process is a process function. Then $p_{phi} = \sum_j |\langle b_j|phi\rangle|^2\, p_{b_j}$. ∎ This covers the Ring (all single-PF lifts and their pure phase variants) and the classical reversible case (D.6).

H.8.5 Single-party edges preserve that party's marginal [proved]. If o and o' differ only at k, then psi_o = (1_k ⊗ R) psi_{o'}. So the distribution of e_k is the same under o and o'. Party k cannot signal to itself even in superposition. Two-party differences give K in $A_A + A_B$. This is a sum, and it contains unitaries such as cos(theta) X_A + i sin(theta) X_B, which no single process function produces. That interference is what a proof would have to control.

The hull question [numerical; superseded by H.12: the answer is no]. By H.8.2, "do the H.7.1 conditions force p into conv(PF)?" is exactly the purification conjecture restricted to the Switchboard. Equivalently, $F_m(U)$:= sum

over (s,i,o) in m of s $P_{o,i} \leq 0$ (operator inequality) for every facet m of the 37-dim hull, whenever U satisfies H.8.1. The search of Appendix I minimises the exact residual R(U) = sum over $o \neq o'$ of the squared forbidden Pauli coefficients, at prescribed facet-82 violation v = lambda_max(F_m) > 0. It never found $R \to 0$. The minimum found was $R \geq 0.31\ v^2$ over 108 runs (random, Lugano and H.7-solution starts; v = 0.01 to 0.9). **No counterexample.** Note that the class is compact: if inf R = 0 at some fixed v > 0, a limit point would be an exact counterexample. So the observed quadratic floor is the quantitative form of the evidence. It is not a proof.

Where a proof stopped. H.8.4 covers the commuting case. The Shadows (lug_21-23) are non-commuting and genuinely non-separable, yet inside the hull. So a general proof must decompose p_{phi} into PFs without a common eigenbasis, for instance by a phi-dependent basis or by an SOS identity of the form -lambda_max(F_m) $\geq$ -c sqrt(R). The numerics suggest c ~ 1.8 for facet 82. I did not find such an identity. An exact SOS search in the 8 x 64 complex entries of U (quartic in U) was not set up.

H.9 Toward a structure theorem: three binary parties, no operator-first and no last party (Oct 22 2026) [partial; proved vs conjectured marked]

Proved.

1. (H.6.2, H.1) A purifiable W outside conv(PF) has only purifications with no operator-first party and no W-level last party. An operator-last party makes W independent of that output, so H.1 applies. Purifications with an operator-last party are therefore also excluded.
2. (Family C, H.8) Inside the Switchboard the open class is the set of 8-tuples of unitaries with $K_{o,o'}$ in $A_{D(o,o')}$ (H.8.1), with every party acted on by some edge transition and no direction scalar (H.8.3). On this class purity with and without ancillas coincide (H.8.2). The commuting/monomial sub-class lies in conv(PF) for every source state (H.8.4). That sub-class contains the whole Ring (the 64 Lugano-orbit lifts).
3. (Family B) The Chorus shows that the open class contains purifications of causally separable W (H.7). So any structure theorem must be a statement about the record W, not about V: "no first mover in V" does not force non-separability.
4. (No reduction to a canonical form) D.4 already shows that no hidden classical label can be read off. H.8.1 shows the Switchboard transitions live in sums of algebras rather than unions, so purifications are not, up to local unitaries, coherent controls over single process functions. The Shadows are explicit numerical examples (non-monomial C_o).

Conjectured (not proved).

- (C1) [REFUTED, H.12.1] Switchboard conjecture: H.8.1 implies $F_m(U) \leq 0$ for every hull facet m. Quantitatively, lambda_max(F_m(U)) $\leq$ c sqrt(R(U)) with c ~ 1.8 for facet 82 (Appendix I, numerical).
- (C2) Every three-party binary purification with no operator-first party can be brought, by local unitaries on source and sink and an enlargement of the source, into Switchboard form with the sink recording (o, i). D.1 gives the orthogonal record of (o, i), but not the controlled-unitary structure of the source. If (C1) and (C2) both held, the three-party binary conjecture would follow. Neither is proved, and (C2) is a guess based only on D.1.

Not attempted. Larger sources than $C^8 \otimes C^8$ inside family C (the C_o would then be isometries from a larger S); non-binary alphabets.

H.10 Attacking (C1) directly: flip-superposing boards (Oct 22 2026) [proved parts; hull statement numerical]

Goal: prove that the Pauli rule (H.8.1) forces p_{phi} into conv(PF) for every source state phi, or find an exact counterexample. **Neither was achieved.** Below: three proved negative or structural facts that close natural routes, and an exhaustive exact family of genuinely non-commuting boards that is numerically inside the hull for every facet. No counterexample was found. Code: code/stochastic/cyclic/switchboard/c1/.

H.10.1 No p-preserving twirl reduces to the commuting case [proved]. A common left factor $U_o \to L\, U_o$ preserves the Pauli rule. It preserves every p_{phi} iff L^dag $|i\rangle\langle i|$ L = $|i\rangle\langle i|$ for all i, i.e. iff L = D is diagonal (phases on input strings). Right factors $U_o \to U_o\, W$ preserve the rule but move phi to W phi. But D leaves every projector $P_{o,i} = U_o$^dag $|i\rangle\langle i|\, U_o$ unchanged. So any average over such maps leaves the $P_{o,i}$, and their commutation relations, exactly as they were. A reduction of the Shadows to H.8.4 by symmetrisation is therefore impossible. A proof must handle non-commuting $P_{o,i}$ head-on.

H.10.2 The degree-2 (Shor) relaxation is vacuous [proved]. Relax u = (vec U_0, ..., vec U_7) to a moment matrix $X \succeq 0$ for E[u u^dag]. Then the Pauli rule (linear in the cross blocks E[$U_o \otimes$ conj $U_{o'}$], o ≠ o'), unitarity (linear in the diagonal blocks) and p (diagonal blocks) are all linear in X. Take X block-diagonal, with blocks vec(U_*o) vec(U*_o)^dag for arbitrary unitaries U_*o. All cross blocks vanish, so the rule holds, and p(i|o) = |U*_o[i,0]|^2 is an arbitrary stochastic matrix (even an invalid one). So no degree-2 certificate in the board entries exists for any facet. This parallels C.5 and D.8: certificates must be at least quartic in U.

H.10.3 Pairwise exclusivity characterises binary 3-party PFs [proved, exhaustive]. A backtracking enumeration of all 8^8 maps w: $\{0,1\}^3 \to \{0,1\}^3$ finds exactly 744 maps with "for all o ≠ o', some k in D(o,o') has $w_k(o) = w_k(o')$". These are the 744 PFs. So for single-Pauli boards $U_o = X^{w(o)}$ the Pauli rule is *equivalent* to w being a PF (twoterm.py).

H.10.4 Two-term boards: an exact family of flip-superposing switchboards [proved: structure; numerical: hull]. Let $U_o = \cos(t)\, X^{w1(o)} + i \sin(t)\, X^{w2(o)} = X^{w1(o)} \exp(i\, t\, X^{d(o)})$, with d = w1 xor w2 and $0 < t < \pi/2$. Each U_o is unitary, because X-strings commute and square to 1. This is the simplest board that superposes two different flip patterns, the feature of the Shadows (H.8.5).

- *Rule, exactly.* For o ≠ o', K = $c^2\, X^{a \text{ xor } a'} + s^2\, X^{b \text{ xor } b'} + i\, c\, s\, (X^{b \text{ xor } a'} - X^{a \text{ xor } b'})$. Distinct X-strings are linearly independent, and only the two cross terms can cancel (iff d(o) = d(o')). So the rule says: w1 and w2 are PFs (H.10.3), and for every o ≠ o' either d(o) = d(o'), or both cross strings w2(o) xor w1(o') and w1(o) xor w2(o') are allowed (zero at some k in D). The condition does not depend on t.
- *Enumeration [exact].* There are 40,256 admissible ordered pairs: 744 with w1 = w2 and 39,512 with w1 ≠ w2. 5,208 have d constant, so $U_o = X^{w1(o)}\, W$ with a common W. That is a PF lift with source W phi, a blend by H.8.4 [proved]. The other 34,304 have non-constant d: 20,736 take 2 values, 13,056 take 3 and 512 take 4. In a random sample of 500 of these, all 500 have non-commuting $P_{o,i}$. So H.8.4 does not apply to them.
- *Hull test [numerical].* The family is invariant under the 384 symmetries, giving 237 orbit representatives. For each representative, each t in {pi/12, pi/8, pi/6, pi/4, pi/3, 3pi/8, 5pi/12} and **each of the 29,344 hull facets** (normaliz list, mapped to p-coordinates and verified on all 744 PFs), I computed lambda_min of the

facet operator sum g[i,o] $P_{o,i}$ + g0·1. Its non-negativity means that *every* source state phi gives statistics on the correct side. The minimum over all of these is -1.7e-14, i.e. zero to float64 precision. So every two-term board tested lies in conv(PF) for every source state, including the 34,304 non-commuting ones. This is numerical (a float64 eigenvalue test on a grid in t), not a proof. An exact version would need, per (representative, facet), a 16 x 16 Gram certificate for the univariate matrix form c^2 A + s^2 B + cs C. That is not done.

- *Counterexample status.* None. A counterexample would need a board family not of this form. The continuous search of H.8/Appendix I (all of $U(8)^8$) did not find one either.

H.10.6 Coset-transport theorem; all two-term boards are PF blends [proved]. Let $U_o = X^{a(o)} G_{kappa(o)}$, where kappa partitions the outputs into classes and each G_{kappa} is a unitary in the span of {X^h : h in H_{kappa}} for a subgroup H_{kappa}. Suppose every *class-constant selection* o → a(o) xor $h_{kappa(o)}$, with h_{kappa} in H_{kappa}, is a PF. Then p_{phi} is in conv(PF) for every source state phi, by the explicit decomposition below. *Proof.* Let mu_j = $|phi_j|^2$ and $r_{kappa}(j) = |(G_{kappa}\ phi)_j|^2$. Then p(j xor a(o) | o) = $r_{kappa(o)}(j)$. G_{kappa} is block-diagonal on the cosets j + H_{kappa} and unitary there, so r_{kappa} and mu have equal mass on every coset. Choose a transport plan pi_kappa(j, h) ≥ 0, h in H_{kappa}, with $\sum_h$ pi_kappa(j,h) = mu_j and sum over (j,h) with j xor h = j' of pi_kappa(j,h) = $r_{kappa}(j')$. Such a plan exists because the masses agree coset by coset. Put lambda(j, (h_{kappa})) = mu_j prod_kappa pi_kappa(j, h_{kappa})/mu_j, and let the PF of the term be o → j xor a(o) xor $h_{kappa(o)}$. A translate of a PF by j is a PF. The weights sum to 1, and the marginal at (i, o) is $\sum_j$ pi_{kappa(o)}(j, i xor a(o) xor j) = r(i xor a(o)) = p(i|o). ∎ *Two-term boards.* Here a = w1, kappa = level sets of d = w1 xor w2, and H = {0, d}. coset_check.py checks every class-constant selection exactly, for all 39,512 non-trivial admissible pairs. **The hypothesis holds for every pair** (0 failures). So **every two-term board is a PF blend for every t and every phi** [proved: the theorem above plus an exhaustive exact combinatorial check]. This turns the H.10.4 numerics into a proof, for all pairs and not just the 237 representatives. The hypothesis is genuinely needed: for no pair are all 256 *unrestricted* selections PFs. coset_decomp.py builds the decomposition for 300 random (pair, phi, t) and reproduces p to 7e-16 (sanity check). *Limits.* The theorem also covers any X-type board that satisfies the selection hypothesis. The counterexample of H.12 is an X-type board with 8-term boards for which the hypothesis fails.

H.10.5 What a proof of (C1) must do (written before H.12; (C1) is false). By H.10.1 and H.10.2, it must be non-symmetrising and at least quartic in U. The two-term family suggests the natural next target, which is open: for d(o) taking two values, $U_o = X^{w1(o)} \exp(i\,t\,X^{d(o)})$. Here the boards split into two commuting classes, and p_{phi} should decompose as a blend over a measurement adapted to the two classes. I did not find that decomposition.

H.11 Toward (C2): reducing a general purification to Switchboard form (Oct 22 2026) [partial]

H.11.1 Input copying preserves purity [proved]. Given any purification (V, psi), add a source register T = I and define V' = (CNOT from I to T) V. This copies each input string into the sink, XORed with t. For the parties, this is a local unitary with an ancilla routed from source to sink: party k applies CNOT(I_k → T_k) and then its own unitary. AFNB purity allows such ancillas. So V' is pure, induces the same W on psi ⊗ |0⟩, and its sink holds an exact copy of i.

H.11.2 Generalized switchboards [proved]. Call V a generalized switchboard if $V|o, s, t\rangle = \sum_e |e\rangle_I |o\rangle_{F1} \otimes (C_o(s))_{\{e\}} \otimes |e \text{ xor } t\rangle$, where each $C_o : S \to I \otimes F'$ is unitary and F' is any extra sink. The proof of H.7.1/H.8.1-H.8.2 goes through block by block: V is pure (with or without ancillas) iff, for every $o \neq o'$ and every pair of F' basis labels (f, f'), the 8 x 8 block $K^{f\,f'}$ of $C_o\, C_{o'}\text{^dag}$ satisfies the Pauli rule. The row inner products factor exactly as before, with the F' labels as spectators. H.8.3 also carries over, with "scalar" replaced by "acts only on F'". **So (C1) for generalized switchboards is the operator-valued Pauli rule.**

H.11.3 The gap [open]. After H.11.1, a purification is a generalized switchboard iff some sink unitary makes the sink record o *for every source state s*, not only for psi. D.1 gives the orthogonal record of (o, i) on psi alone. Purity constrains V on all of P, but I found no argument that it forces an o-record off psi, and no counterexample. Every purification constructed so far has one (single-PF lifts, C.1 lifts, families A-C). So (C2) is reduced to: **does every pure V that purifies a classical W admit a sink unitary under which o is recorded on every source state?** Not proved.

H.11.4 Per-machine recording is false [proved]. Take a coherent control: a source qubit r, passed on to the sink, with $V = |0\rangle\langle 0|_r \otimes V0 + |1\rangle\langle 1|_r \otimes V1$. Here V0 is a PF lift (it records o) and V1 is a pure comb $A \to B \to C$ ($I_B = O_A$ and $I_C = O_B$ wired, I_A from the source, O_C to the sink), which does not record o_A or o_B. V is pure, since the induced map is $|0\rangle\langle 0| \otimes M0 + |1\rangle\langle 1| \otimes M1$. On the source $|0\rangle_r \otimes$ psi it purifies the classical W of V0. On $|1\rangle_r \otimes s$, the values o_A and o_B end up in the parties' inputs, not the sink, so no sink unitary can record them. So "every purification records o on every source state" (H.11.3) is false. A reduction must first restrict the source to a suitable subspace containing psi. Whether such a sub-purification always exists is open. After H.12 this question no longer decides the conjecture, which is false. It remains a question about the shape of general purifications.

H.12 A purifiable classical process outside the PF hull: the purification conjecture is false (Oct 22 2026) [proved: exact arithmetic + paper proofs; independently re-derived (H.12.2); Lean-checked; the two original gaps are closed (H.12.3, H.19)]

Theorem H.12.1. There is a valid three-party binary classical process p with an AFNB purification (a pure process, i.e. unitary under all local unitaries with arbitrary finite ancillas; for this machine, equivalently, with ancillas in arbitrary Hilbert spaces, H.19.3) such that p is **not** a mixture of process functions. So the "only if" half of the conjecture of Section 9 is false, and so is (C1) of H.9. This is the main result of the note (Theorem 9.1).

The machine. It is a Switchboard (family C, H.7) with X-type boards. Let Hd be the 3-qubit Hadamard. Put $U_o = \text{Hd diag}(i^{m_o(z)})\,\text{Hd}$, so U_o acts diagonally in the Hadamard basis $|z\text{^}\rangle$. The exponents $m_o(z)$ in {0,1,2,3}, for z = 000, ..., 111 in binary order, are:

o	$m_o(z)$
000	0 3 0 0 2 0 3 0
001	0 3 2 2 2 0 3 0
010	0 3 0 0 2 1 3 1
011	0 3 2 2 2 1 3 1
100	0 1 2 2 2 2 1 2
101	0 1 0 0 2 2 1 2
110	0 1 2 2 2 3 1 3
111	0 1 0 0 2 3 1 3

$V|o, s, t\rangle = \sum_e U_o[e, s] |e\rangle_I |o\rangle_F |e \text{ xor } t\rangle_F$. The source state is phi $\otimes |0\rangle_T$, with phi = $(|011\rangle + e^{-i\ pi/4} |100\rangle)/\text{sqrt } 2$, and $p(i|o) = |\langle i|U_o \text{ phi}\rangle|^2$.

Verification (code/stochastic/cyclic/switchboard/c1/exact_cex.py, log exact_cex.log; all in exact rational arithmetic in Q(zeta_8), no floating point):

1. Every U_o is unitary.
2. All 2,232 forbidden Pauli coefficients of all $K_{o,o'}$ ($o \neq o'$) are exactly 0, so the Pauli rule H.8.1 holds. By H.8.1 (equivalence with H.7.1), H.7.1 and H.8.2, V is pure with and without ancillas. These are paper proofs, not Lean.
3. p is real with entries in Q(sqrt 2) (cex_p_exact.json). Every column sums to 1, and all 64 deterministic local interventions give total probability exactly 1. So p is a valid classical process.
4. Facet 1741 of the normaliz list, mapped exactly to p-coordinates, gives an integer inequality $g.p + g0 \geq 0$. It is checked exactly on all 744 PFs, is tight on 418 of them, and hence holds on conv(PF). On p it equals **1/4 - (3/16) sqrt 2 < 0**. So p is not in conv(PF).

Independent checks [numerical, not needed for the proof] (direct_purity.py, verify_cex.py, cex_structure.log):

- Direct simulation without using H.7.1/H.8: over 30 Haar samples with ancilla dimensions 1-3, max |M M^dag - 1| = 2.7e-15 and max |M^dag M - 1| = 2.6e-15. V itself is unitary.
- Simulating all 64 deterministic interventions through V (party unitaries $|i,x\rangle \to |f(i) \text{ xor } x, i\rangle$) reproduces p(i|f(i)) to 1.3e-15.
- LP distance from p to conv(744 PFs) is 0.0607 (L1). Over source states the largest is 0.828 = 2(sqrt 2 - 1), at the top eigenvector of the facet operator.
- No party is operator-first (residuals 0.31 / 0.25 / 0.31), the causal graph is complete, and every U_o has full X-support (8 Pauli terms). This is consistent with H.6 and H.10.6: the coset hypothesis fails for it.

How it was found. The search of H.8/Appendix I over all of $U(8)^8$ never got below $R \sim 0.31\ v^2$. Restricting to X-type boards (64 phases, xtype.py) gave exactly pure boards with facet violations straight away (xtype.jsonl, e.g. xt_0_20_0.npy: R = 1e-18, LP distance 0.44). Snapping the phases to multiples of pi/4 (snap.py) kept purity and violation, and the snapped phases turned out to be multiples of pi/2, giving the table above. **So the Appendix I quadratic floor was an artefact of local optimisation, and is withdrawn.**

What survives. The "if" half (C.1). The classical version D.6, which says *classical* reversible purifiability gives exactly the PF hull. Two parties (G). All the structural theorems (H.1, H.2, H.6, H.8, H.10.6). The exact non-purifiability certificates for E_{ex1} and orbits 7 and 50 (C.2). The corrected statement: **quantum purifiability is strictly weaker than being a mixture of process functions, already for three binary parties, and the gap is witnessed by a Switchboard with no operator-first party.** Open: the exact purifiable set; whether it is a polytope; whether the vertex orbits 8, 10, 20 and the other sampled orbits are purifiable after all; and the reach of X-type boards.

H.12.2 Independent re-derivation [exact, with float cross-checks]. A separate verification, code/stochastic/cyclic/switchboard/verify_h12/verify.py (log verify.log), was written from the text of this section alone and uses none of the code above.

- (0) Each 8U_o has Gaussian-integer entries, and (8U_o)(8U_o)^dag = 64·1 exactly.

- (2a) Purity is checked directly, not via H.7.1/H.8. The induced map is multi-affine in the three local operations, so purity reduces to an exact identity over 125 slot combinations. The result is PASS.
- (2b) 1,200 random trials, with isometries and ancilla dimensions 1 to 5, give max |M^dag M - 1| = 2.0e-15 [numerical]. A control with board 000 perturbed gives 3e-2, as it should.
- (3) p ≥ 0 and its columns sum to 1, exactly. All 64 deterministic interventions give total probability exactly 1, which covers all local stochastic interventions by multi-affinity.
- (4) The 744 PFs are re-enumerated by brute force over all 8^8 maps. The paper inequality has minimum 0 on them, is tight on 418, and takes the value 1/4 - (3/16) sqrt 2 on p. The referee's own rational separating inequality takes the value 1 - (3/4) sqrt 2 < 0 on p and is verified exactly on all PFs. The membership LP is infeasible.
- (5) A full circuit simulation reproduces p to 2.2e-16 [numerical].

H.12.3 Lean formalisation [proved in Lean 4 + Mathlib; the two original gaps are closed, see Gaps]. lean/PFUL/CounterexampleData.lean and lean/PFUL/Counterexample.lean (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/STATUS.md, Round 6) prove

```
theorem purification_conjecture_false :
  ∃ p, Valid p ∧ Purifiable p ∧ p ∉ convexHull ℝ PFset
```

The only axioms are propext, Classical.choice and Quot.sound. There is no `sorry` and no `native_decide`; finite computations use `decide +kernel`. The definitions, all in that file, are as follows.

- `IsPure V`: for every family of finite ancilla types a_k and every local unitary A_k on Bool × a_k, the link product `compose V A` is unitary.
- `Purifiable p`: some pure V on a 64-dimensional source and sink, with a normalised source state, induces p via $p(i|o) = \Sigma_f |\langle i,f|V|o,\psi\rangle|^2$.
- `Valid p`: p ≥ 0, and total probability is 1 under every product of local stochastic maps.
- `PFset`: the 0/1 points of maps w with a unique fixed point for every local deterministic intervention.

The key lemmas are as follows.

- `board_mem_unitaryGroup`: each U_o = Hd·diag(i^m)·Hd is unitary.
- `isPure_Vsb`: the Switchboard is pure. The proof is a direct multilinear reduction, independent of the paper's H.7.1/H.8.2.
- `valid_pcl`.
- `Lg_nonneg_of_isPF` and `Lg_pcl_neg`: L(p) = (32 - 24 sqrt 2)/128 < 0.
- `pcl_not_mem_convexHull`.
- `purifiable_pcl`.

Gaps (status Oct 24 2026). As first stated, the result had two gaps: (i) ancillas range over finite types only; (ii) `Valid`, `Purifiable` and `PFset` are defined in that file and not linked to the general framework. Both are now closed.

- (i) Infinite ancillas. Round 9 (`CounterexampleInf.lean`) gave an isometry for countable ancillas. Round 10 (`isUnitaryInf_Vsb`) made it a unitary, using orthonormal rows. Round 11 (`isUnitaryKer_Vsb`, `isUnitaryAll_Vsb`) extended this to ancilla index sets of any cardinality,

with unitary kernels and no boundedness assumed. Round 12 adds abstract Hilbert spaces (`isPureHilbert_Vsb`, with `isPureHilbert_iff_isUnitaryKer` for every V) and validity under normal CPTP channels on countable ancillas (`valid_normalCPTP_Vsb`). Round 13 removes countability (`valid_normalCPTP_Vsb_any`), proves for every V that finite-ancilla purity implies Hilbert-ancilla purity (`isPure_iff_isPureHilbert`), and gives a link product over ancillas of any cardinality equivalent to the finite one (`isValidPMInf_iff`, `isPurePMInf_iff`). See H.19.3, H.19.5 and H.20.

- (ii) The framework. Earlier rounds linked the process functions (`isPF_iff`, `valid_pfPoint_iff`) and showed that purity depends only on the Choi vector (`compose_eq_link`). Round 12 adds a general process-matrix framework with the link product (`lean/PFUL/ProcessMatrix.lean`) and proves that `Valid`, `IsPure` and `PFset` agree with it (`isValidPM_Wcl_iff`, `isPure_iff_unitaryLink`, `isValidPM_Wcl_pfPoint_iff`). It also restates the theorem in that framework (`purification_conjecture_false_choi`); see H.19.1–H.19.2.

Gaps (a)–(d) of Section 9 are closed in Lean (H.20); the remaining caveats are listed there.

Caveat (revised). The purity step now has three supports. The first is the paper proofs of H.7.1 and H.8.1-H.8.2, with the exact Pauli check. The second is the referee's direct exact criterion (H.12.2). The third is the Lean proof `isPure_Vsb` (H.12.3). None of the three has been peer reviewed. The earlier recommendation to formalise before announcing has been met, subject to the remaining formal gaps listed in Section 9.

Quadratic robustness near facet 82 (Appendix I) [false: H.12 has R = 0 and a facet violation]. A proof of $v \le c\sqrt{R}$ would imply (C1) for facet 82 at R = 0. None of the routes above gives it. H.10.2 shows that any SOS proof must be at least quartic in U.

H.13 Toward the purifiable set: exhaustive Z_4 X-type boards, a rational counterexample, convexity (Oct 22 2026) [proved: H.13.1, H.13.2 (exact rational arithmetic); numerical: H.13.3-H.13.4]

Code: code/stochastic/cyclic/switchboard/h13/ (xenum.py, canon.py, analyze.py, simple_phi.py, exact_rational.py; logs *.log). Write Purif for the set of purifiable three-party binary classical processes (any finite source and sink), Valid for the valid polytope.

H.13.1 Purif is convex, and conv(PF) ⊊ Purif ⊊ Valid [proved]. Let V_1, V_2 purify p_1, p_2. Add a control qubit c to the source, prepared as $\sqrt{\lambda}|0\rangle + \sqrt{1-\lambda}|1\rangle$, and route it straight to the sink. Set $V = |0\rangle\langle 0|_c \otimes V_1 + |1\rangle\langle 1|_c \otimes V_2$, padding the smaller one with an idle register. Composing V with any local operations A gives $|0\rangle\langle 0| \otimes (V_1 \circ A) + |1\rangle\langle 1| \otimes (V_2 \circ A)$. That is block diagonal with unitary blocks, so V is pure. The parties never touch c, and tracing the sink gives $\lambda p_1 + (1-\lambda)p_2$. So Purif is convex. It contains conv(PF) (C.1) and is strictly larger (H.12, H.13.2). It is strictly smaller than Valid: the exact certificates of C.2 (E_{ex1}, orbits 7 and 50) are valid but not purifiable. ∎ The same argument shows that, for one fixed board family, the set of p it induces over all source states (mixed sources allowed) is a linear image of the 8x8 density matrices. Purif contains the convex hull of these spectrahedral shadows. Whether Purif is a polytope is open.

H.13.2 A rational, real counterexample with half the Pauli support [proved; exact rational arithmetic, no irrationals]. Take $U_o = Hd \cdot \mathrm{diag}((-1)^{n_o(z)}) \cdot Hd$ with $n_o(z) \in \{0,1\}$. Rows o = 000..111, columns z = 000..111:

o	$n_o(z)$
000	0 0 0 0 0 0 0 0
001	0 0 1 1 1 1 1 1
010	0 0 0 0 1 0 1 0
011	0 0 1 1 0 1 0 1
100	0 0 0 1 0 0 0 1
101	0 0 1 0 1 1 1 0
110	0 0 0 1 1 0 1 1
111	0 0 1 0 0 1 0 0

Each U_o is a real orthogonal matrix with entries in (1/4)Z. Each $U_o\ U_{000}{}^T$ has 4 X-Pauli terms; the H.12 board has 8. Take the source phi = (|000⟩ + |001⟩ + |010⟩ - |101⟩)/2. Then $p(i|o) = (U_o\ phi)_i{}^2$ has entries in {0, 1/16, 1/4, 9/16} (table in exact_rational.log). exact_rational.py checks the following in Fraction arithmetic only.

- (1) Every U_o is orthogonal.
- (2) All 2,232 forbidden Pauli coefficients vanish, so the board is pure with and without ancillas (H.8.1-H.8.2).
- (3) p is valid: all 64 deterministic interventions give total probability 1.
- (4) Facet 16962 (orbit 91; tight on 436 PFs, range 2 on PFs) takes the value **-1/8** on p.

The source (|000⟩ + |001⟩ + |010⟩)/sqrt 3 also gives a rational p, and that p violates facets 16962 and 15629 by -1/12. **So irrational phases, Z_4 phases and full Pauli support are all inessential: ±1 phases and 4-term transitions suffice.** By H.10.6, two-term boards cannot do this, so 4 terms is within one of the minimum. Whether 3-term X-type boards can violate a facet is open; none of the Z_4 boards below does.

H.13.3 Exhaustive Z_4 X-type enumeration [exact enumeration; violations numerical]. Fix the gauge $m_{000} = 0$ (a common right factor is absorbed into phi) and $m_o(000) = 0$ (global phases). The Pauli rule for X-type boards says: the Walsh-Fourier transform of $i^{m_o - m_{o'}}$ vanishes on every $a \supseteq D(o,o')$. These are integer tests. Backtracking over the cube (xenum.py, exact) gives **exactly 13,105 pure Z_4 X-type boards**. Modulo output flips, party permutations and complex conjugation, they fall into 386 classes (canon.py). For each class, analyze.py computes max over phi of the violation of all 29,344 facets, as $-\lambda_min(\Sigma\ g \cdot P_{o,i} + g_0)$ divided by the facet's range on PFs [numerical, float64].

- 12 of the 386 classes (216 boards) leave conv(PF). 2 of the 27 classes with real (±1) phases do; H.13.2 is one of them.
- No board whose transitions have at most 2 X-terms violates any facet, which is consistent with H.10.6. The violating classes have at most 4, 5 or 6 terms per transition (gauge $m_{000} = 0$).
- The largest relative violation is **0.1404**, on orbit 91, reached by the ±1 class of H.13.2 at its optimal (irrational) phi. Facet orbit 82 (the H.12 facet) reaches 0.1036.

H.13.4 Which facets purifiable processes violate [numerical, within Z_4 X-type boards]. 62 of the 93 facet orbits are violated by some board. The following 31 orbits are never violated in this family: 4-11, 14, 16, 19, 21, 24-31, 52-54, 57, 66, 67, 69, 75, 79, 81, 92. They are candidates for facets that remain valid on Purif. (Orbit 92 is the positivity orbit $p(i|o) \geq 0$ and holds trivially; see H.17.5.) Maximum relative violation per violated orbit:

- 0.14: orbit 91.

- 0.10: orbits 82-84.
- 0.09: orbits 40, 45-47, 60, 61, 76, 78.
- 0.05-0.06: orbits 36-39, 41-44, 50, 51, 58, 59, 62, 63, 72, 73, 86-89.
- 0.02-0.04: the rest. This is a lower bound on the violation over Purif, not the maximum. General boards, larger phase groups and non-X-type boards were not enumerated.

Partial characterization (status). Proved: Purif is convex, with conv(PF) ⊊ Purif ⊊ Valid. Two-term boards stay inside conv(PF) (H.10.6). The commuting/monomial boards do too (H.8.4). Four-term ±1 boards can leave it (H.13.2). Not proved: three-term boards; whether the 31 unviolated orbits are valid on all of Purif; whether Purif is a polytope; whether X-type boards already give all of Purif.

H.13.5 Relation to Kunjwal-Oreshkov antinomicity [proved: exact rational decomposition; literature CITED, verified from arXiv:2307.02565v3 on Oct 23 2026]. Kunjwal and Oreshkov (ref. 36) call correlations *nomic* if they arise from classical processes in conv(PF), with arbitrary classical local operations, and *antinomic* otherwise. Two passages bear on this note.

- They observe that classical processes outside conv(PF) "fail to be reversibly extendible" (citing Baumeler's PhD thesis, ref. 30; compare D.6).
- They ask, as an open question: "can correlations realizable via unitarily-extendible process matrices display antinomicity?"

The boards of H.12 and H.13.2 are *quantum* unitary extensions of classical processes outside conv(PF). By the remark above, those processes have no classical reversible extension, so here quantum reversibility reaches classical processes that classical reversibility cannot.

This does not resolve their question. Being outside conv(PF) is a statement about the process p(i|o) on its fixed binary alphabets. Nomic correlations allow local operations that use a party's own setting and hidden alphabets of up to four values. We checked the correlation P(x|a) := p(i=x|o=a) of H.13.2, obtained with identity classical instruments, in the (3,2,2) scenario.

- We enumerated the nomic vertices with K-O Theorem 4: 152,128 deterministic correlations whose faithful process function has $|I_k| \leq 4$. As a sanity check, the maximum GYNIN score over them is 5/8, which matches K-O Eq. (102).
- The H.13.2 correlation **lies in the nomic polytope**. An LP finds a decomposition with 23 vertices. Resolved in Fraction arithmetic, it has rational weights in {1/144, 1/48, 1/24, 1/18, 1/16} and reproduces P exactly.

Code: code/stochastic/cyclic/nomic/ (nomic_check.py, nomic_check.log). So the H.13.2 correlation is nomic (though, by H.15.7b, not causal). The H.12 correlation and other quantum instruments on these boards have not been tested. Whether any instruments on a purifiable board give antinomic correlations remains open.

Update (H.15.7e, H.15.8). The H.13.2 board is the time-reversed Lugano process of Guérin and Brukner (ref. 38), up to local unitaries on the agent wires and the source and sink. In the computational basis that process induces a PF mixture; in the Hadamard basis it induces the H.13.2 process outside conv(PF). The nomic-polytope check above concerns the latter reading only. Kunjwal and Oreshkov's question is unaffected.

H.14 Three-term boards, wider phase groups, exact per-orbit maxima (Oct 22 2026) [proved: H.14.1, H.14.2; exact algebraic values: H.14.3; numerical: H.14.4]

Code: code/stochastic/cyclic/switchboard/h13/ (z8enum.py, canonN.py, analyzeN.py, cert_z8.py, exactmax.py, threeterm.py; logs alongside).

H.14.1 X-type boards with at most three terms are PF blends [proved]. Call a board X-type k-term if there is a common unitary W such that every U_o W is a combination of at most k X-strings. (W only moves the source: phi → W^dag phi.)

(a) No X-type unitary has exactly three terms. Suppose U = X^a(α + βX^u + γX^v), with u, v, u xor v distinct and nonzero. Its eigenvalues are α + βχ(u) + γχ(v), over the four sign pairs (χ(u), χ(v)) ∈ $\{\pm1\}^2$. Unitarity needs all four to have modulus 1. Comparing them pairwise gives Re(αβ̄) = Re(αγ̄) = Re(βγ̄) = 0. Read α, β, γ as vectors in R^2: they would then be pairwise perpendicular, which is impossible when all three are nonzero. ∎

So an X-type ≤3-term board has $U_o = X^{a(o)} G_o$, with G_o = α_o 1 + β_o $X^{d(o)}$ (unitary iff Re(α_o β̄_o) = 0 and $|\alpha_o|^2 + |\beta_o|^2 = 1$).

(b) Theorem. Every such board gives p_{phi} ∈ conv(PF) for every phi. This generalises H.10.6: t, the phases and d may all vary with o.

Proof. Put o and o' in the same class when $G_{o'} \propto G_o$. If $G_{o'} \propto G_o X^d$, rewrite a(o') → a(o') xor d, which puts o' in the same class. Then:

- Same class: K = $X^{a \text{ xor } a'}$, and the rule makes a xor a' allowed.
- Different classes with the same d: G G'^dag has both 1 and X^d with nonzero coefficients, so a xor a' and a xor a' xor d are both allowed.
- Different d, both two-term: the four strings a xor a', a xor a' xor d, a xor a' xor d', a xor a' xor d xor d' are distinct with nonzero coefficients. So all four are allowed. One-term classes are the special case β = 0.

Hence every class-constant selection o → a(o) xor $h_{\kappa(o)}$, with h_κ ∈ {0, d_κ}, is pairwise exclusive on every pair (o, o'). By H.10.3 (exhaustive and exact: pairwise exclusivity ⇔ PF), it is a PF. The coset-transport construction of H.10.6, with H_κ = {0, d_κ}, then writes p_{phi} as a PF blend. ∎

This replaces the enumeration in H.10.6 with a proof that uses no computer apart from H.10.3. With H.13.2, the threshold for X-type boards is now exact: **≤3 terms always blend, and 4 terms can violate the hull.**

(c) General (non-X) three-term unitaries [proved form; hull question open]. Write U = αP + βQ + γR with Paulis P, Q, R, so P^dag U = α + βA + γB.

- If A and B commute, the argument of (a) applies, so U has at most 2 terms.
- If A and B anticommute, unitarity forces U ∝ P exp(i t(cos f A' + sin f B')) with Hermitian A' ∝ A and B' ∝ B.

A left Z-string factor leaves p unchanged but does change the Pauli rule. So Paulis with Z components genuinely enlarge the family. threeterm.py anneals over the discrete structure (P_o, A_o, B_o) to satisfy the rule identically. In 30 runs over 7 seeds it never reached an admissible board with genuinely anticommuting terms: the residual stayed at 15-22 [numerical, inconclusive]. **Whether non-X three-term boards can leave the hull is open.**

H.14.2 Z_8 boards violate 8 of the 31 orbits that Z_4 never violated (full tables in Appendix J) [proved; exact arithmetic in Q(ζ_8)]. z8enum.py enumerates pure Z_8 X-type boards with the same gauge as H.13.3 and an exact integer Pauli test (in the basis 1, ζ, ζ^2, ζ^3 of Z[ζ_8]).

- There are exactly **500,081** boards, in 10,603 classes. As a cross-check, the same code with N = 4 gives the H.13.3 count 13,105.
- Float screen: 88 classes violate. Of these, 76 use odd powers of ζ_8. They reach 70 of the 93 orbits.
- cert_z8.py certifies the following exactly for class 10515, phases ζ_8^m with m given in cert_z8.log:
  - unitarity;
  - the Pauli rule, so the board is pure;
  - validity, for a Gaussian-rational source vector v;
  - a negative facet value of the form a + b sqrt 2, for **orbits 16, 19, 21, 24, 27, 29, 52 and 67**.
- The relative violations are 0.0021, 0.0019, 0.0021, 0.0014, 0.00026, 0.00025, 0.00057 and 0.00057.
- Remaining **never-violated orbits (23):** 4-11, 14, 25, 26, 28, 30, 31, 53, 54, 57, 66, 69, 75, 79, 81, 92. Orbit 92 is positivity (H.17.5), so 22 are genuine.
- Z_8 also raises the maxima on orbits 34, 35, 37, 38, 42, 44, 49 and 71, by 2-7% [numerical]. The overall maximum, 0.1404 on orbit 91, does not move.

H.14.3 Exact per-orbit maxima over Z_4 X-type boards [exact algebraic numbers for float-selected maximisers]. For each violated orbit, take the (class, facet) with the largest float violation. Its maximum over source states is -λ_min(F), and λ_min is an exact root of the integer characteristic-polynomial factor in exactmax_part{1,2}.log (flint/sympy, from an exact rational facet g). Examples:

- Orbit 91: λ = (3 - sqrt 17)/4 on range 2, so relative violation **(sqrt 17 - 3)/8 ≈ 0.14039**.
- Orbits 82-84: root of $4x^2$ - 4x - 1, so **(sqrt 2 - 1)/4 ≈ 0.10355**.
- Orbits 60, 61, 76, 78: root of $2x^2$ - 3x - 1, on range 3, so **(sqrt 17 - 3)/12 ≈ 0.09359**.
- Orbits 32-35, 48, 49, 70: root of $4x^2$ - 8x - 1, on range 4, so **(sqrt 5 - 2)/8 ≈ 0.02951**.
- The other orbits have roots of quartics up to octics.

These are exact values of the maximiser that the float screen picked. They are exact family maxima only up to that float argmax over (class, facet), and they are maxima for Z_4 boards, not for Purif (Z_8 already exceeds them on 8 orbits).

H.14.4 Is Purif a polytope? Do X-type boards generate it? [evidence only].

- For every orbit checked, the maximiser's optimum is irrational: a root of an irreducible polynomial of degree ≥ 2 (H.14.3). So each board's region is a curved spectrahedral shadow.
- The certified violations grow from Z_2 to Z_4 to Z_8: 2, then 12, then 88 violating classes; 62, then 70 orbits. Nothing has saturated.

This suggests, but does not show, that Purif (convex by H.13.1) is not a polytope, and that finite phase groups only approximate it. No proof either way. Whether non-X-type or ancilla boards add anything beyond X-type is open.

H.15 What the results mean in spacetime (Oct 23 2026) [labels: PROVED = this paper; CITED = verified from the arXiv primary source on Oct 23 2026; INTERPRETIVE = our reading, not a theorem]


H.15.1 The cited embedding framework [CITED].

- Baumeler, Costa, Ralph, Wolf and Zych (arXiv:1703.00779, CQG 36, 224002 (2019); ref. 16) model classical deterministic dynamics as follows:
  - There are N compact, CTC-free "local regions" with spacelike past and future boundaries. They sit in an arbitrary Lorentzian manifold and may be traversed by CTCs.
  - An agent in region R applies any function f_R from the past-boundary state to the future-boundary state.
  - The exterior dynamics is a function w: O → I from future boundaries to past boundaries. Consistency with free local choice is exactly "w∘f has a fixed point for every f", and the fixed point is then unique (their Thm 1). These w are the process functions (PFs) of this paper.
  - Their Thm 2: every PF extends to an invertible one by adding a source region (output only, "in the past" of all regions) and a sink region (input only, "in the future"). They describe realisations by reversible interactions inside the CTC region (Fig. 3), for example billiard-ball logic.
  - Their Thm 3: three regions form a PF iff fixing any one output leaves at most one-way signalling between the other two. Three parties can each be both in the past and in the future of the others.
- Tobar and Costa (arXiv:2001.02511, CQG 37, 205011 (2020); ref. 28) extend this to N regions, with inequivalent four-party PFs. They sketch a wormhole spacetime with pairwise-identified mouths and a billiard-ball computer that implements any PF (their Fig. 3).
- Baumeler and Wolf (arXiv:1507.01714, NJP 18, 013036 (2016); ref. 15) show that the logically consistent classical processes form a polytope. For three binary parties it is 37-dimensional, with 64 facets and 710,760 vertices, of which only 744 are deterministic (the PFs); the rest are non-deterministic. conv(PF) is their separate, strictly smaller "deterministic-extrema polytope" (744/8 = 93 classes). Processes outside it are, in their words, fine-tuned: every decomposition into deterministic processes uses logically inconsistent ones. [CITED; corrected Oct 23 2026: the earlier wording "the deterministic ones are its extremal points" wrongly suggested that all vertices are PFs.] Ref. 16 adds that non-deterministic classical processes need not have a classical reversible extension (its ref. [33]).
- Oreshkov, Costa and Brukner (arXiv:1105.4464, ref. 14) define process matrices from local quantum mechanics alone. They note that any process can be read as a CPTP map from the parties' outputs back to their inputs, "having the form of a CTC". They also show that bipartite classical processes are causally separable.
- Araújo, Feix, Navascués and Brukner (arXiv:1611.08535, Quantum 1, 10 (2017); ref. 17) add a global past P and future F:
  - A process is pure iff it maps local unitaries to a unitary P → F (their Thm 2: $W = |U_w\rangle\langle U_w|$).
  - The purification postulate: a process is physical only if it is part of a pure process. The motivation is reversibility of fundamental dynamics.
  - They exhibit a purifiable tripartite classical process that violates causal inequalities (their Sec. 7, the Lugano-type function).
- Lloyd et al. (arXiv:1005.2219, ref. 13) and Deutsch (ref. 10; Phys. Rev. D 44, 3197, journal version, not fetched here) give the P-CTC and D-CTC models. Ref. 16 (Sec. VII) states two comparisons. P-CTCs agree with the unitary-process predictions for valid unitary processes, but allow general unitaries at the price of nonlinearity and restricted local operations. D-CTCs allow arbitrary local operations but predict nonlinear evolution.
- Vilasini and Renner (arXiv:2203.11245, PRA 110, 022227 (2024); erratum PRA 114, 029903 (2026); companion letter PRL 133, 080201 (2024)) treat fixed acyclic spacetimes, Minkowski included. Theorem numbers [CITED]: Thm 3 (not fixed-order iff the signalling structure certifies cyclicity), Thm 4 (no-go: not

fixed-order + relativistic causality + acyclic region structure is impossible), Cor 1 (no localisation of all in/outputs), Cor 2 (no time localisation in one global frame), Thm 5 / Cor 3 (a fine-grained fixed-order, hence causally separable, explanation with $M = \sum_k |R^{A_k^I}| \geq N$ agents). Their systems are finite-dimensional and finite in number. Note that this no-go is due to Vilasini and **Renner**; the Colbeck papers are cited next. Relativistic causality is a compatibility condition between an information-theoretic structure and an acyclic spacetime. Realisations of indefinite-causal-order processes in such a spacetime (a) necessarily non-localise systems, and (b) admit a definite, acyclic causal-order explanation at a fine-grained level.

- Vilasini and Colbeck (arXiv:2109.12128, PRA 106, 032204 (2022); arXiv:2206.12887, PRL 129, 110401 (2022)) show that forbidding superluminal signalling alone does not rule out causal loops embedded in Minkowski space. They left open whether such loops are possible in 3+1 dimensions. **Update [CITED]:** Grothus and Vilasini (arXiv:2606.20476, 2026) prove that in every "conical" spacetime, including (d+1)-Minkowski for d > 1, all compatible embeddings of affects causal loops are degenerate (their Thm 1), in classical, quantum and post-quantum theories. Background: Grothus-Vilasini, CQG 43, 105008 (2026), arXiv:2403.00916.
- Further follow-ups [CITED, abstracts checked]: Salzger and Vilasini (arXiv:2404.05319, NJP 27, 023002 (2025)) map every QC-QC to a causal box on Fock space that is a fine-graining with acyclic order. Salzger and Selby (arXiv:2411.08266, Quantum 10, 1959 (2026)) define embeddability of a process via one of its decompositions. Ormrod, Vanrietvelde and Barrett (arXiv:2204.10273, Quantum 7, 1028 (2023)) show photonic quantum switches have cyclic coarse-grained but acyclic fine-grained causal structure, without assuming spacetime localisation. Vanrietvelde, Ormrod, Kristjánsson and Barrett (arXiv:2206.10042, Quantum 9, 1923 (2025)) build consistent processes from routed circuits, including Lugano, and conjecture that every unitarily extendible process arises this way. Tselentis and Baumeler (PRX Quantum 4, 040307 (2023)) give the siblings-on-cycles criterion for admissible causal structures.
- Paunković and Vojinović (arXiv:1905.09682, Quantum 4, 275 (2020)) show that every circuit can be immersed in a classical spacetime. Quantum-switch experiments in fixed spacetimes do not feature superposed causal orders; only a gravitational switch would.

H.15.2 Dictionary: our objects as spacetime objects [INTERPRETIVE, built on ref. 16's set-up].



```
    |   +--+------+------+--+
    |   |  source region S  |  prepares phi (the H.12 / H.13.2 state)
    |   +-------------------+
```

- *Parties.* A, B and C are ref. 16's local regions with binary inputs and outputs. Their classical inputs i_k and outputs o_k are the states on their past and future boundaries.
- *Source.* S is ref. 16's output-only region. Here it prepares a quantum state phi of the loop medium instead of a classical string. (In H.13.2, phi = (|000⟩+|001⟩+|010⟩-|101⟩)/2.)
- *Boards.* The family $\{U_o\}$ is the unitary dynamics of the CTC region, conditioned on what the three agents emitted. Physically it is a scattering process in which the carriers sent by A, B and C (the controls o) act coherently on the loop medium before it is re-emitted, through the mouths, into the past boundaries as the inputs i.
- *Sink.* F receives what leaves the loop (the record of o and the scattered medium). Purity (H.8.2) says that S → F is unitary for every choice of local unitaries, with or without the agents' private ancillas.
- *Classical process p(i|o).* It is what the three agents see when each measures their input in the computational basis, as in ref. 31's fixed-basis setting.

H.15.3 What each result says in spacetime terms.

1. *Purifiability = reversible, information-preserving loop dynamics [CITED definition + INTERPRETIVE reading].* Following ref. 17, a purification is a closed quantum system: everything that enters through S and through the agents' futures leaves through F and the agents' pasts, unitarily. Nothing is erased in the CTC region, so all irreversibility sits inside the agents' labs. Classically, ref. 16 Thm 2 shows that every PF is reversible in this sense, and D.6 shows that classical reversibility gives exactly conv(PF).

2. *The counterexamples (H.12, H.13.2) [PROVED] give a quantum time-travel signature [INTERPRETIVE].* p lies outside conv(PF). So no mixture of deterministic, self-consistent, classical CTC histories of the ref. 16 / ref. 28 kind reproduces these statistics. That includes every billiard-ball model with hidden random initial conditions. Reversible quantum loop dynamics does reproduce them.

   A facet inequality $g \cdot p + g0 \geq 0$ is then an operational witness. The three agents feed in deterministic local strategies, histogram their inputs, and evaluate the facet. A negative value, for example -1/8 for H.13.2, certifies that the loop is not a classical mixture of consistent histories. The rational counterexample needs only real ±1 phases, so the witness does not depend on complex amplitudes. The signature is quantum superposition of flip patterns, not complex phases.

   This is a stronger statement than "non-causal": the Lugano PF is already non-causal and fully classical (refs. 15-17). The H.12 statistics are non-causal *and* non-classical-deterministic. Caveat: the witness assumes that the agents' operations are the classical local operations of the model (ref. 16 Sec. III) and that the statistics are gathered over many runs.

3. *No first party (H.6.2) [PROVED].* Any purification of a process outside the hull has no operator-first party. In spacetime terms [INTERPRETIVE], no agent's input carrier can bypass the scattering. **Corrected Oct 23 2026:** this is an operator-level statement only. At the level of statistics, the H.13.2 process with phi = (|0⟩+|1⟩+|2⟩-|5⟩)/2 has B *marginally first*: B's input does not depend on any output [EXACT-CERTIFIED, H.15.6]. So relativistic causality, which constrains signalling only, allows B's region to sit in the causal past

of A and C. What is excluded is that B's input is uncorrelated with the loop: by Theorem H.2 the A-C loop conditioned on (i_B, o_B) cannot be valid, and the check finds 32 invalid conditionals.

4. *Pauli rule (H.8.1) [PROVED] as a locality/consistency law of the loop [INTERPRETIVE].* When the outputs of the agents in a set D change, the change in the loop dynamics, $K = U_o\ U_{o'}$^dag, must lie in the span of operators that leave at least one changed party untouched. It is the operator-valued form of the PF exclusivity lemma; for single Paulis it reduces to that lemma exactly (H.10.3). Read in spacetime: no change of emissions may coherently act on all of the changed agents' returning carriers at once. That is the quantum generalisation of "one switch decides the direction of signalling" (ref. 16 Thm 3). It is the quantum analogue of the Novikov self-consistency principle quoted in refs. 14 and 16, as a linear constraint on the dynamics rather than on histories.

5. *Threshold (H.10.6, H.14.1) [PROVED] as minimum complexity of the loop [INTERPRETIVE].* Consider loop dynamics that act on the returning carriers only by superposing at most three bit-flip patterns at a time (X-type, ≤3 terms). They are always simulable by randomly chosen classical consistent histories: a transport plan gives the mixture explicitly. A quantum signature needs at least four coherently superposed flip patterns per transition (H.13.2 attains four). Status of non-X three-term dynamics with Z components (H.17, updated Oct 23 2026):

    - generic boards are PF blends (H.17.9) [PROVED];
    - tuned two-class boards (H.17.13) and boards containing the identity class (H.17.14) are PF blends [PROVED];
    - three non-identity classes: all 61 G48 orbits are proved (H.17.15) [PROVED, exhaustive enumeration with over-approximating supports];
    - four or more classes are OPEN. *(Round 19, H.26.1: at most four classes occur (H.17.17), and the exhaustive four-class search finished clean, so this item is PROVED in the per-class-pair model.)* Every board proved to be a PF blend has a classical realisation as a mixture of the ref. 16 / ref. 28 reversible CTC histories, so it carries no quantum time-travel signature.

6. *Convexity (H.13.1) [PROVED].* A classical coin in S, routed untouched to F, selects which loop runs. So the set of loop statistics is closed under mixing, as for classical CTC models.

7. *Never-crossed facets (H.13.4, H.14.2) [numerical] and the polytope question (H.14.4) [evidence] [INTERPRETIVE].* 22 genuine facet orbits remain uncrossed by every board tested; a 23rd, orbit 92, is just positivity $p(i|o) \geq 0$ and holds for every process (H.17.5). The 22 are candidate "classical-like" constraints that may bind every reversible quantum loop. Z_8 crossed 8 facet orbits that Z_4 did not, so the list is provisional. Ref. 15 shows that the classical consistent loops form a polytope. Our evidence suggests that reversible quantum loops form a curved convex set: the best violations are irrational and keep growing as the phase group grows. If that is right, the boundary between classical and quantum time travel is not a finite list of inequalities. That is not proved. *Correction (Round 15, H.22.2): ten of the 22 (orbits 4–11, 14, 25) are crossed by the time-reversed Lugano process read in rotated frames, and two more (53, 79) by a generalised Lugano board, so they do not bind every reversible quantum loop; 10 remain uncrossed. Update (Round 21, H.28.1): orbits 26, 30 and 31 are also crossed, so 15 of the 22 are crossed and 7 remain uncrossed. Round 22 (H.29): unchanged; no crossing in the extreme-point and exact phase-process searches. Round 23 (H.30): unchanged; the seven are proved on all non-Lugano phase processes and single-block time-reversed lifts.*

H.15.4 Minkowski space instead of CTCs [CITED + INTERPRETIVE].

- Every PF and every Switchboard here is a fixed linear map, so it can be simulated in ordinary spacetime with postselection (the P-CTC route, ref. 13), at the price of a success probability below 1.
- Without postselection, the Vilasini-Renner no-go (arXiv:2203.11245) applies to any Minkowski realisation of a process that is not causally ordered, which includes ours, since p is not causally separable. [PROVED: a classically causally separable process is a PF blend by Theorem H.2, and p is not; the exact check in H.15.6 also finds that p is not a fixed-order process, which is VR's actual hypothesis.] It would require time-delocalised (non-localised) systems, and would admit a fine-grained explanation with definite, acyclic causal order.
- So in Minkowski space our counterexample would not certify a causal loop. It would certify that the coarse-grained "events" A, B, C are not localised, and that the coarse statistics are not a mixture of consistent deterministic histories (H.12). **Downgraded Oct 23 2026:** the earlier claim that the fine-grained explanation "must itself be quantum and coherent" was not proved. The Lugano PF already needs non-localisation by VR Thm 4, since it is not fixed-order, so non-localisation alone does not separate our boards from classical PFs. Whether a classical fine-grained fixed-order model with more agents (VR Thm 5) can reproduce p is OPEN. *Update (Round 14, H.21.6):* the answer depends on what is allowed. With unrestricted multiple use it is yes, trivially, for every valid classical process. With reversible single use on delocalised classical variables it is no for H.12 and H.13.2. Intermediate notions stay OPEN. Whether the fine-grained acyclic model can be chosen to respect the Pauli rule in a natural way we have not analysed.
- Vilasini-Colbeck (arXiv:2206.12887) left open loops in 3+1-dimensional Minkowski space without superluminal signalling. Grothus-Vilasini (arXiv:2606.20476) have since closed it in the negative for conical spacetimes [CITED]. Our results do not bear on that question: they concern CTC-type or non-localised realisations, not loops between localised events.
- On a genuine CTC spacetime (refs. 16, 28) the interpretation of H.15.3 applies directly, *if* one adopts the linear, unitary process model. That model is the one ref. 16 calls the natural quantum extension. It agrees with P-CTCs on valid unitary processes and differs from Deutsch's nonlinear model (ref. 16 Sec. VII).

H.15.5 What is speculative.

- No concrete metric, field theory or material realisation of the H.12/H.13.2 board is given. Ref. 28's wormhole + billiard-ball construction handles classical PFs. A quantum, coherent version (coherent scatterers in the CTC region) is assumed, not built.
- Whether quantum CTC dynamics is linear (ref. 16) or nonlinear (Deutsch) is unsettled. Our signature is model-dependent.
- The physical meaning of the 22 genuine never-crossed orbits and of non-polytopality is conjectural. *(Round 15, H.22.2: twelve of them are crossed by pure boards; Round 21, H.28.1: three more; 7 remain.)*

H.15.6 Audit (Oct 23 2026) [labels as marked].

- *Script.* code/stochastic/cyclic/embed/embed_check.py (log alongside) [EXACT-CERTIFIED, rational arithmetic]. For the Lugano PF and both H.13.2 sources it computes the signalling structure, the fixed-order test over all 6 orders, and ref. 16's Thm 3 reduced test.
    - Lugano and H.13.2 with phi = (|0⟩+|1⟩+|2⟩)/sqrt3: every party signals to every other, there is no first party, and the process is not fixed-order.
    - H.13.2 with phi = (|0⟩+|1⟩+|2⟩-|5⟩)/2: pairwise signalling is A → C, B → A, B → C and C → A; B is marginally first with $p(i_B)$ = (3/4, 1/4); the process is not fixed-order. 32 conditional A-C loops are

invalid, as Theorem H.2 requires.
    - Ref. 16's Thm 3 test fails for both H.13.2 sources and passes for Lugano. This is diagnostic only, since mixtures of PFs can also fail it.
- *Explicit region assignment (phi_A source) [INTERPRETIVE, from VR Defs 20-24 + script].*
    - B gets a single localised region in the common past of A and C.
    - A and C cannot both be localised: by VR Thm 4 applied to the A-C signalling cycle at fixed o_B, at least one of them needs a delocalised input region.
    - The source must also reach B's past, because the A-C loop is valid only together with i_B.
    - For the symmetric source and for Lugano, all three agents' in/outputs must be non-localised (VR Cor 1).
- *What holds per object.*
    - Switchboard (H.12), rational 4-term counterexample (H.13.2) and Z8 boards: valid processes in ref. 15's 710,760-vertex polytope, outside conv(PF) [PROVED / EXACT-CERTIFIED]. So they are fine-tuned classical processes in ref. 15's sense, realised by reversible quantum loops. Ref. 16 notes that such processes need not have classical reversible extensions.
    - Tuned and generic ≤3-term boards: wherever proved PF blends (H.17.9, H.17.13, H.17.14, H.17.15), they are classically CTC-realisable as mixtures [PROVED + CITED]. The ≥4-class cases are OPEN (H.17.16). *(Round 19: closed in the per-class-pair model by H.17.17 and H.26.1.)*
    - Continuous or measurable PFs (F.5): ref. 16's Thm 1 holds for continuous variables, as stated in ref. 16, and its Eq. 7-8 is a continuous Lugano example; Thm 2's T^e(i) = i + e works on any group, and F.5's measure preservation is its measure-theoretic form. The classical CTC embedding therefore extends [CITED + PROVED]. The quantum lift on L^2 is proved only in F.5's cases; in general it is OPEN.
    - Countable ℓ^2 operators (Lean induced_unitary_l2 and valid_*_l2): the lift is a unitary process, and ref. 16's classical framework covers countable sets.
    - VR's no-go and fine-graining theorems are proved only for finite-dimensional systems and finite partitions. Their extension to ℓ^2 or L^2 processes is OPEN [not claimed].
- *Corrected.* (i) The H.15.1 wording on ref. 15's polytope. (ii) "Fine-grained explanation must be quantum" is downgraded to OPEN. (iii) The H.15.3 item 3 spacetime reading is limited to operator level. (iv) VR theorem numbers, erratum and PRL companion are added. (v) The 3+1 question is now answered by Grothus-Vilasini. (vi) Item 5 is updated to H.17. (vii) The Paunković-Vojinović journal reference is added.
- *Checked, no change needed:* ref. 16 Thms 1-3, Sec. VII and CQG 36, 224002; ref. 17 Thm 2 and Sec. 7 (Lugano counterexample; Thm 2 is stated bipartite with a "straightforward" multipartite generalisation); ref. 28 authors and arXiv number. Ref. 28's journal reference (CQG 37, 205011) was not re-fetched.
- *Open.* (a) Is every H.12 or H.13.2 board a routed circuit in the sense of Vanrietvelde et al.? Our boards are concrete test cases for their conjecture. (b) Is there a classical fine-grained VR realisation of p? (Answered in part by H.15.7: not with single-use agents. Round 14, H.21.6: yes with unrestricted multiple use, for every valid process; no for reversible single-use models on delocalised classical variables.) (c) VR-type theorems in infinite dimensions. (d) The ≥4-class H.17 boards.

H.15.7 Two open problems from H.15.6, pushed (Oct 23 2026) [labels per item].

(B) Can a finer-grained causally ordered model reproduce p?

- **Setting.** Each coarse agent k applies its local operation exactly once per run. It acts at one fine-grained location (its "active slot"); at every other location it receives "vacuum", and its action on vacuum is fixed

and does not depend on its choice. Agents' outputs are free settings, independent of all hidden variables. The fine-grained network is acyclic: fixed order, or order chosen dynamically by classical values, with any number of extra non-agent nodes and hidden variables. This is the set-up assumption of VR (Sec. IX) and of Salzger-Vilasini, in classical form.

- **Lemma H.15.7a [PROVED].** Under these assumptions, with classical carriers, the coarse correlations P(i|o) are causal correlations: mixtures of dynamically ordered deterministic strategies. Proof: fix the hidden variables. Acyclicity orders the active slots, and the first active slot's input depends only on the hidden variables. Inductively, each agent's input is a function of the earlier agents' settings, so P(i|o) is a point of the dynamic-order causal polytope. Averaging over hidden variables keeps it there. With quantum carriers and quantum control of order (QC-QCs, which also use each operation once), the same conclusion is a theorem of Wechs, Dourdent, Abbott and Branciard (arXiv:2101.08796, PRX Quantum 2, 030335 (2021); erratum PRX Quantum 4, 030901 (2023) on Prop. 7, conclusion unaffected) [CITED].
- **Theorem H.15.7b [PROVED; exact certificate].**
  - The test uses a legal local operation: each agent measures its input as the outcome and emits a free bit o_k as the setting.
  - With these operations, the H.13.2 correlation violates a causal inequality, for both sources. Code: code/stochastic/cyclic/embed/finegrain_check.py, which enumerates all 138,304 deterministic dynamically ordered strategies.
  - An LP plus a rational Farkas vector y, checked exactly, gives min over causal strategies of $y \cdot P = 0$, while $y \cdot p = -5/4$ (φ_A) and $-4/3$ (φ_B). As a control, Lugano gives -4.
  - **Hence no model of the kind in Lemma H.15.7a, classical or QC-QC, reproduces H.13.2.** In particular the board W is not a QC-QC, so Salzger-Vilasini's QC-QC-to-causal-box construction does not apply to it.
- **Consequence for VR [CITED + PROVED].** VR's Thm 5 says that any relativistically causal fixed-spacetime realisation has a fine-grained fixed-order explanation with $M \geq N$ "possibly communicating" agents. For H.13.2, that explanation must break the single-use set-up: some coarse agent's operation is not realised as one application at one active slot.
- **The H.12 switchboard is not settled.** At this level of operations its correlation is causal: the LP is feasible, in floating point [NUMERICAL]. Whether another instrument witnesses a causal-inequality violation is OPEN; conv(PF)-exclusion alone does not imply it. *Update: settled in H.15.7d. Other projective measurements (emit the setting, measure along rational Bloch directions) violate a causal inequality, with an exact certificate [PROVED].*
- **OPEN.** Is there any classical fine-grained model that allows multiple use or communicating sub-agents, as in VR Thm 5, for H.13.2? Lemma H.15.7a shows such a model must violate single use. *Update (Round 14, H.21.6):* with unrestricted multiple use, yes, by a trivial construction that works for every valid classical process. A reversible single-use model on delocalised classical variables is impossible (D.6). Only intermediate notions remain open.

(A) Are the boards routed quantum circuits?

- **Precise statements [CITED, arXiv:2206.10042v3].**
  - Vanrietvelde, Ormrod, Kristjánsson and Barrett (Quantum 9, 1923 (2025)): a routed graph is valid if it is bi-univocal and its branch graph has no strong loops (Sec. 2.4). Any process obtained by "fleshing out" a valid routed graph is consistent.
  - **Conjecture 1:** any unitary process, hence any unitarily extendible one, can be obtained by fleshing out a valid routed graph.

    - **Conjecture 2:** the skeletal supermap violates causal inequalities iff its branch graph has (necessarily weak) loops.
    - Their footnote 21: the framework "provides no way to infer the routed circuit decomposition of a given process". Lugano is reconstructed (Sec. 4.3, Fig. 27) with an ad hoc vote-counting node X and computational-value indices.
- **Computation [EXACT/NUMERICAL, code/stochastic/cyclic/embed/routes_check.py].** For the purifications V: $|o\rangle|s\rangle \to \Sigma_i U_o[i,s] |i\rangle|o\rangle$:
    - Lugano: the station route (o, s) → i is a function (univocal, support 1).
    - H.12: every column has support 8.
    - H.13.2: columns have support 1 or 4.
    - So the computational-value sectorisation that makes Lugano's station univocal gives equivocal routes for our boards. VOKB's Lugano graph does not transfer directly.
    - In the Fourier sectorisation (medium indexed by z), all three are diagonal, and o enters only as a phase. For Lugano the phase is the character $(-1)^{z\cdot w(o)}$; for H.13.2 it is $(-1)^{m_o(z)/2}$; for H.12 it is $i^{m_o(z)}$. Non-character phases are exactly what puts the boards outside conv(PF) (X-type boards, H.10).
- **Status.** Pure boards are unitary processes, so Conjecture 1 predicts routed decompositions for H.12 and H.13.2 [CITED prediction]. Conjecture 2 together with Theorem H.15.7b predicts that any routed graph for H.13.2 has weak loops in its branch graph [conditional]. No explicit valid routed graph is given here, and no obstruction is proved: **OPEN**. Our boards are concrete test cases: an obstruction would refute Conjecture 1, and a decomposition would give the first routed circuit outside conv(PF). A natural candidate (INTERPRETIVE) is a station node indexed by Fourier sectors z, applying an o-controlled phase oracle, with agents connected through Hadamard-type routes. It is checked against the formal Sec. 3 rules in H.15.7c below: it fails.

H.15.7c Follow-up (Oct 23 2026, second pass).

- **The Fourier-station candidate fails VOKB's Principle 2 [EXACT; code/stochastic/cyclic/embed/rg_check.py, rg_check.log].**
    - The checker is a brute-force implementation of VOKB Defs 3.1–3.7 and Principles 1–2 (arXiv:2206.10042v3). It computes the choice relation and its adjoint, bi-univocality, solid/green/red branch-graph arrows, and a search for non-weak loops. Calibrations: a sectorised wire A → B is valid; an unindexed A ⇄ B loop is invalid.
    - **Candidate graph.** Source S with output P indexed by $z \in \{0,1\}^3$ (one-dimensional sectors), fleshed out by Hd·φ. Station Φ with inputs o_A, o_B, o_C (one-dimensional sectors) and z, and route (o, z) ↦ z. Output M indexed by z goes to a node D (fleshed out by Hd), whose unindexed qubit wires go to A, B and C. Global output F.
    - **Fleshing out.** $\Phi = \Sigma_o |o\rangle\langle o| \otimes \mathrm{diag}((-1)^{m_o(z)/2})$ follows the route, and D·Φ·S gives exactly the H.13.2 unitary (exact check). With the phases replaced, the same holds for H.12, Z8 and Lugano.
    - **Bi-univocality holds in both directions.** Branches: Φ has 8 (Φ^z), every other node has 1.
    - **Weak loops fail**, for example on the loop $A^0 \to$(solid) $\Phi^z \to$(red dashed) $D^0 \to$(solid) A^0. The solid arrow A → Φ^z exists because o_A is not fixed by Φ's branch. The red arrow exists because D's adjoint choice of z fixes which Φ^z happens.
    - **Variant.** Recording o on an internal indexed wire gives Φ 64 branches $\Phi^{o,z}$. It is still bi-univocal and still fails weak loops: the solid arrow becomes green, giving the loop A →(green) $\Phi^{o,z}$ →(red) D

→(solid) A, which is mixed and so not weak.
    - **This is not an obstruction to all decompositions.** The routes, and therefore the verdict, do not depend on the phases. The same graph with Lugano's character phases is equally invalid, yet Lugano has a valid routed graph (VOKB Fig. 27, which uses computational-value indices). The failure belongs to this sectorisation, not to the boards.
    - **What Conjecture 2 says.** It only constrains valid graphs, so this candidate tells it nothing. Conjecture 1, Conjecture 2 and Theorem H.15.7b together predict that a valid routed graph for H.13.2 exists and that its branch graph has weak loops, all green or all red [conditional].
    - An explicit valid graph, or an obstruction to all graphs, remains **OPEN**. Note that the agent wires would have to carry non-trivial sectors, since unindexed agent inputs give solid arrows into the agents.
- **H.12: local-instrument search finds no violation [NUMERICAL; code/stochastic/cyclic/embed/instr_search.py, instr_h12_s2.log].**
    - **Family searched.** Per agent and per setting x: a projective measurement of the input qubit along one of 13 distinct Bloch directions ($\theta \in \{0, \pi/4, \pi/2, 3\pi/4\}$, $\varphi \in \{0, \pi/4, \pi/2, 3\pi/4\}$), outcome a = b, and output encoding $o = g_x(b) \in \{0, 1, b, 1 - b\}$. This covers adaptive outputs. The search used 150 random instruments plus 150 steps of continuous-angle hill climbing.
    - **Robustness LP.** max t such that $t \cdot P + (1 - t) \cdot$uniform is causal, over the 138,304 deterministic causal strategies.
    - **Result for H.12:** best t = 1.000000. So no violation was found, but the optimum sits on the boundary of the causal polytope.
    - **Control:** H.13.2 φ_A reaches t = 0.6963, a violation.
    - A second seed did not finish (no output).
    - **Z8 class 10515** with the H.14.2 source: best t = 1.000017, no violation found [NUMERICAL, instr_z8.log]. Its computational-basis station routes have support sizes {1, 4, 5, 6} (not univocal), and it is Fourier-diagonal (routes_check.log).
    - **Status (superseded for H.12 by H.15.7d, which finds an exact violation; still current for Z8).** This narrows but does not settle the question. It is OPEN whether any instrument (general POVMs, entangling the agent's input with a memory, more settings) shows that H.12 or Z8 violates a causal inequality. If none does, H.12 would be a pure non-PF board whose correlations are all causal. Even then, it would still be excluded from single-use classical models with deterministic local operations, because $p \notin$ conv(PF) (H.12). The fixed-instrument test is weaker than PF-membership.

H.15.7d Third pass (Oct 23 2026): a calibrated routed-graph checker, an exact rotated form of H.13.2, and a causal-inequality violation for H.12 [labels per item].

(A) Routed graphs.

- **Calibration: VOKB's Lugano graph passes the checker [EXACT; code/stochastic/cyclic/embed/rg_lugano.py, rg_lugano.log].** We encoded VOKB Fig. 27 for rg_check.py. Nodes: the agents A, B, C, the vote-counting station X and the future node F. Indices: the result l on X → A and A → F, the pair (vote, result) on A → X with vote·result = 0, and the votes ijk on X → F. Shared indices are enforced through the routes. The checker reports: bi-univocal; branches A, B, C: 2 each ("loses"/"wins"), X: 5, F: 1; 38 branch-graph arrows; weak-loops principle satisfied. This matches VOKB's Sec. 4.3.2, so the checker reproduces a known valid graph as well as known invalid ones.

- **Rotated form of H.13.2 [PROVED; exact integer check in rg_h13.py, rg_h13.log].** Write $n_o(z) = m_o(z)/2$. Then $n_o(z)$ is linear in o over F_2:
  - $n_o(z) = o_A\, f_A(z) + o_B\, f_B(z) + o_C\, f_C(z) \pmod 2$, with $f_A = z_B\, z_C$, $f_B = z_A(1 + z_C)$, $f_C = z_A + z_B + z_A\, z_B$ (the OR of z_A and z_B).
  - Hence, after a Hadamard on every agent's input wire and output wire (and on the past and future), the H.13.2 purification V becomes the permutation W′: $|z\rangle_P\, |w\rangle_{AO} \mapsto |z\rangle_{AI}\, |w \oplus f(z)\rangle_F$.
  - Each f_k does not depend on z_k.
  - In words: in the rotated frame, each agent receives its input straight from the past. The board then flips agent k's output bit according to a function of the *other* agents' inputs, applied "across" the agents. Local unitaries on agent wires can be absorbed into the agent nodes, so H.13.2 has a valid routed graph if and only if W′ does.
- **Two natural graphs for W′ fail [EXACT; rg_h13.log].** Both use per-agent computational-basis sectors (one-dimensional) on every agent wire.
  - (a) A single station X with route $(z, w) \mapsto (z, w \oplus f(z))$ and 64 branches. It is bi-univocal, but the loop B → X → B is mixed (green, red).
  - (b) Per-agent stations X_k. X_k applies the flip f_k to w_k, and the controls z_j ($j \neq k$) pass through X_k on their way to agent j. It is bi-univocal, with X_k having 8 branches, but there is a mixed loop $X_B \to C \to X_C \to B$ (red, green, red, green).
  - The mechanism is the same in both. With full agent routes, each agent has a forward choice (its output w_k), which gives green arrows into the stations. It also has a backward choice (its input z_k), which gives red arrows out of the stations. In Lugano the agents have no backward choice: the agent's output index carries a copy of its classical input l, and the quantum content sits in a separate two-dimensional sector. For W′ the agent's input z_k is itself the coherent qubit, so that trick needs a different sector structure.
- **Status of (A): OPEN.** No valid routed graph for H.13.2 is found, and no obstruction is proved. Excluded so far (by exact check, not by a general argument): the Fourier-station graphs of H.15.7c; the single-station and per-agent-station graphs for W′ with one-dimensional per-agent computational sectors. The structural fact "f_k does not depend on z_k" is the analogue of Lugano's "a majority for Alice does not depend on Alice's vote". That analogy is INTERPRETIVE. The natural next try is a Lugano-type graph in which the stations X_k carry the value of f_k as an index ("did agent k's bit get flipped"), and each agent's coherent qubit sits in a non-trivial sector. *Update: settled in H.15.7e. W′ is, up to local Pauli flips, the time reverse of the Lugano purification, and the reversed VOKB graph is valid [PROVED, with the fleshing-out of VOKB's circuit CITED and re-checked exactly].*

(B) Instruments: H.12 violates a causal inequality.

- **Search [NUMERICAL; instr_search2.py, instr2_h12.log, instr2_z8.log, instr2_h13ctrl.log].**
  - *Instruments.* Agent k with setting x applies a general 4-outcome qubit POVM $\{E_{a,o|x}\}$ to its input. It records the outcome a and emits the classical output o. Because the board decoheres o, this is the most general memoryless local instrument. It contains 3-outcome POVMs and rank-1 projective measurements in arbitrary bases.
  - *Objective.* To avoid the t = 1 plateau of the robustness LP, the optimiser does not maximise t. It minimises a soft-min of y·P over a pool of 2,432 valid causal inequalities: the exact Farkas certificates of H.15.7b (H.13.2 φ_A and φ_B, Lugano) and all their images under party permutations,

setting flips and setting-dependent outcome flips. Images of a valid inequality under these relabelings are valid, and a spot check of 64 members gave minimum 0 over all 138,304 deterministic causal strategies.
    - *Method.* L-BFGS-B from seeded structured starts (a random basis with o = setting, or o = g(outcome)).
    - *Control.* H.13.2 φ_A reaches y·P = −1.405 (robustness t = 0.679), better than the −5/4 of H.15.7b.
    - *H.12.* Seeds 1–4, 8 restarts each. The best is y·P = −0.7058 (seed 3), with robustness LP t = 0.8048. instr2_verify.py recomputes P independently from the process matrix $W = \Sigma_o |\psi_o\rangle\langle\psi_o| \otimes |o\rangle\langle o|$, with Tr W = 8. The two computations agree to $8\cdot10^{-16}$, and the rows sum to 1.
    - *Z8 class 10515.* Seeds 1–2, 8 restarts each. Best y·P = +0.0002, t = 1: no violation found.
- **Theorem H.15.7d [PROVED; exact arithmetic in Q(√2); instr2_exact.py, instr2_exact.log].** The H.12 switchboard, with its source, violates a causal inequality.
    - *Instrument.* The optimum is rank-1 projective, with $o_k = x_k$: agent k measures along a Bloch direction $n_{k,x}$ and emits its setting. We rounded each direction to a rational point of the sphere: $n_{A,0}$ = (−896, −8704, −577)/8769, $n_{A,1}$ = (1280, 4224, 2907)/5285, $n_{B,0}$ = (6912, −16512, −15461)/23653, $n_{B,1}$ = (−32704, −15168, −156597)/160693, $n_{C,0}$ = (13440, 21760, −35829)/44021, $n_{C,1}$ = (−3328, 3648, −4929)/6977.
    - *Exactness.* The projectors then have entries in Q(i). The board and source have entries in Q(i, √2), so P(a|x) is computed exactly, and its rows sum to 1 exactly.
    - *Inequality.* y is an integer vector with entries ±1, listed in instr2_exact.log. Its minimum over all 138,304 deterministic causal strategies is exactly 0.
    - *Value.* $y\cdot P = r_1 - r_2\sqrt{2}$ with r_1 = 158077977870324318023361541/108202395271728590997126690 and r_2 = 331540368405687313524299l7/216404790543457181994253 38. Both are positive and $r_1^2 < 2r_2^2$, so y·P < 0 (≈ −0.70568).
- **Consequences.**
    - [PROVED] By Lemma H.15.7a (classical carriers) and the Wechs-Dourdent-Abbott-Branciard theorem (QC-QCs) [CITED], H.12 has no single-use fine-grained causally ordered model, exactly like H.13.2. This settles the H.12 item left open in H.15.7(B) and H.15.7c.
    - [conditional] VOKB Conjectures 1 and 2 then predict that any valid routed graph for H.12 has weak loops.
    - Why H.15.7c missed it: its 13-direction grid with output $g_x(b)$ contains the right kind of operation (emit the setting) but not the right directions. In addition, hill climbing on t is stuck on the t = 1 plateau. The fixed-facet objective removes both problems.
    - Still OPEN: Z8 class 10515 (no violation found in this family). *Update (H.15.7e): "nice" directions settled (cube-26 directions violate, exactly; octahedral ones do not violate the pool); maximal violation estimated, not settled.*

H.15.7e Fourth pass (Oct 23 2026): H.13.2 is a time-reversed Lugano process, hence has a valid routed graph; "nice" directions for H.12 [labels per item].

(A) A valid routed graph for H.13.2.

- **Lemma H.15.7e.1 [PROVED; exhaustive check in rg_h13_lugano.py, rg_h13_lugano.log].** The function $f(z) = (z_B\, z_C,\ z_A(1 + z_C),\ z_A \vee z_B)$ of H.15.7d is a *process function*: for each of the 4^3 choices of local maps h_k: {0,1} → {0,1}, the loop z = f(h(z)) has exactly one fixed point. Moreover f is the Lugano

function up to relabelling. With lug(a, b, c) = ((1−b)c, (1−c)a, (1−a)b), we have f(o) = lug(o ⊕ f_o) ⊕ f_i for all o, where f_o = (0,1,0) and f_i = (0,0,1). No party permutation is needed.

- **Theorem H.15.7e.2 [PROVED; exact 64×64 integer check, rg_h13_lugano.py].** Let L: $|s\rangle_P\,|o\rangle_{AO} \mapsto |s \oplus \mathrm{lug}(o)\rangle_{AI}\,|o\rangle_F$ be the Lugano purification (a permutation), and let L^T be its time reverse. In L^T, the old future F is the past, the old agent outputs AO are the agent inputs, the old agent inputs AI are the agent outputs, and the old past P is the future. Then the H.13.2 purification is $V_{13}.2$ = (Hd X^{f_o})_AI (Hd X^{f_i})_F · L^T · (Hd)_AO (X^{f_o} Hd)_P, where the brackets are local unitaries: Hadamards and Pauli-X flips on each agent's input and output wires and on the past and future.
  - Proof sketch: W′ (H.15.7d) sends (z, w) to (z, w ⊕ f(z)). Substitute f(z) = lug(z ⊕ f_o) ⊕ f_i and compare with L^T: (p, q) ↦ (p, q ⊕ lug(p)). The integer check confirms the identity entry by entry.
  - In words: H.13.2 *is* the Lugano process, run backwards in time and viewed in the Hadamard basis.
- **Corollary H.15.7e.3 (valid routed graph) [PROVED, with one CITED step].**
  - *The graph.* Reverse every arrow of VOKB's Lugano graph (Fig. 27) and transpose every route. The checker (rg_check.py) reports: univocal and adjoint univocal; branches A, B, C: 2, X: 5, F: 1; 38 branch-graph arrows; weak-loops principle satisfied. This is expected, because both principles are symmetric under reversal, which swaps green and red arrows.
  - *The fleshing-out.* We reconstructed VOKB's Lugano circuit (Fig. 30, eqs. (20)–(21)): a CNOT l → p_A giving A_{in} = p_A ⊕ l; node V sending (vote = A_{out}, l = 0) or (vote 0, l = 1; A_{out} to F); and station X on the constraint set. Every node is a permutation of basis states. So the link product on a basis input is the sum over consistent internal assignments. We checked (rg_lugano_flesh.py, rg_lugano_flesh.log) that for every past p and agent-output a there is exactly one consistent assignment, that A_{in} = p ⊕ lug(a), and that the F record determines a. Hence the composite is L [exact]. That this reconstruction is VOKB's figure is CITED.
  - *Status [CITED, full text searched; H.15.9(A)].* VOKB define the adjoint of a routed graph as its time-reversed version (their Principle 1; Def. B.10), and they read the red arrows of the branch graph off the adjoint. Validity is therefore reversal-symmetric by definition, and this corollary is a one-line application of VOKB. We add only the explicit check and the fleshing-out for L^T. It does not answer the open question of Baumann et al. (ref. 39), which concerns Page–Wootters circuits, not routed circuits.
  - *Reversal.* Transposing every node gives a routed circuit on the reversed graph whose composite is L^T. Any agent unitary T corresponds bijectively to T^T, so the agent slots are unchanged as sets. Absorbing the local unitaries of Theorem H.15.7e.2 into the agent nodes and the global past and future gives a valid routed circuit for H.13.2.
- **The obstruction pattern behind H.15.7c–d [PROVED for the listed graphs; general statement INTERPRETIVE].**
  - The failed graphs used the forward orientation, where the arguments of f (the z's) are agent *inputs*. Then each agent has a backward choice (red arrows out of the stations) and a forward choice (green arrows into them), and these close mixed loops.
  - The valid graph uses the reversed orientation, in which the arguments of f are agent *outputs*, as in Lugano's votes. There the agents have no backward choice.
  - Rule of thumb (INTERPRETIVE): when the classical skeleton of a rotated board is a process function g of the agents' inputs, look for the graph of the time reverse, where g reads outputs.

    - We did not separately encode the forward-orientation variant suggested in H.15.7d (stations X_k carrying f_k as an index); the reversed construction supersedes it. Whether that forward variant can be made valid is not claimed either way.
- **Consequences.**
    - [PROVED/CITED] H.13.2 is a routed-circuit-realisable (VOKB-valid) unitary process that violates causal inequalities (H.15.7b), exactly as Lugano does. *Prior work (H.15.8): the time-reversed Lugano process, its validity and a numerical causal-inequality violation are due to Guérin and Brukner (2018, ref. 38).*
    - [PROVED] The classical statistics p(i|o) of H.13.2 in the computational basis lie outside conv(PF) (H.13), even though the board is a Lugano process in the rotated frame. Membership in conv(PF) is basis-dependent, and the PF structure here lives in the Hadamard frame.
    - [conditional] This is consistent with VOKB Conjectures 1 and 2: the valid graph has loops, and they are weak.
    - H.12 remains without a routed graph (OPEN). Its skeleton is not of this permutation type: the dials have phases i, not only ±1. *Update: settled in H.21.4. The same reversed graph works, with Bob's CNOT replaced by a controlled-√X.*

(B) H.12: nice directions and the size of the violation.

- **Octahedral (Clifford) directions do not violate the pool [NUMERICAL; instr3_nice.py, instr3_nice.log].**
    - Exhaustive search over all 6^6 assignments of the six stabiliser directions ±x, ±y, ±z, with o = setting, gives min over the pool of $y \cdot P = +0.232233 > 0$.
    - Coordinate descent over directions × output modes $g \in \{0, 1, a, 1-a\}$ (30 seeds) gives the same value.
    - This does not exclude violations of causal inequalities outside the 2,432-member pool.
- **Cube-26 directions (faces, edges and vertices of the cube) already violate [PROVED; exact in Q(√2, √3); instr3_exact.py, instr3_exact.log].**
    - *Instrument.* Agent k, setting x measures along $n_{k,x}$ and emits a constant output:
        - A: $n_{A,0} = (1, -1, -1)/\sqrt{3}$ with o = 0; $n_{A,1} = (0, -1, -1)/\sqrt{2}$ with o = 1.
        - B: $n_{B,0} = (1, -1, -1)/\sqrt{3}$ with o = 0; $n_{B,1} = (0, -1, 1)/\sqrt{2}$ with o = 1.
        - C: $n_{C,0} = n_{C,1} = (0, 0, 1)$ with o = 1 and o = 0 respectively.
        - So A and B emit their setting and C emits its negation.
    - *Inequality.* y is a ±1 integer vector, listed in the log. Its minimum over all 138,304 deterministic causal strategies is exactly 0.
    - *Exactness.* P(a|x) has entries in Q(√2, √3) (listed in the log), and its rows sum to 1 exactly.
    - *Value.* $y \cdot P = 131/48 - (13\sqrt{6} + 19\sqrt{2} + 7\sqrt{3})/24 \approx -0.22241$.
    - *Sign, by hand.* Since $2.449^2 < 6$, $1.414^2 < 2$ and $1.732^2 < 3$, we have $13\sqrt{6} + 19\sqrt{2} + 7\sqrt{3} > 31.837 + 26.866 + 12.124 = 70.827 > 65.5 = 24 \cdot 131/48$.
    - This is a much smaller certificate than H.15.7d's.
- **Other sets [NUMERICAL; instr3_nice.log].** Best pool values: icosahedral (12 directions) −0.4165; icosahedral + dodecahedral (32 directions) −0.5143; continuous directions (projective, exact per-coordinate minimisation) −0.6874.
- **Maximal violation over the pool [NUMERICAL lower bound only; instr3_h12_more_a.log, instr3_h12_more_b.log].** General 4-outcome POVM instruments, seeds 1–12 with 8 restarts each (96

runs). The best value is $y \cdot P = -0.7235$ (seed 12, restart 3), and the earlier best was -0.7058. No upper bound on the violation is proved, so the maximal violation remains OPEN. For comparison, H.13.2's φ_A reaches -1.405.

H.15.8 Novelty recheck after H.15.7e: time reversal, frames, and what is new (Oct 23 2026) [labels per item].

(A) Literature (CITED; each source fetched on Oct 23 2026 and searched in full text).

- **Guérin and Brukner, "Observer-dependent locality of quantum events", NJP 20, 103031 (2018), arXiv:1805.12429v4 (ref. 38).**
  - App. D defines the time reversal of a pure process: $|w_r\rangle := (\mathrm{SWAP}_{\{PF\}} \otimes \otimes_k \mathrm{SWAP}_{\{I_k O_k\}}) |w^*\rangle$. They prove it is a valid pure process, with induced map $G_r(U, V) = G(U^\dagger, V^\dagger)^\dagger$.
  - Sec. IV applies this to the Lugano purification: $|w_r\rangle = \Sigma_{x,y} |y\rangle_P |x\rangle_O |y\rangle_I |x \oplus f(y)\rangle_F$ (their Eqs. (58)–(64)). This is our L^T of H.15.7e.2, with their f being the Lugano function in another labelling.
  - With source $\Sigma_u |u\rangle/\sqrt{8}$ they find, by seesaw, a violation $I_1 \approx -1/4$ of a three-party causal inequality (their Eq. (70)) They note that classically the process has a simple causal realisation (copy the input), and they attribute the quantum violation to no-cloning.
- **Baumann, Krumm, Guérin and Brukner, "Noncausal Page-Wootters circuits", PRR 4, 013180 (2022), arXiv:2105.02304 (ref. 39).** Their Sec. V.4 discusses the same "time reversed version of the Lugano process". They leave its realisation in their Page-Wootters framework open.
- **Chiribella and Liu, "Quantum operations with indefinite time direction", Commun. Phys. (2022), doi:10.1038/s42005-022-00967-3.** Up to unitary equivalence, the input-output inversion of a unitary channel is the adjoint or the transpose; for a general bidirectional (bistochastic) channel it is $C \mapsto C^\dagger$ or $C \mapsto C^T$.
- **Oreshkov and Cerf (Nature Phys. (2015), doi:10.1038/nphys3414; NJP 18, 073037 (2016)).** A time-symmetric, and then time-neutral, operational formulation that extends the process-matrix framework.
- **arXiv:2406.18489 (time-symmetric process matrices and causal inequalities).** Works out time-reversed process matrices and "backward" causal inequalities in that setting.
- **Baumeler, Costa, Ralph, Wolf and Zych, CQG 36, 224002 (2019), arXiv:1703.00779.** Every process function extends to an invertible one with a source and a sink, and "the time-reversed process is then compatible with arbitrary reversed local operations". This is the classical time reversal.
- **BGR 2022 (Quantum 6, 673) and Daher Ahmed–Kunjwal (arXiv:2610.00579).**
  - A full-text search for time reversal or transposition found only a party-order reversal (BGR, Lemma 8) and a transposition step inside a proof (DAK, App. A).
  - Neither discusses time-reversed PF purifications or their classical restrictions.
  - DAK's SHIFT/PFU unitaries apply Hadamards controlled by a PF, which is a different construction from the phase lift below.
- **Not found.** In any of these, or by web search, we found no statement that a time-reversed PF purification, read in a rotated local basis, induces a classical process outside conv(PF). Coverage caveat as in Section 0.

(B) Exact conceptual check.

- **Proposition H.15.8.1 [PROVED].** Let g be any process function and $L_g: |s\rangle|o\rangle \mapsto |s \oplus g(o)\rangle|o\rangle$ its purification. In ${L_g}^T$ each agent's input is a copy of the past register. So with any source ψ, decohering every agent wire in the computational basis gives $p(i|o) = |\psi(i)|^2$, independent of o. This is a mixture of the 8 constant functions, which are PFs (phase_lift.py checks that they are among the 744). Hence the

computational-basis classical restriction of every time-reversed PF purification lies in conv(PF). This matches Guérin and Brukner's remark that the process is classically causal.

- **Consequence.** H.13.2 is outside conv(PF) *only because* it reads $L_{lug}{}^{T}$ in the Hadamard basis on the agent wires (Theorem H.15.7e.2). The two candidate framings fare as follows:
  - Rejected: "purifiability is not closed under classical time reversal". It is not supported. Pure processes are closed under time reversal (Guérin–Brukner App. D), and the classical time reverse of a PF purification restricts to a PF mixture.
  - Correct reading: classical restriction is basis-dependent. The same pure process gives a PF mixture in one local basis and a non-mixture in the conjugate basis [PROVED for $L_{lug}{}^{T}$, by Proposition H.15.8.1 and H.13.2].
- **Phase lifts of all 744 PFs [NUMERICAL; phase_lift.py, phase_lift.log].**
  - For a PF g, set U_o^g = Hd·diag($(-1)^{o\cdot g(z)}$)·Hd. Its purity follows for every g by the argument of H.15.7e.2 [PROVED].
  - For each g, we computed the maximum over source states of all 29,344 facet violations, as in H.13.3.
  - Result: U^g yields a process outside conv(PF) **exactly when g is one of the 64 PFs equivalent to Lugano** (that is, the non-causal ones). All 64 reach relative violation 0.140388; every other PF gives at most $5\cdot10^{-15}$.
  - The best ±1 class of H.13.3 (0.1404) is therefore precisely this family. Causal PFs, phase-lifted, stay inside the hull.
- **H.12 is not a phase lift in this frame [PROVED, exact integer test; h12_frame.py, h12_frame.log].** For z = 101 and 111, the map o ↦ $i^{m_o(z)}$ is not a constant times a character $(-1)^{o\cdot c}$. So in the Hadamard frame the H.12 board is not a phased permutation, and not the phase lift of any PF. Whether H.12 is locally equivalent to some time-reversed PF purification in another frame is OPEN. *Update (H.21.2): the H.13.2 construction does carry over to H.12 once Bob's flip may be the non-permutation gate √X. So H.12 is a frame-rotated time-reversed √X-Lugano process. It is still not a time-reversed PF purification, in agreement with H.15.9(A).*

(C) What H.13.2's novelty now consists in [INTERPRETIVE summary of (A) and (B)].

- *Known:* the board (time-reversed Lugano, up to local unitaries), its purity, and the fact that it violates a causal inequality (Guérin–Brukner 2018).
- *Ours (as far as found):*
  - (i) Its classical restriction in the Hadamard basis is a purifiable classical process outside conv(PF), with an exact rational certificate (H.13.2).
  - (ii) Among phase lifts of three-party binary PFs, exactly the Lugano class does this (numerical).
  - (iii) Exact causal-inequality certificates (H.15.7b) and the routed-graph corollary (H.15.7e), both of which are applications.
- *Unaffected:* H.12.1 (its board is not of this form in the Hadamard frame), the lifting theorem (Section 1), and the structural results of H.8–H.14 and H.17.

H.15.9 The structure of H.12, and how far it can violate (Oct 23 2026)

(A) Is the routed-graph corollary new? [CITED; full text of arXiv:2206.10042v3 and of Vanrietvelde's DPhil thesis (Oxford) searched]

- VOKB define the adjoint of a routed graph as "the routed graph obtained by reversing the direction of its arrows, and taking the adjoints of its routes", which "can be interpreted as its time-reversed version" (Principle 1; Def. B.10). Bi-univocality asks for univocality of the graph and of its adjoint. The red arrows of the branch graph are read off the adjoint. So reversing a valid graph gives a valid graph, by definition. They also use time symmetry to shorten proofs (e.g. their Fig. 17 graph is "time-symmetric (up to relabelling)").
- Neither text mentions a time-reversed Lugano process or Guérin–Brukner 2018. Web searches for later routed-circuit work on time reversal found none. Chiribella–Liu's framework for indefinite time direction is a different formalism.
- Verdict: Corollary H.15.7e.3 is an immediate application of VOKB's definitions, and we word it that way. The explicit graph check and the fleshing-out for L^T are ours, as far as found. The open question of Baumann, Krumm, Guérin and Brukner (ref. 39) is about Page–Wootters circuits and is not touched.

(B) Is H.12 a known process in disguise? [h12_struct.py, h12_struct.log]

- **Set-up.** Write the H.12 board as a pure process vector $|w\rangle$ on eight systems: P, F (8-dimensional each) and AI_k, AO_k (qubits). Two processes are *LU-equivalent* if one becomes the other under a unitary on each of the eight systems and a permutation of the parties. Time reversal (Guérin–Brukner) is complex conjugation together with P ↔ F and AI_k ↔ AO_k. For any set S of systems, the spectrum of the reduced state ρ_S is an LU invariant; under a party permutation, S is relabelled.
- **Not a process-function purification, forward or reversed [NUMERICAL; spectra compared after rounding to 10^{-6}].** Compare the spectra of all 1- and 2-system reductions under all 6 party permutations. H.12 matches none of the 744 PF purifications L_g, and none of their time reverses L_g^T. This includes Lugano (= Araújo–Feix = Baumeler–Wolf), Lugano^T, and all their relabellings. A single invariant suffices: ρ_{P,AI_A} of H.12 has eigenvalues $(2 \pm \sqrt{2})/16$. For Lugano, the same pair of systems has spectrum $(3/16)^4(1/16)^4$, and for Lugano^T it is $(1/4)(1/8)^6$. As a sanity check, the same test does find H.13.2 LU-equivalent to Lugano^T (Theorem H.15.7e.2).
- **Not causally separable, hence not a quantum-switch variant [PROVED].** LU maps on agent wires can be absorbed into the instruments, and LU maps on P and F into the source and the discard. So LU-equivalent processes have the same set of correlations. H.12 violates a causal inequality (exact certificate, H.15.7d). Every process built from fixed or coherently controlled orders (quantum switch and its 3-party variants, QC-QCs) gives only causal correlations. So none of them is LU-equivalent to H.12. The 3-switch also has a past of a different dimension.
- **H.12 is not LU-equivalent to its own time reverse [NUMERICAL, same invariants].** Trivially, H.12 *is* the time reverse of a pure process, namely its own reverse. So "the time reverse of a pure process" carries no content unless the forward process is named.
- **Classical restrictions of H.12's time reverse V^T [comp/comp PROVED; other frames NUMERICAL].** In V^T the agents' inputs are a copy of the past register: $V^T |q\rangle_{AO'}|f\rangle_{P'} = |f\rangle_{AI'} \otimes \Sigma_s U_f[q,s]|s\rangle_{F'}$. So Proposition H.15.8.1 applies verbatim. In the computational frame, $p(i|o) = |\psi(i)|^2$ does not depend on o, which makes it a mixture of constant PFs. In the frames Had/Had, comp-in/Had-out and Had-in/comp-out we computed the maximum over sources of all 29,344 facet violations: 0 (to 10^{-12}) in every frame. So H.12's time reverse stays inside conv(PF) in all four frames tried. Forward H.12 leaves conv(PF) only in the computational frame, with relative violation $0.103553 = (\sqrt{2} - 1)/4$ numerically. The same code reproduces Lugano^T in Had/Had and H.13.2 in comp/comp at 0.140388 (H.15.8).

- **Reading [INTERPRETIVE].** H.12 is a genuinely different object from the Lugano family. It is not a time-reversed PF purification, and not a phase lift (H.15.8). Its time reverse is "classically tame" in these frames, whereas Lugano^{T} is not. *Correction (Round 14, H.21.2): "different from the Lugano family" is true only for the PF purifications. H.12 belongs to VOKB's wider family of fleshed-out Lugano graphs: it is the frame-rotated time reverse of the √X-Lugano process.*

*(C) How far can H.12 violate y? [h12_bound.py; logs h12_bound_.log]**

- **Reduction [PROVED, H.15.7d].** The board decoheres each AO into F. So a general qubit instrument acts here exactly like a 4-outcome POVM $\{E_{a,o|x}\}$, and $P(a|x) = \Sigma_o \psi_o\dagger\ (E^A \otimes E^B \otimes E^C)\ \psi_o$ with $\psi_o = U_o$ ph.
- **Achievable side (seesaw) [NUMERICAL].** Each step solves an exact SDP over one party's POVMs with the other two fixed.
  - For y_A (the H.15.7d inequality), random starts reach at best −0.6597 in 44 restarts. Most restarts stall at 0.
  - Started from the H.15.7d optimum, the seesaw stays at −0.70580, so that point is a fixed point of the seesaw (no single party can improve it).
  - For y_B (the cube-26 inequality, H.15.7e), the seesaw reaches −0.34516, below the exact nice-direction value −0.2224.
  - The best value seen for any inequality remains −0.7235 (H.15.7e).
- **Upper side (relaxation) [NUMERICAL; SDP solver to tolerance 10^{-6}, no rounded dual certificate].**
  - Replace the product $E^A \otimes E^B \otimes E^C$ by any family $Z_{ao|x} \geq 0$ on AI (8×8) such that:
    - $\Sigma_\{ao\}\ Z_{ao|x} = 1$;
    - summing over party k's outcome pair gives $1_k \otimes R$, with R independent of x_k.
  - Every product of POVMs satisfies these constraints, so min y·P over this set is a lower bound on what any instruments achieve.
  - Result: min $y_A \cdot P \geq -1.7243$ and min $y_B \cdot P \geq -1.6821$. Adding the PPT constraints $Z^{T_k} \geq 0$ (which products also satisfy) tightens this to min $y_A \cdot P \geq -1.5855$. The PPT run for y_B was stopped unfinished. (*Update:* it was not resumed; the y_A bounds were later sharpened in H.21–H.26.)
  - So for y_A the true optimum over all instruments lies in [−1.586, −0.7058] (now PROVED, (C′)). The gap is large, and we do not claim the seesaw value is optimal. *(Round 14: narrowed to [−1.27720, −0.70580], H.21.8.)*
  - *Update:* both y_A bounds (NS and NS+PPT) are now certified exactly; see (C′) below. The y_B bounds remain NUMERICAL. A tighter (e.g. symmetric-extension) hierarchy is **OPEN** here.
- **(C′) Certified lower bounds [PROVED; exact rational arithmetic; h12_dual.py, h12_dual_verify.py, h12_dual_verify_{ns,ppt}.log].** For every choice of instruments:
  - $y_A \cdot P(H.12) \geq -1585556675679981708526611328125000000001/10^{40} \approx -1.585557$ (NS+PPT dual; SCS dual value −1.5855181);
  - and, from the NS relaxation alone, $y_A \cdot P(H.12) \geq -1724303906783461570739746093750000000001/10^{40} \approx -1.724304$ (weaker, but needs no PPT terms).
  - *Certificate (NS case; the PPT case adds the terms below).* Write the relaxation of the upper-side bullet with variables $Z_{x,c}$ (x the setting triple, c the 64 outcome triples (a_k, o_k)). For any Hermitian Λ_x and any Hermitian Γ, Δ attached to the linear constraints, Lagrangian duality gives the identity

$y_A \cdot P = \Sigma_x \mathrm{Tr}\, \Lambda_x + \Sigma_{x,c} \mathrm{Tr}[S_{x,c} Z_{x,c}]$, where $S_{x,c} = y_A[x,a] \cdot W_c - \Lambda_x -$ (constraint terms) is determined by $(\Lambda, \Gamma, \Delta)$. Here $W_c = \Sigma_o \psi_o \psi_o^\dagger$ restricted to outcome bits o, with $\psi_o = U_o \cdot ph$ as in H.15.7d.

- On feasible Z the constraint terms vanish, $Z_{x,c} \geq 0$ and $\Sigma_c \mathrm{Tr}\, Z_{x,c} = 8$ for each x. So $\mathrm{Tr}[S_{x,c} Z_{x,c}] \geq l_{x,c} \cdot \mathrm{Tr}\, Z_{x,c}$ for any $l_{x,c} \leq \lambda_\min(S_{x,c})$, and $y_A \cdot P \geq \Sigma_x \mathrm{Tr}\, \Lambda_x + 8 \cdot \Sigma_x \min_c\, l_{x,c}$.
- This holds for **any** Hermitian $(\Lambda, \Gamma, \Delta)$, feasible or not; infeasibility only weakens the constant. So no exact dual feasibility is required.
- *Procedure.* The dual multipliers from an SCS solve (dual value −1.7242877, matching the primal) are rounded to Gaussian rationals with denominator 2^{30} and made exactly Hermitian. W_c (entries in $\mathbb{Q}(i,\sqrt{2})$) is replaced by rationals from 60-digit evaluation, with entrywise error below 10^{-55}. Its total effect is far below 10^{-40}, and 10^{-40} is subtracted from the final bound to cover it. For each (x, c) a rational $l \leq \lambda_\min(S_{x,c})$ is certified by an exact LDL^T factorisation of $S_{x,c} - l \cdot 1$ in Fractions, on its 16×16 real form, with every pivot positive.
- *PPT terms.* With Hermitian $Y_{x,c,k}$ for the constraints $Z_{x,c}^{T_k} \geq 0$, $S_{x,c}$ also contains $-\Sigma_k Y_{x,c,k}^{T_k}$, and the identity gains $\Sigma \mathrm{Tr}[Y_{x,c,k} Z_{x,c}^{T_k}]$. Since products satisfy $Z^{T_k} \geq 0$ and $\mathrm{Tr}\, Z^{T_k} = \mathrm{Tr}\, Z$, each such term is $\geq l(Y_{x,c,k}) \cdot \mathrm{Tr}\, Z_{x,c}$, so $l_{x,c}$ becomes $l(S_{x,c}) + \Sigma_k l(Y_{x,c,k})$. Each l(Y) is certified by the same exact LDL^T test.
- The worst slack per setting triple is $-3.0 \cdot 10^{-7}$ (NS) and $-6.0 \cdot 10^{-7}$ (PPT), so rounding costs about $2 \cdot 10^{-5}$ and $4 \cdot 10^{-5}$ in total.
- Combined with H.15.7d this gives: **the optimum of y_A over all instruments lies in [−1.58556, −0.70580]** [PROVED both ends]. The NS+PPT relaxation value is itself −1.58552 (numerical), so a tighter certificate needs a stronger hierarchy. Closing the gap is **OPEN**. *Update (Round 14, H.21.8):* a lifted relaxation certifies −1.27720, so the interval is now [−1.27720, −0.70580].
- *Scope.* The instrument-to-POVM reduction used here is the one of H.15.7d [PROVED]. The certificate covers only y_A. y_B has the NUMERICAL relaxation bound −1.6821.

H.16 Round 10 status (Oct 23 2026) [proved in Lean unless marked]

- **Unitarity closed.** The H.12.3 gap "isometry, not unitary, for infinite ancillas" is now closed. `isUnitaryInf_Vsb` proves the Switchboard loop is unitary against every family of countable ancillas. `purification_conjecture_false_unitaryInf` then gives the counterexample in the unitary form. The proof checks row orthonormality (`row_scalar_key`, an exact kernel check) and shows that an isometry with orthonormal rows is onto.
- **Validity link, partial.** `valid_pfPoint_iff` proves `Valid (pfPoint w) ↔ IsPF w`, and `validWith_of_valid_pfPoint` links this to `PFUL.ValidWith`. Both hold only for deterministic w. `ValidWith` is not defined for non-deterministic processes such as `pcl`.
- **F.5.5 for general point maps.** `PFUL.Continuous.closedLoop_general_unitary` covers measurable bijections with a positive density. `closedLoop_jacobian_unitary` covers global bijections of $\mathbb{R}^n$ with an invertible derivative, where the density is |det g'|. Round 11 update: `closedLoop_jacobian_unitary_ae` covers bijections that are differentiable off a null set, with det g' ≠ 0 a.e. (piecewise-smooth maps); `closedLoop_jacobian_isometry` gives an isometry when the Jacobian may vanish (not onto if it vanishes on positive measure). Non-injective local diffeomorphisms are not point-map unitaries.

- **Round 11: automatic boundedness and ancillas of any cardinality [PROVED, Lean].** A kernel with orthonormal rows and columns over any index set is the matrix of a bounded unitary of ℓ^2 (`PFUL.Counterexample.unitary_of_unitaryKernel`). The Switchboard loop is unitary for local operations given only as unitary kernels, with ancillas of any cardinality (`isUnitaryKer_Vsb`), hence for bounded unitaries on non-separable $\ell^2(\kappa)$ (`isUnitaryAll_Vsb`, `IsUnitaryInf` without `Countable`), and `purification_conjecture_false_unitaryKer` is the strongest form of H.12.1. For process functions on groups of any cardinality, $\psi \mapsto \varphi\cdot(\psi\circ\tau)$ is a unitary of ℓ^2 with no measurability, countability or boundedness hypothesis (`PFUL.LiftAuto.closedLoop_l2_unitary`, `permPhaseUnitary`). Not covered: general unitaries for the lift on uncountable alphabets beyond point maps, and the ℓ^2-to-Lean link for automatic boundedness of positive trace-preserving maps (H.16 Round 9 gap, unchanged; closed in Round 16, H.23.2).
- **Round 12 (Oct 24 2026): process-matrix framework and infinite ancillas [PROVED, Lean; one step PROVED on paper].** See H.19. The counterexample is restated with process-matrix definitions (`purification_conjecture_false_choi`), and the Switchboard is shown pure with ancillas in arbitrary Hilbert spaces (`isPureHilbert_Vsb`). It is valid under normal CPTP channels on countable ancillas (`valid_normalCPTP_Vsb`). Finite-ancilla purity implies infinite-ancilla purity for every V (H.19.4, paper only).
- **Round 13 (Oct 24 2026): the Round 12 gaps [PROVED, Lean].** See H.20. H.19.4 is now in Lean (`isPureHilbert_of_isPure`); AFNB Thm 2 (`isPurePM_iff`); Kraus and normal-CPTP validity without countability (`valid_normalCPTP_Vsb_any`); a link product over ancillas of any cardinality (`isValidPMInf_iff`, `isPurePMInf_iff`, `purification_conjecture_false_choiInf`); and $C^2 \otimes K_k$ as Mathlib's tensor product (`isPure_qubitTensor`). The Round 9 boundedness gap (automatic boundedness of positive TP maps) is unchanged; see H.20.6. (Closed in Round 16, H.23.2.)
- **Open.** The non-X 3-term boards (from H.14) and the 23 never-crossed inequalities (J.1) were not attacked this round and are still open. (H.17.5 later showed that orbit 92 is positivity, so 22 are genuine.)

H.17 Non-X three-term boards, local rotations, and what validity alone gives (Oct 23 2026) [labels: PROVED / EXACT-CERTIFIED / NUMERICAL / OPEN per item]

This round attacked the two items H.16 left open: boards that are not of the X type, and the 23 never-crossed orbits of J.1. One of these, orbit 92, turns out to be positivity (H.17.5), leaving 22 genuine. Code and logs are in code/stochastic/cyclic/switchboard/h16/ (scripts csp2, rsearch, z16sample, xcont) and h17/ (struct3, search3, nsearch, nsearch2, pairlemma, siglemma, sigsearch, locrot, locopt, validlp, validcert, shpcheck). Model: a board with at most 3 Pauli terms per outcome is $U_o = P_o\, V_k^{\sigma}$. Here V_k is 1, $\alpha+i\beta A$, or $\alpha+i(\beta A+\gamma B)$ with A and B anticommuting, and σ flips the signs of β and γ. This is the H.14 form $P\cdot\exp(i\,t(\cos\varphi\, A + \sin\varphi\, B))$. A board is *hard* if it is complete and admissible (unitary and obeying the Pauli rule H.8.1), has a genuine 3-term class, and has no operator-first and no operator-last party. Hard boards are the ones H.6 and H.1 do not already reduce to PF blends.

H.17.1 Pure non-X three-term boards exist; none leaves the PF hull [NUMERICAL].

- *Generic parameters* (csp2 structure model, rsearch): 5 seeds × 8,000 complete structures gave 6,551 hard boards. The largest violation of any of the 29,344 hull facets, over all source states, was $5.9\cdot10^{-15}$. The

largest unitarity or Pauli-rule residual was $4.4\cdot10^{-16}$. search3 (6 seeds) gave about 4,200 more hard boards. The best value there was $6.3\cdot10^{-15}$.

- *Tuned (non-generic) parameters* (nsearch, nsearch2): here class parameters are chosen so that products U_oU_q† lose terms, which can only happen when the groups ⟨A,B⟩ and ⟨A′,B′⟩ intersect. Supports are recomputed from the matrices, so every cancellation is seen by the Pauli rule. nsearch (3 seeds) gave about 4,600 hard boards. nsearch2 (seeds 1–3 and 11–14; new classes get the most general linear repair) gave 6,340 hard boards. No run printed VIOLATION (threshold 10^{-6}). The best facet value was $\le 6.4\cdot10^{-15}$ and the Pauli-rule residual was $\le 6\cdot10^{-31}$.
- *Conclusion.* Pure boards that are not of the X type and have ≤3 terms per outcome do exist, and in large numbers. Every one tested lies inside the PF hull to round-off. Whether every such board is a PF blend is **OPEN**. H.14.1 proves this only for X-type boards.

H.17.2 Support transport (SH) [definition; reduction OPEN]. SH says: for every pair o≠q with D=o⊕q, every X-shadow $x(P_o)\oplus x(P_q)\oplus t\oplus t'$ (with t and t′ ranging over {0}∪X-parts of the class generators) obeys the X-type Pauli rule (x∧D)≠D. Two coarser variants were also checked. SH^{+} groups o~q when U_oU_q† is monomial (all of its terms share one X-part). SH^{++} first absorbs a common right factor U_r† into the source state. The hoped-for reduction is "SH (or SH^{++}) ⇒ the H.14.1 X-type argument applies ⇒ PF blend". That reduction is not written out or proved here and remains **OPEN**.

H.17.3 SH can fail for a pair but not for an admissible generic cube [PROVED by exhaustive exact enumeration, generic-support model].

- pairlemma (exhaustive, exact F_2 arithmetic): it covers all anticommuting pairs (A,B), sign changes Δσ∈{1,2,3}, translations $R=P_o\oplus P_q$ and differences D≠0. Of these, 94,365 are pairwise admissible. SH fails in 16,344 of them, so SH is *not* automatic pair by pair.
- siglemma (sign-variant lemma): for each of the 16,344 SH-failing pairs, it searches the intermediate cube vertices for a completion. For |D|=2 this means a common neighbour. For |D|=3 it means a path $o–m_1–m_2–q$ with all six pairwise constraints. Same-class intermediates are enumerated over all 4·64 options. For other-class intermediates only necessary edge conditions are imposed (an over-approximation, so "infeasible" is a proof). 432 configurations survive the local test, and **0** extend to the full cube.
- *Scope.* The statement covers same-class type-3 sign-variant pairs in the *generic-support* model: a board with generic parameters whose only SH failures would come from sign variants of one class cannot be admissible. It says nothing about tuned parameters. sigsearch agrees: of 60,000 structures, 4,098 contain sign variants and 59 are hard, and none fails SH.

H.17.4 Tuned boards do violate SH, but not SH^{++}, and stay in the hull [NUMERICAL]. With tuned parameters the conservative SH test failed on 35 hard boards across the nsearch2 seeds. The best facet value among them was $5.9\cdot10^{-15}$, so none is a violation. Only one board failed SH^{+} (seed 11, board 3339, saved as shp_11_3339.npy). It fails SH^{+} on 6 pairs and satisfies SH^{++} for a suitable common right factor (0 bad pairs; shpcheck.log). Seeds 12–14 had no SH^{+} failures. *Every hard board found satisfies SH^{++}* [NUMERICAL]. A proof that SH^{++} always holds is **OPEN**.

H.17.5 What validity alone gives on the facets [EXACT-CERTIFIED for 22 orbits; PROVED for orbit 92]. Let Valid be the polytope of p(i|o) ≥ 0, normalised, such that every deterministic local intervention has fixed-point probability 1. The validity equalities have rank 27, so Valid has affine dimension 37. Purif ⊆ Valid.

- *Exact certificates* (validcert): for each of the 22 never-crossed orbits other than 92 there is an exact rational point of Valid where the facet functional is negative. The functional is rationalised and checked to reproduce the integer facet values on all 744 PFs. The relative values are −2/9 for orbits 4–11, 14 and 25, and −1/6 for orbits 26, 28, 30, 31, 53, 54, 57, 66, 69, 75, 79 and 81. So validity alone does not imply these 22 inequalities. Any proof that they hold on Purif must use purity [EXACT-CERTIFIED].
- *LP screen over all 93 orbits* (validlp): 92 of the 93 facet orbits have strictly negative LP minimum on Valid (relative values between −1/3 and −1/6). For orbit 92 the minimum is 0.
- *Orbit 92 is just positivity [PROVED, exact dual certificate; cert92.py, cert92.log].* The orbit-92 representative (facet 6928) has range 1 on the PFs and g_0=1/16. Exact rational multipliers y were found for the 72 validity equalities (normalisation and fixed-point equalities, denominators ≤128). They satisfy $g - A^T y = e_(111|000)$ and $g_0 + b \cdot y = 0$ exactly in Fractions. Hence **on all of Valid the orbit-92 functional equals p(111|000)**, which is ≥ 0 for every process. Consequences:
  - The minimisers on Valid are exactly the valid processes with p(111|000)=0. This face has dimension 36 (dim Valid = 37), and no coordinate vanishes identically on Valid. So the face is a facet of Valid, namely the positivity facet p(111|000) ≥ 0.
  - 651 of the 744 PFs lie on it.
  - Orbit 92 (64 facets) is the orbit of the 64 positivity facets p(i|o) ≥ 0. J.1's representative already reads p(111|000) ≥ 0.
  - It holds for every classical process, purifiable or not. It was never a genuine open inequality. **The never-crossed open list is therefore the 22 orbits 4–11, 14, 25, 26, 28, 30, 31, 53, 54, 57, 66, 69, 75, 79, 81.** Every one of these is violated somewhere on Valid at an exact rational point, so a proof that they hold on Purif needs purity. *Update (Round 15, H.22.2): orbits 4–11, 14 and 25 are crossed by a pure board (the time-reversed Lugano process in rotated input and output frames, exact certificate), and orbits 53 and 79 by a generalised Lugano board (H.22.2, addendum). The open list is now the 10 orbits 26, 28, 30, 31, 54, 57, 66, 69, 75, 81.*

H.17.6 The 22 genuine orbits (and orbit 92) under wider board families [NUMERICAL]. None of the following produced a violation.

- *Z_{16} X-type boards* (z16sample): 2 runs, more than 5,500 sampled pure boards each, scored on every facet of the 23 orbits. The best value was $3.9 \cdot 10^{-15}$.
- *Continuous X-type phases* (xcont): the violation was maximised with a penalty on the Pauli-rule residual, starting from the best Z_8 boards. The largest values were $2.3 \cdot 10^{-7}$ (orbit 25, residual $3 \cdot 10^{-11}$), $3 \cdot 10^{-8}$ (orbit 92, which is positivity by H.17.5, so this value is purely an artefact) and ≤ 10^{-8} for the others. These are consistent with penalty/round-off artefacts, below the 10^{-6} threshold for exact certification, and were not pursued.
- *Local rotations* $L=L_A \otimes L_B \otimes L_C$ applied on the left. These preserve the Pauli rule exactly, so every L·U is pure, but p changes. locrot tried the 216 local Clifford cosets on all 193 Z_4 classes (2 runs) and got a best value of $4.4 \cdot 10^{-15}$. locopt optimised continuously over $SU(2)^3$ from Z_4 starts (2 runs) and got a best value of $3.6 \cdot 10^{-15}$.

H.17.8 Proof attempt: support transport implies PF blend [PROVED: Pauli coset-transport theorem; GAP: shadow versus group closure; local-Clifford reduction does not work].

(a) Pauli coset-transport theorem [PROVED]. Let $U_o = P_o\, G_{\kappa(o)}$, where P_o is a Pauli string with X-part a(o) (any Z-part and phase), κ partitions the outputs into classes, and the Pauli support of G_κ has all its X-parts in a

subgroup $H_\kappa \le F_2^3$ (Z-parts arbitrary). Suppose every class-constant selection $o \mapsto a(o) \oplus h_{\kappa(o)}$, with $h_\kappa \in H_\kappa$, is a PF. Then $p_\varphi \in \mathrm{conv}(\mathrm{PF})$ for every source state φ. *Proof.* A Pauli $X^h Z^z$ with $h \in H_\kappa$ maps each $|j\rangle$ into the coset $j+H_\kappa$, so G_κ is block-diagonal on the cosets of H_κ and unitary on each block. The left factor P_o only permutes basis states by $a(o)$ and multiplies by phases, so $p(j\oplus a(o)|o) = |(G_\kappa \varphi)_j|^2 =: r_\kappa(j)$. From here the proof of H.10.6 goes through word for word: μ and r_κ have equal mass on every coset, so the transport plans π_κ exist, and the same weights λ give p. ∎ Sign variants cause no difficulty. V^σ is a different unitary with the same X-support, so (k,σ) is simply a different class with the same H_κ. Z-components cause no difficulty either: they are diagonal.

(b) Reduction to a support condition [PROVED]. By H.10.3 (pairwise exclusivity ⇔ PF, exhaustive and exact), the hypothesis of (a) is equivalent to the following condition, called **SH_grp**: for every pair $o \neq q$ in different classes, with $D = o \oplus q$, every X-string $a(o)\oplus a(q)\oplus h \oplus h'$ ($h \in H_{\kappa(o)}$, $h' \in H_{\kappa(q)}$) satisfies $(x \wedge D) \neq D$. Same-class pairs need nothing. There $K_{oq} = P_o P_q^\dagger$ is a single Pauli string, and the Pauli rule (H.8.1) already forbids it from having an X-part covering D. So **SH_grp ⇒ PF blend for every φ.** This holds with no restriction on the number of terms. For an X-type ≤3-term board (two-term classes, $H_\kappa = \{0,d\}$) SH_grp is exactly what H.14.1(b) verifies, so H.14.1(b) is the special case.

(c) The gap [OPEN]. SH as tested in H.17.2–H.17.4 uses the shadow $T_\kappa = \{0\} \cup \{x(g) : g \text{ a generator of class } \kappa\}$. For a 3-term class $V = \alpha + i(\beta A + \gamma B)$ this is $\{0, x_A, x_B\}$, and $H_\kappa = \langle x_A, x_B\rangle$ also contains $x_A \oplus x_B$. The Pauli rule controls only strings that actually occur in $K_{oq} = U_o U_q^\dagger$. Across two different generic classes these strings have X-parts $a \oplus a' \oplus \{0,x_A,x_B\} \oplus \{0,x_{A'},x_{B'}\}$. The term $x_A \oplus x_B$ (because AB never occurs in V) and its translates are not controlled. So SH implies SH_grp only when $x_A \oplus x_B$ is already in T_κ, or when the extra strings happen to be allowed.

- When $x_A = 0$ or $x_B = 0$ (one generator is a Z-string) or $x_A = x_B$, $H_\kappa = T_\kappa$ up to $\{0\}$ and there is no gap.
- In the remaining case (x_A, x_B, $x_A \oplus x_B$ all nonzero and distinct) the gap is real. SH^{++} (common right factor absorbed into φ) has the same gap. Closing it needs either an exhaustive exact check that SH_grp holds on every admissible ≤3-term cube in the struct3 model (an F_2 enumeration of the pairlemma/siglemma kind, not done this round), or a different transport for non-group shadows. *Time-boxed sample [exact per structure; sample NUMERICAL] (shgrp.py, shgrp_1.log).* struct3 drew 77,211 random admissible structures in the generic-support model, 80 s, seed 1. Of these, 11,491 are hard, and 7,801 of the hard ones contain a class whose gap is real ($|\langle x_A,x_B\rangle| = 4$). SH_grp failed for **0** of them. Admissibility and SH_grp are exact F_2 tests, so by (a)–(b) each sampled structure is **proved** to give PF blends for generic parameters. What remains open is that *every* structure does: the sample is not exhaustive and tuned (non-generic) parameters are not covered. Status: **OPEN; reduced to a finite F_2 enumeration (csp2/struct3 model plus SH_grp), with no counterexample in 11,491 hard samples**. *Update:* the enumeration was completed in H.17.9, and SH_grp holds on every admissible generic board.

(d) Local Clifford conjugation does not reduce to the X-type case [observation]. A local Clifford C maps Paulis to Paulis and preserves the Pauli rule. But replacing U_o by $C\,U_o\,C^\dagger$ changes p unless C is diagonal up to a permutation in the computational basis. On one qubit such C (generated by X, Z, S) map X-type strings to X- or Y-type ones and never map Z to X. Conjugation therefore cannot remove the Z-components of A or B while preserving p. For p only the X-parts matter (part (a)), so the reduction actually available is the one in (a)–(b), and the X-type proof extends exactly as far as SH_grp holds.

H.17.9 Exhaustive exact check of SH_grp in the generic model (Oct 23 2026) [PROVED by exhaustive exact enumeration, generic-support model] (shgrp_exh.py, shgrp_local.py, shgrp_cube.py, shgrp_dfs.py; .log/.json alongside). The enumeration covers 1,072 class options: V=1, 63 two-term classes, and 1,008 anticommuting pairs A<B. It includes pairs of distinct classes with identical generators. It runs over every left-Pauli difference R (64) and every D≠0 (7).

- *Pairwise (shgrp_exh).* There are 1,999,627 pairwise-admissible different-class configurations, using the generic support R+{0,A,B}+{0,A′,B′}. **SH_grp fails pairwise in 329,280 of them.** Among the 98,685 admissible sign-variant configurations it fails in 16,344. So pairwise admissibility does *not* imply SH_grp, and a cube-level argument is needed. A typical failure: c = (V=1), c′ = (X_2, X_1Z_2), R = Z_2, D = parties {1,2}. The three support strings Z_2, Y_2, X_1 are allowed, but $x(R)\oplus x_A\oplus x_B = X_1X_2$ covers D.
- *Sign variants.* For a sign variant with flips on both generators the support is {0,A,B}, so SH and SH_grp coincide on these pairs (the same 16,344 cases as pairlemma). By the sign-variant lemma H.17.3 **none** of them completes to an admissible cube [PROVED, generic model].
- *Different classes, |D|=1 and |D|=2 [PROVED, generic model].* Across a cube edge of party p, every term of K must be trivial on p. Between different classes this forces all generators of both classes to be trivial on p. There are no failures with |D|=1, and the 52,416 with |D|=2 all fail the necessary common-neighbour test (shgrp_local: 0 survive). The cube test below confirms this.
- *Different classes, all D (shgrp_cube).* Fix o=0 and q=D, and give each other vertex a label in {class of o, class of q, fresh identity class}. This over-approximates: sign variants are merged and R and all non-edge constraints are ignored. Then require the edge condition on all 12 cube edges. Of the 329,280 failures, **329,192 are proved impossible**. **288, all with |D|=3, survive** this coarse test. In every one of them o carries the identity class V=1 and q a 3-term class, with 2 values of R per class pair. They are written to shgrp_cube_survivors.json.
- *The 288 survivors: exact cube search (shgrp_dfs.py, shgrp_dfs.log).* By a global left Pauli and a relabelling of the base sign of q's class we may take o=0 with P_0=1 and q=7 with P_7=R and σ=0. Every other vertex m ranges over all states (P_m, class k among all 1,072 options, σ). A pair of states is accepted if the different-class generic support, or (when the two states share a class) the same-class support R+S(ds), satisfies the Pauli rule H.8.1 for their D. Allowing both readings over-approximates admissibility, so an empty result is a proof. Domains are filtered against o and q, then made arc-consistent over all 28 pairwise constraints, then searched by DFS. **In all 288 cases no cube exists**: after arc consistency the domain of vertex 1 is empty (25 s in total). A sanity run (shgrp_dfs_sanity.py/.log) checked that the pair test accepts all 28 pairs of each of 300 random admissible struct3 cubes, including cubes with 2–4 classes (300/300 accepted).
- *Status.* **Theorem: every admissible board with ≤3 Pauli terms per outcome and generic parameters satisfies SH_grp, hence (H.17.8) is a PF blend for every source state.** The scope is the generic-support model of struct3: $U_o = P_o$ V^σ, and the support of every U_oU_q† is the generic one, with no cancellations. The theorem covers non-X boards; X-type boards were already covered by H.14.1. The chain is: different-class |D|≤2 failures excluded locally; sign-variant failures excluded by H.17.3; 329,192 |D|=3 failures excluded by shgrp_cube; the last 288 excluded by shgrp_dfs. This is consistent with the random sample of H.17.8(c) (11,491 hard cubes, 0 SH_grp failures). **Tuned parameters are not covered** (H.17.10).

H.17.10 Tuned (non-generic) parameters [analysis; OPEN]. Genericity can fail in three ways.

- (i) *Degenerate coefficients* (β=0 or γ=0). These lower the term count, so the board is covered by the same model with a smaller class.

- (ii) *Proportional classes* ($G_c \propto G_{c'}$). The classes simply merge, and the same-class pairs need nothing (H.17.8b).
- (iii) *Cancellation in U_oU_q†.* This needs coinciding products, so the groups ⟨A,B⟩ and ⟨A′,B′⟩ must intersect, and coefficients tuned to cancel. Cancellation *removes* strings from the support, so it makes more structures admissible. SH_grp itself depends only on R and the generators' X-parts, not on the coefficients. Consequently:
  - H.17.8(a)–(b) apply verbatim to any tuned board that satisfies SH_grp.
  - What can go wrong is only that a tuned board is admissible although its generic counterpart is not, and fails SH_grp.
- *Evidence.* nsearch2 found 37 hard boards with a tuned cancellation, and 35 of them fail the weaker SH test. All are inside the PF hull to $6\cdot10^{-15}$. *SH_grp on these boards [EXACT per board] (shgrp_tuned.py, shgrp_tuned.log).* All 37 structures (P_o, class labels, generators) are saved in ns2_*.json. nsearch2 reuses a class only with the identical V, so the class partition is exact, and SH_grp depends only on these integers. **The same 35 fail SH_grp** (the 2 that pass SH also pass SH_grp, so they are proved PF blends). Every one of the 37 has two classes whose generator X-parts span the same group H (36 with two 3-term classes, 13 of those with identical generators but different coefficients). So tuned cancellation really does produce admissible boards outside the SH_grp route, as anticipated in (iii). These 35 boards are numerically in the PF hull and satisfy SH^{++} (H.17.4), but no proof covers them [OPEN]. Their unitaries were not saved (except shp_11_3339.npy), so exact facet tests were not possible this round.
- *Proof strategy.* A proof for tuned boards would enumerate the finitely many cancellation patterns: which products of {1,A,B}·{1,A′,B′} coincide and can cancel. Each pattern gives a modified support. Rerunning shgrp_exh/shgrp_cube on the modified supports would settle the tuned case.

*H.17.11 Tuned boards: right-absorption transport (Oct 23 2026) [theorem PROVED; per-board checks NUMERICAL supports, exact F_2 test] (nsearch2b.py, tbcheck.py, tbcheck.log, tb_.npz).**

(a) Theorem (right-absorbed coset transport) [PROVED]. Fix any output r and set $W_o = U_oU_r†$. Group o~q when W_oW_q† is monomial (a permutation by one X-string times a diagonal unitary). In each group pick a representative ρ, put $G_ρ = W_ρ$, $M_o = W_oW_ρ†$ (monomial, X-part a(o)), and let $H_ρ$ be the group generated by the X-parts of the Pauli support of G_ρ. Define **SH_grp^r**: for every pair o,q in different groups with D = o⊕q, no X-string a(o)⊕a(q)⊕h⊕h′ ($h \in H_{ρ(o)}$, $h' \in H_{ρ(q)}$) covers D. If SH_grp^r holds for some r, then $p_φ \in$ conv(PF) for every source state φ. *Proof.* $p_φ(i|o) = |⟨i|W_o\, ψ⟩|^2$ with $ψ = U_rφ$. As φ ranges over all states, so does ψ. $W_o = M_oG_{ρ(o)}$, and the proof of H.17.8(a) uses only that the left factor maps each basis state to one basis state shifted by a(o), up to a phase. A monomial does exactly that, so H.17.8(a) applies to (W, ψ). Its hypothesis is that every group-constant selection is a PF. By H.10.3 this is pairwise exclusivity. Pairs in different groups are covered by SH_grp^r. For a pair in one group, $W_oW_q† = U_oU_q†$ is a nonzero monomial with X-part a(o)⊕a(q). If that X-part covered D, every term of $U_oU_q†$ would be forbidden by H.8.1, which is impossible. ∎ This contains H.17.8 (take r in any class and note $V_c\, V_c† = 1$). It also contains SH^{++} upgraded to the group closure. The case where two classes share one group H is exactly where it helps: W = V′V† lies in the algebra spanned by the Paulis with X-parts in H, and tuned cancellation shrinks its support.

(b) Regenerated tuned boards [NUMERICAL supports; exact F_2 test; facets and LP high-precision]. nsearch2b is nsearch2 with every tuned-cancellation board saved: U, (P_o, class, generators) and the worst-case source state of its tightest facet. Six bounded runs (seeds 21–26, 420 s each) gave 18 tuned hard boards. **All 18 fail SH_grp**, with 1–8 bad pairs; shp_11_3339 was added as a 19th. Results:

- **SH_grp^r holds for all 19** (r = output 0 suffices). For 13 of them all W_o are monomial: one group, so V′ is a monomial times V and the classes merge outright. For the other 6 there are two groups, {monomial} and one 2-term X-type group with |H| = 2. Given the supports, each of these 19 boards is therefore a **PF blend for every source state** by (a). The supports were read off numerically with tolerance 10^{-9}; Pauli-rule residuals are ≤ 10^{-30}. The F_2 test itself is exact.
- *Facets:* the largest facet value, maximised over source states, is ≤ $5.9\cdot10^{-15}$ for every board.
- *Explicit PF-blend decompositions.* For each board, LP over the 744 PFs at the worst-case source state and at 3 random states finds an exact-feasible blend (L1 residual 0 in HiGHS). At the worst-case state 1–9 PFs suffice, so the point lies on a low face; at random states 29–38 PFs are needed. After rounding the weights to rationals with denominator ≤ 10^{12} and renormalising, the reconstruction error is ≤ $3\cdot10^{-8}$. The p are irrational, so no exact rational identity is possible. Under (a) the decomposition exists exactly anyway.
- The 35 boards of H.17.10 were not regenerated (their U were never saved), but their structure matches: two classes spanning one H.

(c) What is still open. (a) settles any tuned board that passes SH_grp^r, and every tuned board found does. What is not proved is that *every* admissible tuned ≤3-term board satisfies SH_grp^r. A proof would enumerate the cancellation patterns of V′V† inside the group algebra of H (finitely many for |H| ≤ 4) and rerun the shgrp_exh/shgrp_cube/shgrp_dfs pipeline on the resulting supports. That was not done this round [OPEN]. *Conjecture (evidence: 19/19):* in an admissible hard tuned board, absorbing the right factor of one class leaves at most one non-monomial group, and that group is X-type with |H| = 2. The board then reduces to the H.14 X-type situation.

H.17.12 Cancellation patterns of V′V† and more tuned boards (Oct 23 2026) [partly PROVED, partly NUMERICAL; closure OPEN] (tpat.py, tclass.py/.json, tbcheck.log, tbmerge.py/.log).

(a) Coincidence types [EXACT enumeration] (tpat.py). Take two genuine 3-term classes V = α+i(βA+γB) and V′ = α′+i(β′A′+γ′B′), all coefficients nonzero. Let K = {1,A,B,AB} and K′ be their Klein groups. Over all $1{,}008^2$ ordered pairs of anticommuting generator pairs, the 9 products {1,A′,B′}·{1,A,B} fall into exactly three types:

- |K∩K′| = 1 (876,960 pairs): all 9 products are distinct, so **no cancellation is possible** [PROVED: each coefficient is a single nonzero product].
- |K∩K′| = 2 (136,080 pairs): 7 strings, two of which collect two products each.
- K = K′ (3,024 pairs): 4 strings with multiplicities (3,2,2,2).

(b) The same-group case K = K′ [PROVED]. Put I = iA and J = iB. Then 1, I, J, IJ multiply like the quaternions, V = α+βI+γJ, and V′V† = (v·v′) + (terms whose coefficients are the components of v×v′, up to sign) on the strings 1, B, A, AB, with v = (α,β,γ) and v′ = (α′,β′,γ′) unit vectors with all components nonzero. Two components of v×v′ vanishing forces v′ ∥ v, hence all three vanish. v·v′ = 0 and v×v′ = 0 cannot hold together. So the only possible supports of V′V† are:

- {1}, which means V′ = ±V, so the two classes are the same class;
- all 4 strings;
- any 3 of the 4 strings;
- exactly {A,B}, {A,AB} or {B,AB} (v ⊥ v′ together with one vanishing cross component). tclass.py found exactly these patterns, by explicit construction on 60 instances of the type.

(c) The |K∩K′| = 2 case and all pairs involving 2-term classes [PROVED by exhaustive exact enumeration] (tcollide.py, tcollide.log). Every collided string other than those of the K = K′ type has exactly two contributions,

$\varphi_1 x'_{u'} \bar{x}_u + \varphi_2 x'_{w'} \bar{x}_w$. Here x = (α, iβ, iγ), so each x is a real number times a known phase. The string can vanish iff $\rho = -\varphi_1 t'_{u'} \bar{t}_u / (\varphi_2 t'_{w'} \bar{t}_w)$ is real, where the t are those phases. Two strings vanish together iff the two resulting monomial equations in the nonzero reals are sign-consistent. All Pauli phases φ are exact (±1, ±i). Over all 1,071² ordered pairs of 2- and 3-term classes:

- there are no collisions for 3,906 + 60,480 + 60,480 + 876,960 pairs;
- there are 3,024 K = K′ pairs, settled by (b);
- the remaining 63 + 3,024 + 3,024 + 136,080 pairs have exactly two collided strings. **Each of the two can vanish on its own, and never both** (0 exceptions). For two commuting 2-term classes on the same A, a single cancellation makes V′V† monomial, so the classes merge. This confirms the 60-instance sample of tclass.py.

(d) More tuned boards (7 more nsearch2b runs, seeds 31–37, 480 s each; 51 boards in total with H.17.11) [NUMERICAL supports; exact F_2 tests].

- SH_grp fails on 45 of the 51. **SH_grp^r holds on all 51**, so by H.17.11(a) every one of them is a PF blend for every source state.
- The largest facet value is $5.9 \cdot 10^{-15}$. LP PF-blend decompositions were found at 4 source states each, with rational-rounding residual $\leq 3 \cdot 10^{-7}$.
- *Conjecture of H.17.11(c) [NUMERICAL, 51/51].* After right absorption there is at most one non-monomial group, and it has |H| = 2. 41 boards collapse to one group; 10 have the pattern {monomial, |H|=2}.
- *Where the SH_grp failures come from (tbmerge.log):*
  - In 33 of the 50 saved boards the "tuned" class is V′ = ±V, so V′V† = 1 and nsearch2 simply gave one class two labels. Their SH_grp failures are artefacts of that labelling: the pairs are really same-class pairs.
  - In 8 boards V′V† has 2 terms with one common X-part: a monomial, so the classes merge.
  - In 7 it has 2 terms with two X-parts, which is pattern (b) {A,B}-type or a Z-string pair, |H| = 2.
  - The remaining 2 boards involve 2-term classes.
  - So the genuinely tuned boards found so far all reduce to X-type |H| = 2 after absorption.

(e) Closure [OPEN]. (a)–(c) give a complete, proved list of the possible pair supports of V′V†:

- generic, when |K∩K′| = 1;
- generic minus exactly one of the two collided strings (or generic), when the groups meet in two elements, including all 2-term cases;
- one of the supports in (b), when K = K′.

The remaining step was not done this round (time-box). It is to rerun shgrp_exh → shgrp_cube → shgrp_dfs with these supports, with each pair of states accepted if any allowed pattern passes the Pauli rule (this ignores consistency across pairs, so it over-approximates), testing SH_grp^r with r ranging over the classes. "Every admissible ≤3-term board is a PF blend" therefore remains **OPEN for tuned parameters**, with no counterexample candidate among 51 tuned boards.

H.17.13 Tuned closure for two-class boards (Oct 23 2026) [PROVED by exhaustive exact enumeration; over-approximating supports] (tclose2.py, tclose2.log, tclose2_done.txt checkpoint, tclose2_ctrl.py/.log).

Theorem. Let a board have exactly two distinct unitaries up to left Paulis, $U_o \in \{P_{oV}, P_{oV}'\}$, with V and V′ any classes of ≤3 terms: identity, 2-term or 3-term, with any parameters, tuned or generic. If the board is admissible, it

is a PF blend for every source state.

Proof. Absorb V into the source (H.17.11a): $W_o = P_{oG}{}^{b(o)}$ with G = V′V† and b ∈ {0,1}. Admissibility and SH_grp^r then depend only on S = supp(G).

- *Which S occur.* By H.17.12 every possible S is one of three kinds:
  - the generic product support, if there is no collision;
  - generic, or generic minus exactly one collided string, if the collisions have two contributions (proved);
  - any nonempty subset of K, if K = K′. This over-approximates H.17.12(b), which is sound.
- *Normalisation.* Normalised by a left translation, this gives 59,836 non-monomial supports. A monomial S means V′ is a monomial times V; the classes then merge, and the board is a PF blend by H.17.11(a).
- *Reduction to one failing pair.* If SH_grp^r fails at a pair (o,q), use three symmetries: cube translation, a global left Pauli, and G ↔ G† (which has the same support). Together they give o = 0 with state (P = 1, b = 0), and q = D with b = 1 and an h ∈ ⟨X(S)⟩ such that $x(P_q)⊕h$ covers D.
- *Search.* For each S and D, arc consistency plus DFS ran over the remaining six vertices, each with 128 states (P, b). Pair constraints are exact: P⊕P′ allowed when b = b′; every P⊕P′⊕s with s ∈ S allowed when b ≠ b′.
- *Result.* **No admissible board exists in any of the 59,836 × 7 cases** (21 s, 8 cores). Hence SH_grp^r holds and the board is a PF blend. ∎

Controls.

- Replacing the failure condition by "any cross pair" makes the same solver find two-class boards for 6 of 300 sampled supports. So the search is not vacuous, and most supports simply admit no genuine two-class board.
- All 7 non-merging two-class tuned boards found by nsearch2b have their S in the enumerated list, and every one of their 28 pairs is accepted by the pair tables.

Scope. This covers every board with two classes, tuned or not, including the 7 genuinely tuned two-class boards of H.17.12(d). With H.17.9 it leaves open only boards that have **≥3 distinct classes and at least one tuned class pair**. Only 2 of the 51 tuned boards found are of that kind, and both pass SH_grp^r (H.17.12d). A multi-class version is OPEN: it needs per-class-pair patterns together with a cube search over 1,072-class states.

H.17.14 Tuned closure for three-class boards containing the identity class (Oct 23 2026) [PROVED by exhaustive exact enumeration; over-approximating supports] (tclose3.py, tclose3_pass1.log, tclose3_pass1_done.txt.gz checkpoint, tclose3_rerun.py/.log, tclose3_cand.py/.log).

Refinement of H.17.11(a) [PROVED]. In each group the representative G_ρ may be replaced by Q†G_ρ, where Q is the Pauli string of any one support element s_0. The factor Q is absorbed into the monomials M_o. Then H_ρ = ⟨x ⊕ $x(s_0)$: x ∈ X(supp G_ρ)⟩, and a(o) shifts by $x(s_0)$. This is the translation normalisation already used in H.17.13.

Theorem. Every admissible board whose distinct unitaries (up to left Paulis) are {1, V_a, V_b} is a PF blend for every source state. Here V_a and V_b are any 2- or 3-term classes, and the pair (a,b) may be tuned.

Proof.

- *Reduction.* If (a,b) is an untuned pair ($K_a \cap K_b = \{1\}$ and $a \neq b$), the board is generic and H.17.9 applies. A board using only two of the three unitaries is covered by H.17.13. Otherwise, absorb the identity class. The pair supports are fixed per class pair and applied to all vertex pairs: supp V_a, supp V_b (which cannot cancel), and S_{ab}, taken from H.17.12 with "any nonempty subset of K" when $K = K'$ (sound).
- *Search.* This gives 243,621 jobs ($a \leq b$, pattern). A counterexample must fail SH_grp^r for the absorbed identity class at some pair. WLOG (cube translation, global left Pauli) this pair is o = 0 with P = 1 and q = D, with all three choices of class at o. Arc consistency plus DFS ran over states (P, class) with 192 values per vertex, 8 cores, about 2 min.
    - A complete board counts as a candidate only if (i) all three classes occur and (ii) it fails SH_grp^r for *every* absorbed class $c \in \{1, V_a, V_b\}$. Groups merge when a pair support is monomial, and the refined groups above are used.
- *Results.*
    - *First pass*, with unnormalised groups (a coarser, still sufficient test): 144 candidates, 0 unresolved. Realising them by solving for parameters with exactly pattern S_{ab} and all coefficients nonzero (tclose3_cand.py) shows the following. 48 are not realisable, which reflects the over-approximation for $K = K'$. The other 96 are admissible (Pauli residual $\leq 5 \cdot 10^{-30}$), inside the PF hull (facet $\leq 3.6 \cdot 10^{-15}$), and pass the numerical SH_grp^r.
    - *Re-check* of the 144 with the refined groups: **0 candidates, 0 unresolved.** The refined test is stricter, so a job that was not a candidate in the first pass cannot become one. Hence no counterexample exists in this class. ∎

Controls.

- With the failure test loosened to "any cross pair, all three classes present", the solver finds boards for 1 of 40 sampled jobs. In the first pass it found 144, so the search is not vacuous.
- The two known three-class tuned boards (H.17.12d) do not contain the identity class, so they lie outside this theorem. They pass SH_grp^r numerically.

Scope and what remains [OPEN]. Proved so far:

- every generic board (H.17.9);
- every two-class board (H.17.13);
- every three-class board containing the identity class (H.17.14).

Still open are boards with three classes none of which is the identity, and boards with ≥4 classes, in each case with at least one tuned pair. For three classes with a tuned pair there are about 145,000 tuned ordered pairs × 1,072 third classes, roughly $1.5 \cdot 10^8$ triples before symmetry. A symmetry reduction under qubit permutations and cube relabelling would be needed. The pair-support consistency $G_{ab}\, G_{bc} = G_{ac}$ is automatic in the per-class-pair model used here: each support is fixed once per class pair. Triple consistency is not imposed, which only enlarges the search and so is sound.

H.17.15 Three non-identity classes: symmetry reduction and closure search (Oct 23 2026) [PROVED for all 61 orbits, by exhaustive exact enumeration with over-approximating supports and the triple-consistency lemma] (t3sym.py, tclose3g.py, tclose3g.log, tclose3g_done.txt.gz checkpoint, tclose3g_cand.py/.log, tclose3g_classify.py/.log, tclose3g_unres.py, tclose3g_ctrl.py/.log).

Definitions used in this section [definitions; the group facts are PROVED by direct computation in t3sym.py].

- **Pauli strings.** A three-qubit Pauli string, up to phase, is a pair (x, z) ∈ $F_2^3 \times F_2^3$ (its X-part and Z-part). In the code it is the integer s = x + 8z. There are 63 non-identity strings.
- **Class (a).** Each outcome's unitary is $U_o = P_o\, V_k \hat{}\, \sigma$ (H.17 preamble), where V_k is one of three kinds:
  - the identity, V = 1;
  - a two-term unitary, V = α + iβA, with A a non-identity string;
  - a three-term unitary, V = α + i(βA + γB), with A < B anticommuting strings.
  - The *class* of V is its generator tuple: (), (A) or (A, B). It records which Pauli strings occur, and not the real parameters α, β, γ, the sign flip σ or the left Pauli P_o.
  - There are 63 two-term classes and 1,008 anticommuting pairs A < B. That gives 1,071 non-identity classes, or 1,072 with the identity (tclose2.py, `classes`).
  - A board puts a pair (P_o, class) on each vertex o of the cube $\{0,1\}^3$. Here "three non-identity classes" means that exactly three distinct classes a, b, c occur and none of them is ().
  - Two classes are *tuned* when they are equal or their Klein groups K = ⟨generators⟩ ∪ {1} share a non-identity element. Only then can V_aV_b† have cancellations (H.17.12).
- **The group G_{48} (b).** An element is g = (π, m), with π a permutation of the three qubits (equivalently, of the parties) and m ⊆ {A, B, C} a set of qubits (a bit mask in F_2^3).
  - It acts on a string in two steps, exactly as `act` in t3sym.py. First z ↦ z ⊕ (x ∧ m): this is conjugation by the diagonal gate S on the qubits in m, since S X S† = Y, S Y S† = −X and S Z S† = Z. Then the qubit positions of x and z are permuted by π.
  - It acts on a class by acting on each generator and re-sorting. Any sign it introduces is absorbed into the real parameters β, γ, which a class does not record. Conjugation preserves anticommutation, so classes go to classes.
  - On cube labels o and differences D it acts by π.
  - *Why |G| = 48.* The S-parts form $(\mathbb{Z}_2)^3$. On unsigned strings each S-conjugation is an involution (S^2 = Z acts trivially up to sign), and they commute.
  - The permutations form S_3, of order 6, and they normalise the S-part: $\pi\, S_m\, \pi^{-1} = S_{\pi(m)}$. So $G_{48} = (\mathbb{Z}_2)^3 \rtimes S_3$, the hyperoctahedral group of order 8 · 6 = 48.
  - Checked: the 48 pairs (π, m) give 48 distinct permutations of the 64 strings, and these are closed under composition.
  - The product is semidirect, not direct: permutations and S-masks do not commute. The earlier shorthand "$S_3 \times (\mathbb{Z}_2)^3$" is corrected here.
  - Every g is F_2-linear on (x, z) ∈ F_2^6.
- **Action on classes and orbits (c).** The orbit of a class c is $G_{48}\cdot c = \{g\cdot c : g \in G_{48}\}$, the set of classes reachable from c. Orbits partition the 1,071 classes. t3sym.py uses the lexicographically smallest member, min_g g·c, as the orbit's representative. Result: **61 orbits**, 9 of two-term classes and 52 of three-term classes [PROVED by enumeration].
- **Why one representative per orbit suffices (d).** For g = (π, m), define g·U by $U_o \mapsto S_m\, P_{\pi^{-1}o}\, V\, S_m\dagger$ with qubits permuted by π. [PROVED]
  - (i) Unitarity and admissibility are preserved: conjugation and relabeling preserve unitarity, and the forbidden-string form ((x|z) ∧ D) = D of the Pauli rule H.8.1 depends only on x and x∨z, which S does not change, and it is covariant under π.
  - (ii) $p_{g\cdot U}$ is p_U with the parties relabeled by π. The left S_m is diagonal, so it does not change any computational-basis probability. The right $S_m\dagger$ is absorbed into the source state, which ranges over all states anyway.

    - (iii) The PF hull is invariant under party relabelings.
    - (iv) Every finite object the search uses is the image under the same F_2-linear map: the forbidden-string rule ((x|z) ∧ D) = D (S preserves x and x∨z), the pair supports and pattern lists of H.17.12, the tuned relation, the groups H of H.17.11a and the test SH_grp^r.
    - Hence U is a counterexample if and only if g·U is. So if a counterexample with first tuned class a exists, one exists with first tuned class equal to the representative of a's orbit. Checking the 61 representatives (with b and c over all classes) is therefore exhaustive.
- **Status words (e).**
    - An orbit is **PROVED** (completed) when tclose3g.py has finished every job whose first tuned class is that orbit's representative, and every candidate and every UNRESOLVED job has then been eliminated by the triple-consistency lemma (tclose3g_cand.py). It follows that no counterexample has its first tuned class in that orbit.
    - An orbit would be **still being searched** (OPEN) if its jobs had not all been run and checked. The search has now finished (tclose3g.log: 61 of 61 orbits, 5,659,539 jobs), and tclose3g_cand.py has been run on all of it, so no orbit is in this state any more. All 61 are PROVED.
    - "**Genuine**" is not a status of these class orbits. It refers to the *facet* orbits of J.1 and H.17.5: orbits of PF-hull facet inequalities under relabelings of parties, settings and outcomes. There, "genuine" means not equivalent to positivity (orbit 92 is positivity, leaving 22 genuine). Class orbits and facet orbits are different objects that happen to share the word "orbit".
- **Lemma (triple consistency) [PROVED].** Let V_a, V_b, V_c be unitaries with Pauli expansions. Write S_{xy} = supp(V_x V_y†), a set of unsigned strings.
    - Then $S_{ac} \subseteq S_{ab} \oplus S_{bc} := \{s \oplus t : s \in S_{ab}, t \in S_{bc}\}$, and the same holds for the other two orderings.
    - *Proof.* V_aV_c† = (V_aV_b†)(V_bV_c†). Expanding both factors, every term of the product is a phase times the string s ⊕ t, with $s \in S_{ab}$ and $t \in S_{bc}$. Cancellation can only remove terms.
    - The condition is unchanged by the job translations $(S_{ab}, S_{ac}, S_{bc}) \mapsto (S_{ab} + t_b, S_{ac} + t_c, S_{bc} + t_b + t_c)$. A job whose supports violate it has no unitary realisation, so it cannot be a counterexample.

Symmetry group [PROVED]. Let $G_{48} = (\mathbb{Z}_2)^3 \rtimes S_3$ (defined above). It acts by permuting the three qubits, applied to Pauli strings and cube labels together, and by conjugating with a diagonal S gate on any subset m of the qubits. On strings the S part acts as z ↦ z ⊕ (x ∧ m).

- Qubit permutations relabel the parties, so they preserve admissibility, the Pauli rule H.8.1 and the PF hull.
- For the S part, write $U_o = P_o V_k \mapsto S P_o V_k S\dagger$. The left S is diagonal, so it does not change p(i|o). The right S† is absorbed into the source state.
- The S part preserves X-parts and x∨z, so it preserves the forbidden-string rule ((x|z)&D)==D. It also preserves which pair supports are nontrivial, so it preserves SH_grp^r and the groups H of H.17.11a/H.17.14.
- Hence a board is a counterexample if and only if its image is.
- Output flips, cube translations and a global left Pauli are already quotiented out by the WLOG root (o = 0, P = 1) and the translation normalisation. G ↔ G† maps a support to the same support (supp V† = supp V up to the Pauli map), so it gives no further reduction.
- Under G_{48} the 1,071 non-identity classes fall into 61 orbits: 9 orbits of 2-term classes and 52 of 3-term classes.

Reduction. A board with exactly three non-identity classes and a tuned pair can be relabelled so that (a,b) is tuned. Then apply $g \in G_{48}$ so that a is an orbit representative. Here b runs over every class tuned with a, and c runs over

every non-identity class.

- Boards using fewer classes are covered by H.17.13. Boards containing the identity class are covered by H.17.14. Boards with no tuned pair are generic and covered by H.17.9.
- Pair supports (S_{ab}, S_{ac}, S_{bc}) are taken from the H.17.12 lists, using "any nonempty subset of K" when K = K′, which is sound.
- Jobs equal up to the class-wise translations (S_{ab}, S_{ac}, S_{bc}) ↦ ($S_{ab}+t_b$, $S_{ac}+t_c$, $S_{bc}+t_b+t_c$) are solved once. This gives 17,855 jobs per 2-term orbit and 105,747 for each 3-term orbit completed so far, about $5.7\cdot10^6$ jobs in all if that count holds for every orbit. Before the reduction there were $5.3\cdot10^7$ pattern products for the representatives alone, and about $1.5\cdot10^8$ class triples.

Search. The search is the same arc consistency plus DFS as in H.17.14, with 192 values (P, class) per vertex.

- At the root, the absorbed class a must fail SH_grp^r at a pair at o = 0, with each of the three classes allowed at o.
- A leaf counts as a candidate only if all three classes occur and SH_grp^r fails for every absorbed class. The test uses the Pauli-factored groups of H.17.14, and groups merge when a pair support is monomial.
- Each job has a node budget of $2\cdot10^5$. Jobs that exhaust it are re-run with budget $2\cdot10^7$ (tclose3g_unres.py).

Results (run finished Oct 24 2026, 00:11 CDT).

- **Coverage.** tclose3g.py completed all 61 orbits (9 2-term and 52 3-term representatives a): 5,659,539 jobs in all, that is 17,855 per 2-term orbit and 105,747 per 3-term orbit (log line `SUMMARY orbits 61 of 61 jobs 5659539 cand 188 unres 1274`).
- **Raw outcome.** 188 candidates (in 20 orbits) and 1,274 jobs that exhausted the $2\cdot10^5$ node budget (UNRESOLVED; in 58 orbits). Three orbits (3, 6 and 8, all 2-term) returned neither. Per-orbit counts are in tclose3g_classify.log.
- **All eliminated by triple consistency [PROVED; tclose3g_cand.py, tclose3g_classify.py].** Every one of the 188 candidates and every one of the 1,274 UNRESOLVED jobs violates the triple-consistency lemma below. So none of them has a unitary realisation, and no bigger budget or numerical realisation is needed. Since no candidate passes the check, there was nothing to realise numerically as a board outside conv(PF).
  - *How they fail.* Every UNRESOLVED job has at least one single-string (monomial) pair support, and 994 of the 1,274 have two. A monomial $S_{xy} = \{s\}$ makes V_x a Pauli string times V_y, so the other two supports must be translates of each other, and in these jobs they are not. Of the 188 candidates, 155 have a monomial pair support. The other 33 have none, and each violates at least one of the three inclusions.
  - *The check is not vacuous [NUMERICAL control].* Among all jobs, 16,715 of 17,855 (orbit 0) and 101,637 of 105,747 (orbits 9 and 30) are triple-consistent. So the lemma removes only about 4–6% of the jobs, and every flagged job happens to lie in that small set. The supports ((0,4,32,36),(4),(0,4,32,36)) of the two known three-class tuned boards are consistent, and the solver finds no counterexample for them (tclose3g_ctrl.log).
- **Theorem H.17.15 [PROVED, in the per-class-pair model with over-approximating supports used since H.17.13].** Every admissible ≤3-term board whose distinct unitaries (up to left Paulis) are three non-identity classes, with at least one tuned pair, is a PF blend for every source state. With H.17.9, H.17.13 and H.17.14, this covers **every ≤3-term board with at most three distinct classes**. Orbit status: 61 PROVED, 0 counterexamples, 0 unresolved.

Controls.


- *Loosened test.* With the failure test loosened to "any cross pair, all three classes present", the solver finds boards for 5 of 200 sampled orbit-0 jobs, so the search is not vacuous.
- *Known boards.* The two known three-class tuned boards (tb_25_3980, tb_26_554; H.17.12d) have pair supports ((0,4,32,36), (4,), (0,4,32,36)). For these supports the loosened solver finds a board, so the real board is representable. The real solver finds no counterexample (tclose3g_ctrl.log).

Structural reduction [attempted; not achieved]. We tried to absorb one class of a ≥3-class board via H.17.11a so that the identity case H.17.14 would apply. This does not reduce the problem. After right-absorbing V_c, the new unitaries U_oV_c† are again ≤3-term only when the ratio supports stay small. In the K = K′ case, V_aV_c† can have 3 or 4 terms. Likewise "classes sharing one group H merge" is false in general. Two classes with the same H but a 3-term K = K′ ratio do not become one class, and their joint coset condition is exactly what the search checks. So the three-class case is handled only by enumeration.

≥4 classes [OPEN]. The per-class-pair model extends verbatim, with (k choose 2) fixed pair supports and the same root and leaf tests. A cube has 8 vertices, so k ≤ 8. However, the number of jobs grows by a factor of about 10^3–10^5 per extra class. No reduction of the ≥4-class case to the ≤3-class case is known. A ≥4-class counterexample would have to fail SH_grp^r for every absorbed class. Its restriction to the vertices carrying three classes is not itself a board, so H.17.15 does not apply to it. *Update:* see H.17.16 for reductions (Lemmas A–C), an exhaustive search of the Klein-cluster family and numerics. The case remains OPEN.

*H.17.16 Four or more classes: reductions, a Klein-cluster search, and numerics (Oct 24 2026) [lemmas PROVED; Klein-cluster search (k = 4) PROVED, all 21 K-orbits; numerics NUMERICAL; the general ≥4-class case remains OPEN] (h17/tclose4.py, tclose4.log, tclose4_done.txt.gz checkpoint; h17/nsearch4.py, ns4_.log/.json; h17/realize4.py, realize4_*.log).**

Question. Is four Pauli terms per outcome really the minimum for a board outside conv(PF)? By H.17.9 and H.17.13–H.17.15, every admissible board with ≤3 terms per outcome and **at most three** distinct classes is a PF blend. What is left is ≤3-term boards with **at least four** distinct classes. Here "distinct" means distinct up to a left Pauli: two vertices whose unitaries differ only by a left Pauli count as the same class. This section reduces that case, searches its most cancellation-rich family exhaustively, and searches numerically. It does not close the case. Graded note 83 has a picture of what a four-term operator does (docs/figs/fourterms.png, drawn by docs/figs/fourterms.py from the H.13.2 table): one term is one history, while H.13.2 at o = 001 splits 000 into four signed branches of amplitude ±½ that can interfere.



Lemma A (one-string supports merge classes) [PROVED]. If S_{xy} = supp($V_x V_y^\dagger$) is a single string {s}, then $V_x V_y^\dagger = \lambda Q_s$ with $|\lambda| = 1$. So $V_x = \lambda Q_s V_y$, which is V_y up to a left Pauli (the phase goes into P_o). Consequence: in a board with exactly k distinct classes, no pair of the k classes has a single-string support. (H.17.15 already used this. All its UNRESOLVED jobs had such a support.)

Lemma B (edges force constant directions) [PROVED]. Let o and $o \oplus e_p$ be adjacent along party p's direction e_p, with $U_o = P V_x$ and $U_{o \oplus e_p} = P' V_y$. The Pauli rule H.8.1 with $D = e_p$ forbids every string of $U_o U_{o \oplus e_p}^\dagger = P(V_x V_y^\dagger)P'^\dagger$ that acts non-trivially on qubit p. Let a be the qubit-p part of $P \oplus P'$. Then every $s \in S_{xy}$ has the same qubit-p part a: the ratio is *p-constant*. Corollaries:

- (B1) If S_{xy} contains 1 and some string that is non-trivial on qubit p, then x and y are never adjacent along p.
- (B2) An **untuned** pair has the generic support {1, A, B, A′, B′, …}, which contains 1 (H.17.12): its identity coefficient is $\alpha\alpha' \neq 0$, because the two Klein groups share no non-identity string. ($\alpha = 0$ cannot occur in a 3-term class, since $i(\beta A + \gamma B) = iA(\beta + \gamma AB)$ is a 2-term class up to a left Pauli.) It also contains each generator, with coefficient $\propto \beta\alpha'$ etc. So two untuned classes can be adjacent along p only if all their generators are trivial on qubit p.
- (B3) By Lemma A, distinct classes never have a single-string support. So the class-change edges along each direction p join only pairs whose ratio is p-constant.

Lemma C (triple consistency) [PROVED, H.17.15]. For every triple x, y, z of classes in the board, $S_{xz} \subseteq S_{xy} \oplus S_{yz}$. With k classes this gives (k choose 3) necessary conditions on the (k choose 2) pair supports.

Where the open case sits [PROVED]. H.17.9 covers every *generic* board (all pair supports generic, the untuned model) for any number of classes. So a ≥4-class counterexample must have ≥4 distinct unitaries **and** at least one tuned pair whose support is cancelled or reduced, as classified in H.17.12.

No gluing lemma [OPEN]. We looked for a lemma that would deduce the k-class case from the (k−1)-class or 3-class case. None was found. The obstruction: a board's restriction to the vertices that carry three of its classes is not a board, because the vertex set is not the whole cube. So H.17.15 cannot be applied to it. A counterexample

must fail SH_grp^r for **every** absorbed class (H.17.11a), and nothing we know forces that failure into a three-class sub-configuration. Right-absorption does not reduce the class count either, for the reason given in H.17.15's "structural reduction" paragraph.

Size of a full search [estimate]. The tclose3g scheme extends directly: k classes, (k choose 2) fixed pair supports, and the same root and leaf tests with 64k values per vertex. Naively there are about $1.1 \cdot 10^5$ triple jobs per 3-term orbit × ≥1,071 fourth classes ≈ $1.1 \cdot 10^8$ per orbit, so about $7 \cdot 10^9$ over the 61 orbits. Translation deduplication saved 9.4× in tclose3g, which would leave about $7.5 \cdot 10^8$ jobs. At 4–8 ms per job per core, that is days to weeks on the 8-core box, so it was **not run**. k = 5 and 6 are larger still. (Generating the k = 5 Klein-cluster jobs below ran out of the box's 15.6 GB of memory.)

Exhaustive search of the Klein-cluster family KC, k = 4 [PROVED, all 21 K-orbits; over-approximating supports as in H.17.13–H.17.15].

- **Family.** Fix a Klein group K = {1, A, B, AB}, with A and B anticommuting. Then every class uses only strings from K: the 2-term classes (A), (B), (AB) and the 3-term classes (A,B), (A,AB), (B,AB). This is the most cancellation-rich family. The 3-term classes all have Klein group K, so any pair involving a 3-term class is tuned and its support may be cancelled. Only pairs of two different 2-term classes, such as (A) and (B), are untuned. There are 336 Klein groups. Under G_{48} (H.17.15(b)) they fall into **21 orbits**, and one representative K per orbit suffices, by the same argument as H.17.15(d).
- **Jobs.** Take every 4-subset of the six classes. Every 4-subset contains at least one 3-term class, and its first one is absorbed at the root. Assign every pair a support from the H.17.12 lists (any nonempty subset of K when K = K′). Then apply filter A (Lemma A: no single-string support) and filter C (Lemma C on all four triples), and deduplicate. Both filters are necessary conditions, so the search stays exhaustive. For K_0 = (1, 8, 9), the 284,391 raw support assignments drop to 115,911 after filter A and to 88,695 jobs after filter C. Every completed block has 88,695 jobs (tclose4.log).
- **Search.** The same arc consistency plus DFS as tclose3g, with 256 values (P, class) per vertex and a node budget of $2 \cdot 10^5$. The root and leaf tests are those of H.17.15: all four classes must occur, SH_grp^r must fail for every absorbed class, and groups merge when a pair support is X-monomial.
- **Result. All 21 K-orbits completed** (tclose4.log: `SUMMARY blocks 21 jobs 1862595 cand 0 unres 0`). That is 21 × 88,695 = 1,862,595 jobs, with **0 candidates and 0 UNRESOLVED jobs** (none exhausted the $2 \cdot 10^5$ budget). So no admissible ≤3-term board whose classes are four distinct members of one Klein cluster fails SH_grp^r for every absorbed class. Every such board is therefore a PF blend for every source state (H.17.11a) [PROVED, in the per-class-pair model with over-approximating supports]. This settles one family only. Four classes not confined to a single Klein group are not covered.
- **The search is not vacuous [NUMERICAL control].** With the leaf test loosened to "all classes present, any cross pair", the solver finds a board for 40 of 40 sampled K_0 jobs. So every sampled job admits a pattern-compatible structure, and the zero counts come from the SH_grp^r test, not from empty domains.

Realising Klein-cluster structures [NUMERICAL] (realize4.py). For random KC k = 4 jobs, the loosened solver was asked for a *hard* structure: no party that is operator-last, meaning identical states on all of its edges. Then least squares was used to look for real class parameters, $V = p_0 + i\Sigma p_m H(g_m)$ with every $|p_m| \geq 0.05$, that satisfy the Pauli rule exactly. A first version without the hardness filter did realise 4-class boards, for example classes (A,B), (A,AB), (B,AB), (A). But all of them had an operator-last party (all P = 0, identical along C), so they are trivial PF blends, and their facet maxima were ≈ $3–4 \cdot 10^{-15}$. The final runs (seeds 1–3, each 400 random draws with replacement over all 21 K-representatives, node budget $3 \cdot 10^6$; realize4_1–3.log) used the hardness filter. In **all 1,200 draws**, the exact solver *completed* and found **no** pattern-compatible 4-class structure that has no operator-

last party and places some vertex in a group different from (not merged with) the absorbed class: 1,200 "no_hard_struct", 0 UNRESOLVED. So there was nothing to realise. This is exact for each job drawn (in the over-approximating support model), but it is a random sample of jobs, not an exhaustive check, so the sample as a whole is NUMERICAL. It is stronger than the SH_grp^r test result: in the jobs sampled, the pattern constraints already force a trivial (operator-last) board.

Numerical search ignoring class count [NUMERICAL] (nsearch4.py). This is nsearch2b extended to up to 8 classes, with an optional bias towards opening a new class at each vertex (probability 0.9–1.0). Seeds 41–45 were unbiased and 46–48 biased; 44 and 45 were stopped early. Totals: 39,206 complete admissible boards, of which 5,800 are hard (no operator-first or operator-last party). Of the hard boards, 5,790 have one distinct unitary up to left Paulis, 10 have two, and **none has ≥3**. The best facet value over all hard boards is $6.1\cdot10^{-15}$, and the largest Pauli-rule residual is $6.8\cdot10^{-31}$. So random admissible ≤3-term boards essentially never carry several genuinely different unitaries: the rule couples the classes so tightly that they collapse. No board outside conv(PF) was found.

Status [summary].

- PROVED: Lemmas A–C, and the fact that the open case needs ≥4 distinct unitaries with a cancelled tuned pair.
- PROVED (exact, exhaustive): every admissible ≤3-term board with **exactly k = 4 distinct classes, all four drawn from one Klein cluster** {(A),(B),(AB),(A,B),(A,AB),(B,AB)}, is a PF blend for every source state. All 21 of 21 G_{48}-orbits of Klein groups were searched: 1,862,595 jobs, 0 candidates, 0 UNRESOLVED. *Scope:* the per-class-pair model of H.17.13–H.17.15, with one support per class pair taken from the H.17.12 pattern lists (over-approximated by every nonempty subset of K when K = K′), and the root and leaf tests of tclose3g. The reduction to orbit representatives is the H.17.15(d) argument applied to Klein groups.
- NUMERICAL: no violation in nsearch4 (5,800 hard boards, none with ≥3 distinct unitaries) or realize4 (1,200 sampled KC jobs, none admitting a hard 4-class structure).
- OPEN:
  - k = 5–8 classes inside one Klein cluster. The cluster has only 6 classes, so k ≤ 6 there. Job generation for k = 5 and 6 ran out of memory and was not attempted further. *Update (H.17.16b):* with streamed generation, k = 5 is half done (52 of 104 blocks, all clean) and running; k = 6 is estimated at $\geq1.5\cdot10^{8}$ jobs. *Update (H.17.16c):* k = 5 finished, 104 of 104 blocks clean; k = 6 was not run. Both cases are vacuous by the class bound H.17.17.
  - Every k ≥ 4 board whose classes are **not** confined to a single Klein group, for example four classes spread over several Klein groups. The size estimate above puts the full k = 4 search out of reach on this box.
  - Hence the statement "four terms per outcome is the minimum" is still OPEN. No counterexample with ≤3 terms is known, and none was found here. *Update (H.17.17):* at most four classes can occur, and the four-class case is reduced to a finite search that is running. *Update (Round 19, H.26.1):* that search finished clean, so the statement is PROVED in the per-class-pair model.

Reproducing. Run `cd code/stochastic/cyclic/switchboard/h17 && NPROC=5 python3 tclose4.py 4` (about 35 minutes on 5 cores). It checkpoints each block to tclose4_done.txt.gz, so an interrupted run resumes when the same command is rerun. Do not run k = 5 or 6 with tclose4.py (job generation runs out of memory); use the streamed tclose56.py of H.17.16b.

H.17.16b Round-7 update: streamed k = 5 search, a cross-cluster sample, and a counting fact (Oct 24 2026) [generator and reductions PROVED sound; finished k = 5 blocks PROVED (same model and scope as

H.17.16; all 104 finished, see H.17.16c); cross-cluster sample NUMERICAL; gluing OPEN] (h17/tclose56.py, tclose56.log, tclose56_done.txt.gz; h17/tclose4x.py, tclose4x_1.log, tclose4x_1.jsonl).

- **Streamed job generation [PROVED sound].** tclose56.py produces exactly the job set of H.17.16 without storing it. It runs a backtracking loop over the class pairs (a depth-first enumeration that assigns one pair support at a time and undoes it on failure). Each pair's support list is deduplicated and filtered by Lemma A, and Lemma C is tested as soon as the last of a triple's three pairs is assigned. Each finished assignment is sent straight to the worker pool. Both filters are necessary conditions, so nothing admissible is lost. *Validation:* for k = 4 and K_0 it yields 88,695 jobs, the same number as tclose4.py. Memory stays at about 25 MB per worker; the old generator ran out of memory at k = 5.
- **Stabiliser reduction [PROVED].** The *stabiliser* Stab(K) of a Klein group K is the set of elements of G_{48} (H.17.15(b)) that map K onto itself. Its size ranges from 1 to 16 over the 21 orbits. Each such element permutes the six classes of the cluster, maps admissible boards to admissible boards, and preserves "SH_grp^r fails for every absorbed class" (the H.17.15(d) argument). So it suffices to search one class subset per Stab(K)-orbit, the lexicographically smallest one (the *canonical* subset). Blocks are run in order of increasing size.
- **k = 5 inside one Klein cluster [PROVED for the finished blocks; the rest is running at the time; *finished, see H.17.16c*].** There are 104 canonical blocks (pairs of a K-representative and a 5-subset). Blocks with two three-term classes have 8,019 jobs each. Blocks with all three three-term classes have about $7.3 \cdot 10^5$ jobs each. Status at commit time: 52 of 104 (all 52 blocks with two three-term classes) blocks finished, 416,988 jobs, **0 candidates and 0 UNRESOLVED** (tclose56.log). *Round-8 update:* 54 of 104 blocks (1,867,698 jobs), still 0 candidates and 0 UNRESOLVED. By Theorem H.17.17 no five-class board exists, so this run is a consistency check only. The remaining blocks run in the background. Each block is checkpointed to tclose56_done.txt.gz, and rerunning `NPROC=4 nohup nice -n 5 python3 tclose56.py 5 >> tclose56.log 2>&1 &` resumes the run. The estimated total is about $3.8 \cdot 10^7$ jobs ≈ 63 core-hours (about 16 hours on 4 cores).
- **k = 6 [estimate; not run].** There is one block per K (all six classes). A partial generation already exceeds $7.1 \cdot 10^6$ jobs per K, so the total is at least about $1.5 \cdot 10^8$ jobs, or about 250 core-hours. That is out of reach without more hardware, and none was rented.
- **Cross-cluster k = 4 sample [NUMERICAL] (tclose4x.py).** A tuple of four classes is drawn as follows: a is a G_{48}-orbit representative of a three-term class; b is tuned with a, since by "Where the open case sits" a tuned pair is needed; c and d are any further classes, the identity included. Every filtered support assignment of the tuple is then solved exactly with the H.17.16 solver. Result (final, Round 8): 20,000 tuples (seed 1), 278,194 jobs, **0 candidates, 0 UNRESOLVED**. The mean is 13.9 jobs and 0.074 s per tuple. (At the Round-7 commit: 9,466 tuples, 132,146 jobs, also clean.) Each sampled tuple is settled exactly, but the sample as a whole is NUMERICAL evidence only.
  - *Cost of the full search.* With a fixed to its orbit representative, the tuple space has $4.41 \cdot 10^9$ elements. This overcounts: it includes c, d pairs already excluded by Lemma A and some G_{48}-equivalent duplicates. At the measured 0.074 s per tuple, that is about $9 \cdot 10^4$ core-hours, roughly 2.6 years on 4 cores. The figure of about $7.5 \cdot 10^8$ jobs in H.17.16 counted only triple jobs times a fourth class, so it was an underestimate. Even granting the remaining Stab(a) symmetry (at most 48), the search stays at about $2 \cdot 10^3$ core-hours or more. The full cross-cluster search is therefore **not feasible on this box**. *Superseded (H.17.17):* by the class bound, a four-class board has a rigid shape, and the whole four-class case is the search of 2,722 canonical geometries (about $2.8 \cdot 10^6$ jobs) of H.17.17, which is feasible.

- **A counting fact [PROVED].** Suppose a board on the 8 vertices of the cube has exactly k classes, and s of them occur at only one vertex. Every other class occupies at least two vertices, so $s + 2(k - s) \le 8$, that is, $s \ge 2k - 8$. For k = 5 at least two classes are *singletons* (occur at a single vertex), and for k = 8 all of them are. By Lemmas A and B, all three edges at a singleton's vertex are class-change edges whose ratio supports are p-constant in their own direction. This constrains a ≥5-class board, but it does not reduce it to fewer classes. *Sharpened in H.17.17:* there are no singletons at all (s = 0), so $k \le 4$.
- **Gluing [OPEN in Round 7; see H.17.17].** No reduction from ≥4 classes to the proved cases was found (see H.17.16 "No gluing lemma"). The counting fact and the stabiliser reduction are the only structural gains this round. Round 8 (H.17.17) replaces gluing by a class bound: $k \le 4$, and k = 4 is a finite search.

H.17.16c The k = 5 Klein-cluster run finished (Oct 25 2026) [PROVED, exhaustive exact search, same model and scope as H.17.16; a consistency check of Theorem H.17.17, not new coverage; coverage audit PROVED by an independent recount; k = 6 not run] (h17/tclose56.py, tclose56.log, tclose56_done.txt.gz; tclose56_audit.py, tclose56_audit.log).

Statement [PROVED, per-class-pair model]. Let K be any Klein group of three-qubit Paulis and choose any 5 of the 6 classes of its cluster {(A),(B),(AB),(A,B),(A,AB),(B,AB)}. Give each class pair one support from its H.17.12 pattern list (over-approximated by every nonempty subset of K when the two Klein groups coincide), keep only assignments that pass Lemma A (no single-string support) and Lemma C (triple consistency). Then no admissible board on the cube uses all five classes and fails the right-absorbed test SH_grp^r for every choice of absorbed class. Equivalently, every such five-class board, if one existed, would be a PF blend for every source state. This is the H.17.16 statement with k = 5 in place of k = 4.

Result. All **104 of 104** canonical blocks (21 G_{48}-orbits of Klein groups × Stab(K)-orbits of 5-subsets) finished: **38,135,448 jobs, 0 candidates, 0 UNRESOLVED** (no job hit the solver budget). There are 52 blocks with two of the three three-term classes (8,019 jobs each, 416,988 jobs) and 52 blocks with all three (725,355 jobs each, 37,718,460 jobs). tclose56.log ends with `SUMMARY k 5 {"jobs": 38135448, "cand": 0, "unres": 0} (this invocation)`. The phrase "this invocation" is harmless here: the log has a single header line, `k 5 Klein orbits 21 blocks 104 done 0`. So one invocation started from an empty checkpoint and ran all 104 blocks. The partial counts of Rounds 7 and 8 came from an earlier, discarded checkpoint. Wall time was 133,887 s (about 37.2 hours; finished Oct 25 2026, 7:27 PM CDT) with the documented NPROC=4 worker pool. That is about 149 core-hours, more than the 63 core-hours estimated in H.17.16b.

Coverage audit [PROVED by direct recount] (tclose56_audit.py, tclose56_audit.log). The audit does not use tclose56.py's block bookkeeping. It was modelled on glue_k4_audit.py (H.26.1a).

1. It re-enumerates all Klein groups (336) and their G_{48}-orbits (21), and checks that tclose4.klein_reps() returns exactly the 21 orbit minima. The orbit sizes sum to 336.
2. For each representative it recomputes Stab(K) and the Stab(K)-orbits of the six 5-subsets with its own union-find. This gives **104 expected blocks**.
3. It matches the 104 checkpoint records to these orbits (by orbit membership, not by the chosen representative): **104 covered, 0 missing, 0 duplicates, 0 extra**. Every record has cand = [] and $n_{unres} = 0$, and the jobs sum to 38,135,448.
4. Every block line of the log agrees with its record.
5. It recounts the jobs of **all 104 blocks** with an independent eager generator: a full itertools.product over the deduplicated pattern lists, with Lemmas A and C applied afterwards, in place of the backtracking generator.

It finds **0 mismatches**. For example, the three-three-term block of K_0 has a raw product of 970,299 assignments, of which 725,355 survive the filters.

What it adds over k = 4. Logically, nothing new is needed. By Theorem H.17.17 (PROVED, also in Lean under stated hypotheses) an admissible ≤3-term board has at most four classes, so five-class boards do not exist and the statement above is vacuously true. H.26.1 already settles "four terms per outcome is the minimum" from k ≤ 4 and the 2,722-geometry four-class search. The value of this run is as an **independent consistency check**. A different code path (the Klein-cluster family, streamed generation and the tclose4 solver, rather than the glue_k4 geometries) reaches the same conclusion for five classes without using the class bound. Had it found a candidate, either the class bound or the model would have been wrong. The loosened cross-check of H.17.17 (glue_k5check: 0 of 90 sampled k = 5 jobs admit any five-class board) points the same way.

What remains. k = 6 inside a Klein cluster was **not run**; the estimate is at least $1.5 \cdot 10^8$ jobs. It is also vacuous by H.17.17, so nothing depends on it. Five-class boards whose classes are not confined to one Klein cluster were never searched directly; they too are excluded only by the class bound.

Caveats.

- The search code is not formally verified. Only the class bound and Lemma H are in Lean.
- The solver and the generator use only integer bit operations on 6-bit Pauli labels and boolean numpy arrays. There is no floating-point arithmetic, so no rounding question arises.
- The statement inherits the scope of H.17.16: the per-class-pair model, over-approximating supports, and the root and leaf tests of tclose3g/tclose4. The symmetry reduction is the H.17.15(d) argument applied to Stab(K).

Reproducing. Run `cd code/stochastic/cyclic/switchboard/h17 && NPROC=4 nohup nice -n 5 python3 tclose56.py 5 >> tclose56.log 2>&1 &` (about 37 hours on 4 cores; it resumes from tclose56_done.txt.gz). The audit is `python3 tclose56_audit.py -1 > tclose56_audit.log` (about 9 minutes; the argument 6 recounts only a sample). SHA-256 at commit:

- tclose56.py `3ffa5d369c3147a2972645e6326a11f75137a344caf670588e8be6f245426e28`;
- tclose56.log `7ea8dd29e5904a3e99e6d5cc2f6f9e193a4d3f8cd5e757ae9209b64c1a56dece`;
- tclose56_done.txt.gz `fbf55bc1bdb2cec61cb8715cabc6fce8cc0e3ccf987380d1f0304cdeacd906bb`;
- tclose4.py `31473ded4a2093a4dc5f2080b317eba26b5c7c21828ae87d98a30adbf38ead59`;
- tclose3.py `9eac0647e3d2db9a186e6689c6bba8661360985cd667cccc5005b7b875182084`.

H.17.17 The gluing lemma: rigid directions, at most four classes, and a finite four-class search (Oct 24 2026) [Lemma D, Lemma H and the class bound PROVED; Lemma H and the class bound also PROVED (Lean), under stated hypotheses; four-class case reduced to a finite search of 2,722 geometries, PROVED for all 2,722 (Round 19, H.26.1; per-class-pair model of H.17.13–H.17.16); facet-locality numbers NUMERICAL] (h17/glue_local.py, glue_adj.py, glue_k4enum.py, glue_k4canon.py, glue_k4.py, glue_k5check.py, glue_facets.py and their .log files; glue_k4_tuples.json, glue_k4_canon.json, glue_k4_done.jsonl, glue_k4_loose.jsonl).

Goal. H.17.16 and H.17.16b left one case open: admissible ≤3-term boards with **four or more** distinct classes. We wanted a gluing lemma, an argument that reduces this case to the proved ones (≤3 classes: H.17.9, H.17.13–H.17.15; Klein clusters: H.17.16; Lemmas A–C; the counting fact $s \geq 2k - 8$ of H.17.16b). The lemma we found does not glue small boards together. It shows that large boards cannot exist: a ≤3-term board has at most four classes, and a four-class board has a rigid shape that a finite search can cover completely.

Definitions used below.

- A **class** is a unitary up to a left Pauli, as in H.17.16: $U_o = P_o V_{\kappa(o)}$. Its **label** is its Pauli support type, as in H.17.12: (), (A), or (A, B) with A and B anticommuting. Two different classes can share a label, if their parameters differ. The identity class (label ()) is the class of the Paulis themselves.
- For a qubit (= party) p, the **qubit-p part** of a Pauli string is its single-qubit factor on p (one of I, X, Y, Z).
- A qubit p is **rigid** for a non-identity class x if the strings in supp V_x have pairwise distinct qubit-p parts. A cube direction e_p is rigid for x when the qubit p is.
- A support S is **p-constant** if all its strings have the same qubit-p part (Lemma B).
- Absorbed class, groups, H_ρ and SH_grp^r are as in H.17.11a.

Lemma D (failure witnesses are local) [PROVED]. Fix the absorbed vertex r. For a vertex o write $W_o = U_o U_r^\dagger$ and let Aff_o be the affine hull, over F_2, of the X-parts of supp W_o. The refined SH_grp^r test of H.17.11a fails at the pair (o, q) exactly when (i) $W_o W_q^\dagger$ is not X-monomial, and (ii) Aff_o ⊕ Aff_q contains a vector v with $v \wedge D = D$, where $D = o \oplus q$. Since $W_o = P_o(V_{\kappa(o)}V_{\kappa(r)}^\dagger)P_r^\dagger$, we have Aff_o = $x(P_o) \oplus x(P_r) \oplus$ aff $X(S_{\kappa(o)\kappa(r)})$, and $x(P_r)$ cancels in Aff_o ⊕ Aff_q. So whether (o, q) fails depends only on $x(P_o \oplus P_q)$, D, and the supports $S_{\kappa(o)\kappa(r)}$, $S_{\kappa(q)\kappa(r)}$ and $S_{\kappa(o)\kappa(q)}$: that is, on at most three classes. *Proof.* Two vertices lie in the same group exactly when $W_o W_q^\dagger$ is monomial, and monomials form a group. Inside a group, left multiplication by a monomial shifts every X-part by the same vector, so Aff_o is a translate of the group's coset H_ρ by a(o), which is the test of H.17.11a. *Check [NUMERICAL]:* on all 80 saved tuned boards (tb_*.npz and tb4_*.npz) and every absorbed vertex, the full-matrix test and the local formula agree on all 17,920 pair tests (glue_local.log). Lemma D is what the tclose solvers already use. Its content is that a failure witness only involves ≤3 classes. That alone does not glue anything, because the other vertices still carry arbitrary classes. This is the obstruction recorded in H.17.16.

Lemma H (rigid directions) [PROVED].

- (i) Every non-identity ≤3-term class has a rigid qubit. For a two-term class $\alpha + i\beta A$, every qubit on which A acts is rigid: its parts are I and $a \neq I$. For a three-term class $\alpha + i(\beta A + \gamma B)$, A and B anticommute, so they anticommute on an odd number of qubits. On such a qubit p the parts of 1, A and B are I, a and b with $a \neq b$ both non-identity, so p is rigid.
- (ii) If p is rigid for $x = \kappa(o)$, then $o \oplus e_p$ carries the same class x.

Proof of (ii).

1. By Lemma B, every string of $U_o U_{\{o \oplus e_p\}}^\dagger$ acts trivially on qubit p. Hence $V_x V_y^\dagger = \sigma \otimes T$, where σ is a single-qubit Pauli on p (up to phase), T is a unitary on the other two qubits, and $y = \kappa(o \oplus e_p)$. So $V_y = (\sigma \otimes T^\dagger)V_x$.
2. Write $V_x = \Sigma_s c_s a_s \otimes R_s$, one term for each string s of supp V_x. Here a_s is its qubit-p part, R_s is the rest, and all $c_s \neq 0$. Rigidity says the a_s are pairwise distinct, so the σa_s are distinct too. Hence the terms of $V_y = \Sigma_s$

c_s (σa_s) $\otimes$ ($T \dagger R_s$) have disjoint supports, and $|\mathrm{supp}\ V_y| = \Sigma_s\ |\mathrm{supp}(T \dagger R_s)| = m \cdot |\mathrm{supp}\ T|$. Here $m = |\mathrm{supp}\ V_x| \in \{2, 3\}$, and multiplication by a Pauli only permutes strings.

3. Since $|\mathrm{supp}\ V_y| \le 3$ and $m \ge 2$, we get $|\mathrm{supp}\ T| = 1$. So T is a phase times a Pauli, V_y is V_x up to a left Pauli, and $y = x$. ∎

Check [NUMERICAL, independent route]. The rigid set can also be computed from the H.17.12 pattern lists: a direction q is non-rigid for x when some label y and some pattern S of (x, y) with $|S| \ge 2$ (Lemma A) is q-constant (Lemma B). This computation finds a rigid direction for all 1,071 non-identity labels. Its rigid set equals the analytic one for all 1,071 (glue_adj.log). The identity class has no rigid direction.

Theorem H.17.17 (class bound) [PROVED]. An admissible ≤3-term board has at most four classes. If it has exactly four, every class occupies exactly two vertices. The two vertices of a non-identity class form an edge along its rigid direction, and that class has exactly one rigid qubit.

- *Proof.* By Lemma H(ii), the vertex set of a non-identity class is closed under its rigid directions. It is therefore a union of edges, of even size ≥ 2. The identity class, if present, takes the remaining vertices, so its size 8 − (even) is also even and ≥ 2.
- This is the counting fact of H.17.16b with s = 0: there are **no singleton classes**, so $2k \le 8$ and $k \le 4$.
- If k = 4, every class has exactly two vertices. A non-identity class with two rigid directions would need ≥ 4 vertices.
- *Consequences.* The k = 5 and k = 6 Klein-cluster searches of H.17.16b ask about boards that do not exist. Their clean results are consistent with this, but no longer needed. The tclose56 run was left running as instructed. *Update (H.17.16c):* it finished all 104 k = 5 blocks with 0 candidates and 0 UNRESOLVED.
- *Cross-check [NUMERICAL] (glue_k5check.log):* the H.17.16 solver with its leaf loosened to "all k classes present" finds a board for 225 of 225 sampled K_0 jobs with k = 4, and for **0 of 90** with k = 5.

Machine check [PROVED (Lean)] (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/PFUL/LemmaH.lean; lean/STATUS.md; lean/LemmaH_axioms.log). Lemma H and the class bound are checked in Lean 4 with Mathlib. There is no sorry and no new axiom; `#print axioms` lists only propext, Classical.choice and Quot.sound.

- *The model.* A Pauli string is a vector in $(F_2^2)^3$. An operator is its Pauli expansion, a finitely supported map to $\mathbb{C}$. The product of expansions is the twisted convolution $\sigma_t\sigma_s = \varphi(t, s)\sigma_(t+s)$, and the proofs use only $\varphi \ne 0$.
- *Lemma H(i).* `rigid_two` and `rigid_three`: the supports {1, A} with A ≠ 1, and {1, A, B} with A, B anticommuting, each have a rigid qubit.
- *The counting step of (ii).* `card_support_tmul`: $|\mathrm{supp}\ W \cdot V| = |\mathrm{supp}\ W| \cdot |\mathrm{supp}\ V|$ when all strings of W share their qubit-p part and p is rigid for V.
- *Lemma H(ii).* `lemmaH_ii`: if moreover $|\mathrm{supp}\ V| \ge 2$, $|\mathrm{supp}\ W \cdot V| \le 3$ and $W \cdot V \ne 0$, then W is one Pauli string times a scalar.
- *The class bound.* For an abstract cube labelling closed along rigid directions, every class has even size ≥ 2, so k ≤ 4 (`RigidBoard.card_image_le_four`). If k = 4, every class has two vertices, and a non-identity class is one edge along its unique rigid direction (`card_class_eq_two_of_four`, `class_eq_edge_of_four`, `rigid_unique_of_four`).
- *End to end.* `classBound` combines these.
- *Hypotheses taken from the paper, not proved in Lean:*

    - the support shapes of H.17.12;
    - at most three terms, and nonzero class operators;
    - the factorisation $V_y = W \cdot V_x$ with W qubit-p-constant across a class-changing p-edge (step 1 of the proof of (ii): Lemma B plus unitarity);
    - labels are classes, i.e. operators that agree up to a left Pauli and a scalar carry the same label;
    - the identification of the twisted convolution with the Pauli multiplication table.

The four-class case is finite [PROVED enumeration] (glue_k4enum.py, glue_k4canon.py).

- *Labelled geometry.* A labelled geometry gives the class at each of the 8 vertices, together with each class's label. The enumeration lists every labelled geometry a four-class board can have:
    - pair the 8 vertices (105 pairings), with every pair an edge except possibly the identity class's;
    - give vertex 0 a G_{48}-orbit representative label; translations and G_{48} are symmetries (H.17.15(d)), and a non-identity class can always be moved to vertex 0;
    - label the other classes so that across every cube edge along q between different classes, some admissible pattern of the two labels is q-constant (Lemma B, with Lemma A);
    - allow at most one identity class; repeated labels are allowed.
- *Counts.* This gives 21,906 labelled geometries, and **2,722 up to cube translations × G_{48}** (canonical forms). The neighbour sets are small: for a non-identity label x and a non-rigid direction q, at most 76 labels can sit across a q-edge, and in 1,620 of 1,845 (label, direction) cases only 3 can.
- *Scope gain.* This covers what H.17.16 and H.17.16b left open: cross-cluster tuples, four classes with repeated labels (two classes with the same Pauli support type but different parameters, which the Klein-cluster search did not include), and tuples containing the identity class.

Exhaustive four-class search [PROVED, exhaustive exact search; same model and filters as H.17.16] (glue_k4.py).

- *Supports.* For each canonical geometry, each class pair gets every H.17.12 pattern, filtered by Lemma A, Lemma B (a pair adjacent along q needs a q-constant support) and Lemma C. For two three-term classes with the same Klein group, the exact list of H.17.12(b) is used, so the support {1, C} is dropped. This cuts the job count from about $1.14 \cdot 10^7$ to about $2.8 \cdot 10^6$. The first 261 geometries were run before this filter, with a larger (over-approximating) list; their clean results remain valid.
- *Paulis.* $P_0 = 0$, because a common left Pauli changes no string, no X-part difference and no admissibility condition. The other seven P_o run over all 64 Paulis, with arc consistency on the Pauli rule.
- *Quick exit.* If plain arc consistency on the Pauli rule (with $P_0 = 0$) already empties some vertex's domain, the job has no admissible board at all and is closed.
- *Root.* A pair at which SH_grp^r fails for the absorbed class of vertex 0. Every counterexample has one.
- *Leaf.* Three conditions:
    - no W-level-last party (every ratio along that party's edges has X-part set {0}; such boards are PF blends by H.1);
    - no operator-first party (every ratio acts trivially on that qubit; PF blends by H.6.2);
    - SH_grp^r fails for every absorbed class (Lemma D).
- *Why the hardness filter is needed.* Without it, the search returns boards such as all four classes stacked along one direction with all $P_o = 0$. Those fail SH_grp^r for every r, but one party is W-level last, so they are PF blends anyway.

- **Final result (Round 19, H.26.1) [PROVED, exhaustive exact search]:** all **2,722 of 2,722** canonical geometries finished (2,896,784 jobs), with **0 candidates and 0 UNRESOLVED** (glue_k4_done.jsonl; glue_k4.log ends with SUMMARY … cand 0 unres 0). How the exhaustive proof works, with a worked example, is in H.26.1a.
- **Result (status at the Round 8 commit, superseded):** 401 of 2,722 canonical geometries finished (248,597 jobs), **0 candidates and 0 UNRESOLVED** (glue_k4_done.jsonl, glue_k4.log). The remaining geometries run in the background on 3 cores at about 140 jobs/s, an estimated 5 hours more (about $2.8 \cdot 10^6$ jobs in total). Each finished geometry is checkpointed to glue_k4_done.jsonl, and rerunning `cd code/stochastic/cyclic/switchboard/h17 && NPROC=3 nohup nice -n 5 python3 glue_k4.py >> glue_k4.log 2>&1 &` resumes the run.
- *Control [NUMERICAL]:* with the leaf loosened to "hard board" (no SH test, no root), the first 200 geometries in enumeration order (1,768 jobs) give a hard admissible board in 18 of them. So the search space is not empty.

Conclusion [PROVED, in the per-class-pair model]. Combined with Theorem H.17.17 and the ≤3-class results (H.17.9, H.17.13–H.17.15), the open case is no longer a gluing problem. It is a **finite exact search** of 2,722 canonical four-class geometries, already running.

- If glue_k4 finishes all 2,722 with 0 candidates and 0 UNRESOLVED, then every admissible ≤3-term board is a PF blend in the per-class-pair model, and "four terms per outcome is the minimum" becomes PROVED in that model.
- Until then the statement stays **OPEN**. Its status is that of the H.17.16b k = 5 run: each finished geometry is settled exactly, and none has produced a candidate. (That run has since finished too; H.17.16c.)
- *Update (Round 19, H.26.1):* the condition is met. All 2,722 geometries finished with 0 candidates and 0 UNRESOLVED, so **every admissible ≤3-term board is a PF blend, and "four terms per outcome is the minimum" is PROVED, in the per-class-pair model** (over-approximating supports, with the hardness filter and the leaf test of glue_k4.py).
- An UNRESOLVED job (budget exhausted) would be rerun with a larger BUDGET. A candidate would be checked against the full H.17.11a test and the hull facets, as in H.17.15.
- The cross-cluster cost estimate of H.17.16b (about $9 \cdot 10^4$ core-hours) is superseded: by the class bound, the four-class geometries above are all that needs to be searched, at about $2.8 \cdot 10^6$ jobs.

Angles that did not lead to a gluing lemma (recorded briefly).

- (1) *Facet locality [NUMERICAL] (glue_facets.log).* Facets are defined only modulo the 27 affine-hull equalities. For each of the 29,344 facets we computed the smallest set of corners (outputs o) that some equivalent representative of the facet touches:
  - 64 facets touch 1 corner (positivity), 192 touch 3, 2,944 touch 4, 8,608 touch 5, 17,408 touch 6, and 128 touch 7.
  - All 20,320 facets violated (over source states) by the four-term counterexample H.13.2 need ≥ 4 corners, including its certificate facet 16962, which needs 5.
  - So facets do not localise to ≤3 corners, let alone to ≤3 classes, and marginalising onto few corners cannot work.
- (2) *Restricting to faces [INTERPRETIVE].* Fixing one party's output gives a two-party sub-board, but H.13.2 is a non-blend whose sub-boards carry no obstruction of their own. Any reduction must use the three-term hypothesis on the whole cube. Lemma H does exactly that.

- (3) *Klein-group decoupling.* Not needed after Lemma H, because the four-class search covers every Klein-group configuration at once.

Prior literature. Lemma H is a short counting argument about Pauli supports of the kind used throughout H.8–H.17. We know of no earlier statement of it, but it is elementary, and we claim it only as a lemma of this paper.

H.17.7 Status after this round.

- PROVED: the sign-variant lemma H.17.3, with the stated scope; the Pauli coset-transport theorem and the reduction SH_grp ⇒ PF blend (H.17.8a–b); in the generic-support model, every admissible ≤3-term board, non-X boards included, satisfies SH_grp and is therefore a PF blend for every source state (H.17.9, exhaustive exact enumeration).
- PROVED: every admissible three-class board $\{1, V_a, V_b\}$, tuned or generic, is a PF blend (H.17.14).
- PROVED: every admissible two-class ≤3-term board, tuned or generic, is a PF blend (H.17.13, exhaustive exact enumeration over 59,836 supports).
- PROVED: every admissible board with three non-identity classes and a tuned pair is a PF blend: all 61 G_{48} orbits are done, and all 188 candidates and 1,274 budget-exhausted jobs fail triple consistency (H.17.15). So every ≤3-term board with at most three distinct classes is a PF blend.
- PROVED: complete classification of the cancellation patterns of $V'V^\dagger$ for all pairs of ≤3-term classes. There is no cancellation unless the Klein groups meet. When they meet in two elements, at most one collided string vanishes. When $K = K'$, only the supports of H.17.12(b) occur.
- PROVED: right-absorbed coset transport, SH_grp^r ⇒ PF blend (H.17.11a). Each of the 19 regenerated tuned boards passes it, so each is a PF blend (supports read numerically, H.17.11b).
- PROVED: Lemmas A–C of H.17.16; and no ≥4-class counterexample in the Klein-cluster family KC with k = 4, for all 21 K-orbits (H.17.16; over-approximating supports). Round 7 (H.17.16b): k = 5 in KC, 52 of 104 canonical blocks done (416,988 jobs, 0 candidates, 0 UNRESOLVED; rest running; *finished Oct 25: all 104 blocks, 38,135,448 jobs, 0 candidates, 0 UNRESOLVED, H.17.16c*); the counting fact $s \geq 2k - 8$. Cross-cluster k = 4 sample of 20,000 tuples clean [NUMERICAL]. Round 8 (H.17.17): Lemma D (failure witnesses are local) and Lemma H (rigid directions); **every admissible ≤3-term board has at most four classes**, and with four classes each class is one edge along its rigid direction; the four-class case is a finite search of 2,722 canonical geometries, 401 finished with 0 candidates and 0 UNRESOLVED, the rest running. *Update (Round 19, H.26.1, H.26.1a):* all 2,722 canonical geometries finished (2,896,784 jobs), with 0 candidates and 0 UNRESOLVED, and the coverage was audited independently (glue_k4_audit.log). So "four terms per outcome is the minimum" is PROVED in the per-class-pair model. *Update (H.17.16c):* the k = 5 run also finished (104 of 104 blocks, 0 candidates, 0 UNRESOLVED), as a consistency check of the class bound.
- PROVED (exact dual certificate): orbit 92 is the positivity orbit and holds on all of Valid (H.17.5).
- EXACT-CERTIFIED: the other 22 never-crossed orbits are not implied by validity alone (H.17.5).
- NUMERICAL:
  - pure non-X ≤3-term boards exist and all tested ones lie in the PF hull;
  - every hard board found satisfies SH^{++};
  - the 19 tuned boards have explicit LP PF-blend decompositions at 4 source states each (H.17.11b);
  - no Z_{16}, continuous-phase or locally rotated X-type board violates any of the 22 genuine orbits.
  - nsearch4 (up to 8 classes): 5,800 hard admissible ≤3-term boards, none with ≥3 distinct unitaries and none outside conv(PF) (best facet value $6.1 \cdot 10^{-15}$) (H.17.16).
- OPEN:

- "non-X ≤3-term ⇒ PF blend" for tuned (non-generic) parameters. SH_grp fails on tuned boards (H.17.10), but the right-absorbed version SH_grp^r (H.17.11, proved sufficient) holds on all 19 regenerated tuned boards. That it holds on every admissible tuned board is open. It now holds on all 51 tuned boards (H.17.12d), and the cancellation patterns of V′V† are completely classified [proved] (H.17.12a–c); the closure is now **proved for every two-class board** (H.17.13) and every three-class board containing the identity class (H.17.14). Three non-identity classes are reduced by G_{48} to 61 orbits, and all 61 are proved (H.17.15). Remaining: ≥4 classes with a tuned class pair (H.17.16: Lemmas A–C reduce it to ≥4 distinct unitaries with a cancelled tuned pair; the Klein-cluster family is searched; no gluing lemma is known; so whether four terms is the minimum stays open). *Round 8 (H.17.17):* k ≤ 4 is PROVED, so what remains is the four-class search of 2,722 canonical geometries, partly done and running; four terms is the minimum once it finishes clean;
- the 22 genuine never-crossed orbits on general purifiable processes. *(Round 15, H.22.2: twelve are crossed, exactly certified; Round 21, H.28.1: three more (26, 30, 31); 7 remain open.)*

Runs were cut off at the time limit: nsearch2 seeds 13 and 14 ran with `timeout 840`, and their logs are the last checkpoints.

H.18 Embedding in spacetime II: realisations on time-delocalised subsystems (Oct 24 2026) [labels: PROVED = this paper; NUMERICAL = floating-point check; CITED = read in the arXiv primary source on Oct 24 2026 (IDs checked against the arXiv API); INTERPRETIVE = our reading; OPEN]

H.15 asked whether our boards fit into an ordinary spacetime with each agent at one place and time. The Vilasini–Renner no-go (H.15.1, ref. 32) rules this out for H.12 and H.13.2, because neither is causally ordered. This section takes the other route in the literature. The agents' systems are not localised at single times; they are *delocalised* over several time steps of an ordinary, acyclic quantum circuit. Code: code/stochastic/cyclic/embed/tds_h13.py, tds_h13.log.

H.18.1 Definitions.

- *Temporal circuit.* An ordinary quantum circuit: gates act at definite times, wires run forward in time, and there are no cycles. A *time-local system* is one wire of such a circuit between two gates.
- *Time-delocalised subsystem (TDS)* (Oreshkov, ref. 40). Take the joint Hilbert space of several time-local wires, for example $H_{T1} \otimes H_{T2} \otimes H_Q$ at two different times. Fix an isomorphism J (a unitary change of tensor factorisation) onto a new product, for example $H_{A_I} \otimes H_{B_I} \otimes H_{rest}$. The new factor A_I is a subsystem of the joint wires, but it need not live on any single wire or time. For instance, A_I may equal T1 when a control Q is 0 and T2 when Q is 1, coherently.
- *Realisation on TDS* (refs. 40, 41). A process W with agents A, B, C has such a realisation if there is a temporal circuit whose gates may depend on the agents' unitaries U_A, U_B, U_C, together with isomorphisms J_{in} (on the circuit's input wires) and J_{out} (on its output wires), with the following property: for **every** choice of U_A, U_B, U_C, the circuit rewritten in the J-factorisation equals the cyclic composition of W with exactly one copy of each U_X. A separate gate in the time-local picture that depends on U_X is called a *time-local instance* of U_X. WBO stress that several time-local instances do not mean the operation is applied several times. On the TDS it is applied exactly once.

- *Unitary extension* (ref. 17). This is a pure process, with a global past P and future F, that reduces to the given process when P is fed a fixed state and F is discarded. Every pure board of this paper is its own unitary extension, with the purification V: $P \otimes A_O\, B_O\, C_O \to A_I\, B_I\, C_I \otimes F$ of H.8.2.

H.18.2 What the literature proves [CITED].

- *Oreshkov* (arXiv:1801.07594, Quantum 3, 206 (2019); ref. 40) introduces TDS. **Thm 1:** every unitary extension of a bipartite process has a realisation on TDS. **Thm 2:** so does a class of isometric extensions. He conjectures that processes built by a specific "coherent control of time instances" construction (his Eq. (22)) cannot violate causal inequalities, and leaves this open.
- *Wechs, Branciard and Oreshkov* (WBO; arXiv:2201.11832, Nat. Commun. 14, 1471 (2023); ref. 41).
  - **Prop. 1:** every unitary extension of a **tripartite** process has a realisation on TDS. The temporal circuit has the following shape: a gate ω_1 depending on U_C; U_A and U_B on targets T1, T2, coherently controlled by Q, so their order is coherently controlled; middle gates ω_2; and a final ω_3 depending on U_C. The proof fixes U_C and uses the standard form of bipartite unitary processes, a "variation of the quantum switch" (refs. 43, 45).
  - *Example:* the Baumeler–Wolf unitary extension U_{BW} of the Araújo–Feix process W_{AF}, whose function is (¬b∧c, ¬c∧a, ¬a∧b). It violates causal inequalities. WBO give its circuit in full (their Fig. 5 and Suppl. Note 4A, Eqs. (51)–(57)). It is a classical, deterministic circuit. A time-local instance of U_C is applied first, and its output decides the order of A and B. Afterwards U_C may be "reversed and reapplied" with a NOT gate in between, and Alice's and Bob's outputs decide coherently whether this happens.
  - They argue that the causal-inequality assumptions are still meaningful on TDS, and they show that some TDS variables have no time-local counterpart, i.e. no effective localisation in time.
  - **Open in WBO:** more than three parties, and whether every process with indefinite causal order has such a realisation.
- *Barrett, Lorenz and Oreshkov* (arXiv:2002.12157, Nat. Commun. 12, 885 (2021); ref. 45) and *Yokojima, Quintino, Soeda and Murao* (arXiv:2003.05682, Quantum 5, 441 (2021); ref. 43). Every bipartite unitary process is causally separable. More precisely, a pure two-slot superchannel is either a fixed-order unitary circuit or a coherent superposition of the two orders. In particular, purifiable bipartite processes cannot violate device-independent causal inequalities.
- *Wechs and Oreshkov* (arXiv:2411.16504, Phys. Rev. Lett. (2025), DOI 10.1103/9mk4-8sn5; ref. 44) give a "circuit (super)operator" that tracks how a possibly cyclic circuit changes under a change of subsystem decomposition. They show that the two parties' causal perspectives on the quantum switch are **not** related by such a change.
- *Portmann, Matt, Maurer, Renner and Tackmann* (arXiv:1512.02240, IEEE Trans. Inf. Theory 63, 3277 (2017); ref. 42) define *causal boxes*: systems closed under composition that allow superpositions of message orders and time-dependent behaviour. Salzger and Vilasini map QC-QCs into causal boxes (H.15.1). Our boards are not QC-QCs (H.15.7b), so that map does not apply to them.
- *Ormrod, Vanrietvelde and Barrett* (arXiv:2204.10273, Quantum 7, 1028 (2023); ref. 46) model causal structure under sectorial constraints and define a sector-level fine-graining of causal structure. Applied to photonic quantum-switch experiments, the fine-grained structure is acyclic. VOKB's routed graphs (ref. 18) build on this.
- Vilasini–Renner (no-go for localised embeddings, Thm 4; fine-grained acyclic explanation, Thm 5), Vilasini–Colbeck (cyclic and fine-tuned causal models in Minkowski space) and Paunković–Vojinović

("every circuit can be immersed into a classical spacetime") are summarised in H.15.1, and are used below as stated there.

H.18.3 Both boards have realisations on TDS [hypotheses PROVED; theorem CITED]. H.8.2 shows that the purification V of each pure board is a unitary $P \otimes A_O\, B_O\, C_O \to A_I\, B_I\, C_I \otimes F$, with every party a qubit. So each board is a unitary extension of a tripartite process, and WBO Prop. 1 applies to both. **H.12 and H.13.2 each run as an ordinary acyclic quantum circuit, with the agents acting once each on time-delocalised subsystems.** This includes the instruments that violate causal inequalities: H.15.7b for H.13.2 and H.15.7d for H.12. Those instruments dilate to unitaries with ancillas, and Prop. 1 covers all unitaries.

H.18.4 An explicit circuit for H.13.2 [PROVED, with NUMERICAL confirmation].

- **(a) Our Lugano purification is WBO's U_{BW} [PROVED, exact].** lug(a,b,c) = ((1−b)c, (1−c)a, (1−a)b) = (¬b∧c, ¬c∧a, ¬a∧b). So L: $|s\rangle_P|o\rangle_{A_O} \mapsto |s \oplus \mathrm{lug}(o)\rangle_{A_I}|o\rangle_F$ is exactly WBO's Eq. (5).
- **(b) WBO's circuit, re-implemented [NUMERICAL].** We built the gates ω_1, the controlled U_A/U_B slots, ω_2 (both branches), the second slot and ω_3 of Eqs. (51)–(54) on a 6-qubit register ($p_1p_2p_3$ and one ancilla qubit per agent). The circuit equals the cyclic composition of L with U_A, U_B, U_C for 20 Haar-random 2-qubit agent unitaries. The maximum deviation is $3.9\cdot10^{-16}$, and the composite is unitary to $1.7\cdot10^{-15}$.
- **(c) Time reversal [PROVED].** Write Cyc(W; U_A, U_B, U_C) for the cyclic composition. Then Cyc(L^T; W_A, W_B, W_C) = Cyc(L; $W_A{}^T$, $W_B{}^T$, $W_C{}^T$)^T. Here $W_X{}^T$ swaps the agent's input and output wires and the roles of its ancillas, and the outer transpose swaps P with F. *Proof:* the cyclic composition is a contraction of indices, and transposing every factor transposes the contraction. So if a temporal circuit $g_k \cdots g_1$ (with isomorphisms J_{in}, J_{out}) realises L with agents W^T, then $g_1{}^T \cdots g_k{}^T$ (with $J_{out}{}^T$, $J_{in}{}^T$) realises L^T with agents W.
  - This reversed circuit is again an ordinary temporal circuit. The transpose of a controlled-W^T is a controlled-W. The time-local instances of C become W_C (in the transposed ω_1) and $W_C\dagger\ \sigma_x\ W_C$ (in the transposed ω_3), and the permutation gates become their inverses. The isomorphisms are real permutation-type unitaries, so their transposes are isomorphisms too.
  - *Check [NUMERICAL]:* for 20 Haar draws, the maximum deviation from Cyc(L^T; W) is $4.5\cdot10^{-16}$.
- **(d) H.13.2 [PROVED, with NUMERICAL confirmation].** By H.15.7e, $V_{13.2}$ = (Hd X^{f_o})_{A_I} (Hd X^{f_i})_F · L^T · (Hd)_{A_O} (X^{f_o} Hd)_P (rechecked exactly in tds_h13.py).
  - Absorb the agent-wire factors into the agents: agent X runs W˜_X = Hd·W_X·(Hd $X^{f_o,X}$) inside L^T. The P and F factors become a fixed preparation and readout. The reversed WBO circuit then realises H.13.2 on TDS.
  - *Checks [NUMERICAL]:* 20 Haar draws give a maximum deviation of $6.8\cdot10^{-16}$. With the classical instruments of H.15.7b (measure the input, emit the setting), whose dilation is a SWAP of the system with a qubit ancilla, the deviation is $1.1\cdot10^{-15}$, and the circuit's P(i|o) equals the board's to $2.2\cdot10^{-15}$.
  - So the exact causal-inequality violation of H.15.7b is produced by an ordinary acyclic circuit, in the TDS variables.
- **(e) Reading the circuit [INTERPRETIVE].**
  - In forward time, the circuit first applies a C-instance $W_C\dagger\ \sigma_x\ W_C$, coherently conditioned on the past bits. Then A and B act once each, in an order coherently controlled by Q. Last comes a C-instance W_C fed by Q.

    - Classically, H.13.2 is the time-reversed WBO process seen in the Hadamard frame. All of its non-classicality sits in the local frame changes Hd, since the bare circuit is a reversible classical (permutation) circuit.
- **(f) What is new [CITED vs ours].**
    - The existence of a realisation is WBO's theorem, and the forward circuit is WBO's.
    - Ours are: the identification of H.13.2 with a frame-rotated time reverse of U_{BW} (H.15.7e); the time-reversal step (c), which is immediate from the definitions but which we did not find stated in WBO (full text searched for "time-revers" and "transpose"); and the exact assembly and numerical check.
    - Guérin and Brukner (ref. 38) studied the time-reversed Lugano process itself; WBO cite them for the decomposition of U behind their isomorphisms. We do not claim that the reversed circuit is new as an object, only that we found no explicit statement of it.

H.18.5 Placing the circuit in spacetime [PROVED as a composition of cited results; physical reading INTERPRETIVE].

- Paunković–Vojinović (ref. 35): every circuit can be immersed in a classical spacetime with compatible causal orders. Put the five gate layers of H.18.4 at successive, timelike-separated points of one laboratory in Minkowski space. This gives an explicit spacetime embedding of H.13.2 in which every time-local gate is localised and the agents' inputs and outputs are TDS.
- There is no conflict with Vilasini–Renner Thm 4. That theorem concerns embeddings in which each agent's input and output are localised in a region, and here they are not. The circuit is an instance of their Thm 5 alternative: a fine-grained acyclic explanation whose nodes are the time-local gates.
- *Fine-grained, not fine-tuned [INTERPRETIVE].* The identity of H.18.4 holds for all agent unitaries, with gates that do not depend on any special parameter values. So the realisation is of the fine-graining kind, not a fine-tuned cyclic model in the Vilasini–Colbeck sense. We have not checked VC's formal fine-tuning definition against it.
- *Relation to H.15.7a/b [PROVED consistency].* Lemma H.15.7a assumes that each agent's operation is used once at the time-local level. In the H.18.4 circuit, C has two time-local instances (one of them $W_C^\dagger$ σ_x W_C), and A and B act in a coherently controlled order. So the circuit is not a model of the H.15.7a kind, and H.15.7b, which excludes such models, is not contradicted. This answers the quantum half of the OPEN question in H.15.7b, "is there a fine-grained model with multiple use for H.13.2?": yes. Whether a model with **classical** carriers exists stays **OPEN**, because the Hd frame changes make this circuit quantum. *Update (Round 14):* H.21.6 splits this question and answers its two extreme forms.

H.18.6 H.12 [existence CITED; explicit circuit OPEN; routed graph OPEN]. ***Superseded by H.21: both are now given.***

- WBO Prop. 1 gives existence (H.18.3).
- The explicit construction does not carry over: H.12 is not a phased permutation in the Hadamard frame (H.15.8), so no frame change of the H.18.4 kind reduces it to a classical reversible circuit.
- An explicit circuit would need WBO's general proof run concretely: fix U_C, bring the induced bipartite unitary process into switch-variation form (refs. 43, 45), and assemble ω_1–ω_3. This was not done this round [OPEN].
- A valid routed graph for H.12 also remains **OPEN** (H.15.7c).
- *Update (Round 14, H.21).* Both items are settled. The second bullet was wrong in its conclusion: H.12 is not a phased permutation, but it is the frame-rotated time reverse of the √X-Lugano process (Theorem

H.21.2). WBO's general proof run concretely gives one circuit (H.21.1), and the H.18.4 circuit with one CNOT replaced by a controlled-√X gives a structured one (H.21.3). A valid routed graph is in H.21.4.

H.18.7 Status.

- PROVED: H.18.3 (both boards satisfy WBO's hypotheses); H.18.4(a), (c), (d) (the explicit reversed-WBO circuit for H.13.2); the H.18.5 consistency with H.15.7a/b.
- NUMERICAL: the floating-point confirmations in H.18.4.
- CITED: H.18.2 and WBO Prop. 1.
- INTERPRETIVE: H.18.4(e) and the fine-graining reading in H.18.5.
- OPEN: an explicit TDS circuit and a routed graph for H.12 (*settled in H.21*); a classical-carrier fine-grained model for H.13.2 (*split in H.21.6: trivially yes with unrestricted multiple use, no with reversible single use, intermediate notions OPEN*); realisations for more than three parties (open in WBO too).

H.19 Round 12: the counterexample in the process-matrix (Choi) framework, and infinite ancillas (Oct 24 2026) [labels: PROVED (Lean) / PROVED (paper) / CITED / OPEN per item]

Lean files: lean/PFUL/ProcessMatrix.lean, CounterexampleChoi.lean, CounterexampleHilbert.lean (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/STATUS.md Round 12). There is no `sorry`, no `native_decide` and no new axiom. `#print axioms` gives only propext, Classical.choice and Quot.sound for every theorem named below (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/Round12_axioms.log).

H.19.0 Reconciliation (state before this round).

- *Covered:* finite ancillas (`isPure_Vsb`); ancilla index sets of any cardinality with unitary kernels, and bounded unitaries on $\ell^2(\kappa)$ for any κ (Round 11, `isUnitaryKer_Vsb`, `isUnitaryAll_Vsb`); the process-function link (`isPF_iff`, `valid_pfPoint_iff`); and purity as a property of $|V\rangle\rangle$ (`compose_eq_link`).
- *Stale:* the abstract, §0, Section 9 and H.12.3 still said "finite ancillas, not linked", and H.12.3 still said "isometry, not unitary" (closed in Round 10). This round corrects them.
- *Not covered:* (1) a general process-matrix definition of validity and purity, with `Valid`, `IsPure` and `PFset` proved to agree with it; (2) ancillas that are abstract Hilbert spaces rather than $\ell^2(\kappa)$ with its standard basis; (3) validity of the Switchboard under non-unitary local channels with infinite ancillas; (4) whether finite-ancilla purity implies infinite-ancilla purity.

H.19.1 The framework [definitions; PROVED (Lean) lemmas]. Parties k have finite input and output types I_k, O_k. The source is P and the sink is F. A process matrix W is a matrix on $P \times F \times \prod_k (I_k \times O_k)$.

Local operations. A local operation with input ancilla X_k and output ancilla Y_k is given by its Choi matrix C_k on $(I_k \times X_k) \times (O_k \times Y_k)$. It is CPTP (`IsCPTPChoi`) iff $C_k \geq 0$ and $\Sigma_b\, C_k((a,b),(a',b)) = \delta_\{aa'\}$. By `isCPTPChoi_choiOf_iff`, this is equivalent to complete positivity (`PFUL.Choi.IsCP`) plus trace preservation of the map whose Choi matrix is C_k.

Link product. It is written in indices:

```
(W ∗ C)((π,ξ),(φ,η); (π',ξ'),(φ',η')) = Σ_{a,a'} W(π,φ,a; π',φ',a') ∏_k
C_k((a_k.1, ξ_k),(a_k.2, η_k); (a'_k.1, ξ'_k),(a'_k.2, η'_k)).
```

This is the link product of Chiribella, D'Ariano and Perinotti [49]. The partial transpose is absorbed into the index convention, as for Choi vectors.

Definitions:

- `IsValidPM W`: $W \geq 0$, and for all finite ancillas X, Y and all CPTP C_k, $W * C$ is the Choi matrix of a CPTP map from $P \times \prod X_k$ to $F \times \prod Y_k$. With trivial source, sink and ancillas this is the AFNB normalisation $\mathrm{Tr}[W(\bigotimes_k C_k)] = 1$ [17].
- `UnitaryLink W`: for all finite ancillas X and all unitaries $A_k : I_k \times X_k \to O_k \times X_k$, $W * (|A_k\rangle\rangle\langle\langle A_k|)_k = |M\rangle\rangle\langle\langle M|$ for some unitary M.
- `IsPurePM W := IsValidPM W ∧ UnitaryLink W`. This is AFNB's pure process [17, Def. 1] with finite ancillas.

General lemmas:

- `link_posSemidef`: a link of PSD matrices is PSD.
- `link_rankOne`: a link of rank-one matrices is rank one, with the linked vector.
- `isUnitaryM_of_vecOp_eq`: if $|A\rangle\rangle\langle\langle A| = |M\rangle\rangle\langle\langle M|$ and M is unitary, then A is unitary.

Scope. These are finite-dimensional definitions: every type in them is finite.

H.19.2 Bridges from the counterexample's definitions [PROVED (Lean)]. Write $\mathrm{Wcl}\ p = \Sigma_{i,o}\ p(i|o)\ |i,o\rangle\langle i,o|$ for the diagonal process matrix of a classical process, with trivial source and sink.

- `isValidPM_Wcl_iff p : IsValidPM (Wcl p) ↔ Valid p`. So classical validity under products of stochastic maps is the same as AFNB validity under all CPTP local operations with finite ancillas. For the direction ⇐, each output distribution $\Sigma_y C_k(\ldots)$ is treated as a complex weight with fixed row sums. `valid_sum_complex` extends `Valid` multilinearly to such weights, by writing each local map in terms of the three deterministic maps (identity, NOT, constant).
- `isValidPM_Wcl_pfPoint_iff w : IsValidPM (Wcl (pfPoint w)) ↔ PFUL.Countable.IsProcessFunction (wBits w)`. The valid deterministic process matrices are exactly the process functions of the general definition.
- `isPure_iff_unitaryLink V : IsPure V ↔ UnitaryLink (choiMat V)`, for every V. The proof is `link_choiMat_vecOp`: $|V\rangle\rangle\langle\langle V| * (|A_k\rangle\rangle\langle\langle A_k|) = |\mathrm{compose}\ V\ A\rangle\rangle\langle\langle \mathrm{compose}\ V\ A|$.
- `trace_link_Vsb` and `isValidPM_choiMat_Vsb`: $W_{sb} = |\mathrm{Vsb}\rangle\rangle\langle\langle \mathrm{Vsb}|$ is valid under all CPTP local operations with any finite ancillas. The trace condition uses only trace preservation of the C_k. Its proof is the scalar-key identity of `isPure_Vsb` with the weights $b_k(x,y,z) = \Sigma_{y'} C_k((z,\xi_k),(x,y'); (y,\xi'_k),(x,y'))$.
- `isPurePM_choiMat_Vsb : IsPurePM (choiMat Vsb)`.
- `inducedP_eq_born`: $p(i|o) = \Sigma_{\varphi,\pi,\pi'} W(\pi,\varphi,(i,o); \pi',\varphi,(i,o))\ \psi_\pi\ \mathrm{conj}(\psi_{\pi'})$, the Born rule.

- `purification_conjecture_false_choi`:

```
∃ p, IsValidPM (Wcl p) ∧ (∃ P F W ψ, IsPurePM W ∧ Σ|ψ|² = 1 ∧ ∀ i o,
p(i|o) = Σ_{φ,π,π'} W(π,φ,(i,o); π',φ,(i,o)) ψ_π conj(ψ_π')) ∧ Wcl p ∉
convexHull ℝ {W | ∃ w, W = Wcl (pfPoint w) ∧ IsValidPM W}.
```

  Every predicate in it is a framework predicate. The hull statement is transported along the injective $\mathbb{R}$-linear map p ↦ Wcl p (`Wcl_mem_convexHull_iff`).

H.19.3 What "pure" means with infinite-dimensional ancillas [definition; PROVED (Lean)]. *Definition.* V is pure against infinite ancillas if, for every family of complex Hilbert spaces K_k of any dimension and every family of unitaries A_k on $C^2 \otimes K_k$, the closed loop is a unitary of $C^P \otimes \bigotimes_k K_k$.

Mathlib has no Hilbert tensor product, so the Lean definition (`IsPureHilbert`) is stated through Hilbert bases:

- $C^2 \otimes K_k$ is any Hilbert space H_k with a Hilbert basis indexed by Bool × κ_k, where κ_k indexes a Hilbert basis of K_k. Every Hilbert space has one (Mathlib `exists_hilbertBasis`).
- The joint space is any Hilbert space G with a Hilbert basis indexed by P × ∏_k κ_k.
- The loop must be a unitary U of G whose matrix in that basis is the link product of V with the matrices $\langle b_r, A_k\, b_c \rangle$.

A Hilbert space is determined up to unitary equivalence by the cardinality of a Hilbert basis, so this is the tensor-product statement up to that identification [INTERPRETIVE: the identification only; Round 13 upgrades the local factor $H_k = C^2 \otimes K_k$ to PROVED (Lean), H.20.5]. The loop's matrix entries are finite sums over the Switchboard's indices of products of ancilla matrix entries, so they need no convergence argument. Only unitarity is an infinite-dimensional statement.

- `isIsoKernel_kerOf` and `isCoIsoKernel_kerOf`: in any Hilbert basis, the matrix of a unitary has orthonormal columns and rows.
- `isPureHilbert_iff_isUnitaryKer V`: for every V, purity with Hilbert-space ancillas is equivalent to the kernel form of Round 11. One direction transports along Hilbert bases. The other takes $H_k = \ell^2(\text{Bool} \times \kappa_k)$ and uses `unitary_of_unitaryKernel`.
- `isPureHilbert_Vsb`: the Switchboard is pure with ancillas in arbitrary Hilbert spaces, separable or not.

H.19.4 Finite-ancilla purity implies infinite-ancilla purity [PROVED (paper); PROVED (Lean) in Round 13, H.20.1]. *Proposition.* Let V be any process on finite P with binary parties, the setting of `IsPure`. (For general finite $I_k = O_k$ the argument is the same.) If V is pure against all finite ancillas, then for all ancilla index sets κ_k and all unitary kernels a_k, `compose V a` has orthonormal columns and rows. Hence `IsUnitaryKer V` holds, and so does `IsPureHilbert V` by H.19.3.

Proof.

1. *The column Gram entry.* Fix columns c = (π, α) and c' = (π', α'). Their inner product is

```
Σ_φ Σ_{o,e,o',e'} conj V(e,φ; o,π) V(e',φ; o',π') ∏_k g_k(o_k, e_k; o'_k, e'_k),
```

where $g_k(x, y; x', y') = \Sigma_{b \in \kappa_k}$ conj $a_k((x,b),(y,\alpha_k))$ $a_k((x',b),(y',\alpha'_k)) = \langle(\langle x| \otimes 1)\, A_k|y,\alpha_k\rangle, (\langle x'| \otimes 1)\, A_k|y',\alpha'_k\rangle\rangle_{K_k}$. These series converge absolutely and do not depend on the basis.

2. *A finite-dimensional subspace.* The Gram entry depends only on the finitely many vectors $A_k|y,\alpha_k\rangle$ and $A_k|y,\alpha'_k\rangle$, $y \in$ Bool. Let $L_k \subset K_k$ be the finite-dimensional span of e_{α_k}, $e_{\alpha'_k}$ and the components $(\langle x| \otimes 1)A_k|y,\alpha_k\rangle$ and $(\langle x| \otimes 1)A_k|y,\alpha'_k\rangle$.

3. *Extension to a unitary.* A_k maps $C^2 \otimes \mathrm{span}(e_{\alpha_k}, e_{\alpha'_k})$ isometrically into $C^2 \otimes L_k$. An isometry between subspaces of a finite-dimensional space extends to a unitary B_k of $C^2 \otimes L_k$, since the orthogonal complements have equal dimension.

4. *Applying finite purity.* B_k is a local unitary with a finite ancilla. Use an orthonormal basis of L_k containing e_{α_k} and $e_{\alpha'_k}$; these coincide or are orthogonal. The corresponding column Gram entry of compose V B is built from the same g_k, so it equals the entry for A. Since V is pure against finite ancillas, it is $\delta_{cc'}$.

5. *Rows.* A row Gram entry involves only finitely many rows of the a_k, i.e. the vectors $A_k\dagger|x,\beta_k\rangle$ and $A_k\dagger|x,\beta'_k\rangle$. The same construction applies with $A_k\dagger$ in place of A_k.

6. *Conclusion.* `unitary_of_unitaryKernel` turns the unitary kernel into a bounded unitary. ∎

The converse (infinite-ancilla purity implies finite-ancilla purity) is `IsPureKer.isPure` in Lean. So for every finite V, purity against finite ancillas, purity against unitary kernels and purity against arbitrary Hilbert ancillas are equivalent; the first implication was on paper only in Round 12; Round 13 formalises it (`isPureHilbert_of_isPure`, H.20.1). The Switchboard does not need the proposition, because `isPureHilbert_Vsb` is proved directly.

H.19.5 The Choi form with infinite ancillas [PROVED (Lean) for the Kraus/kernel form; OPEN as an operator link product]. W stays a finite matrix; only the local Choi operators become infinite. For a channel on $C^2 \otimes \ell^2(X_k)$, the Choi operator is not trace class, since its partial trace is the identity. So W ∗ J cannot be defined as a trace of a product of trace-class operators. This is the obstruction of Appendix A/F, and Lean uses the kernel form instead.

- On countable ℓ^2, every normal CPTP map is a Kraus channel (`isNormalCPTP_iff_kraus`).
- Every Choi kernel whose finite sections are PSD and which satisfies the trace-preservation condition is the Choi kernel of a Kraus kernel (`exists_kraus_of_choi`).
- `isIsoKernel_compose2_Vsb`: the closed loop of Vsb with isometric local kernels Bool × X_k → Bool × Y_k has orthonormal columns. The input and output ancillas may differ and may have any cardinality.
- `valid_normalCPTP_Vsb`: take normal CPTP local channels $\Phi_k : B(\ell^2(\mathrm{Bool} \times X_k)) \to B(\ell^2(\mathrm{Bool} \times X'_k))$ with countable X_k and X'_k. Each Φ_k is a Kraus channel with kernel V_k. The closed loop `krausLoop V` is the link product of Vsb with the Kraus kernels; its entries are finite sums over the Switchboard indices. By `isIsoKernel_krausLoop` it is an isometric Kraus kernel, so the induced

global map is normal CPTP. In finite dimensions this is `isValidPM_choiMat_Vsb` restricted to those channels.

- *Not formalised:* (i) the closed loop's Choi kernel as a convergent series W ∗ J for non-trace-class J (this was done for process-function lifts in BornPairing.lean, but not for the Switchboard); (ii) channels on uncountable ancillas, since the repository's Kraus theorem needs countable alphabets. Round 13: (ii) is closed (`valid_normalCPTP_Vsb_any`), and (i) is replaced by an entrywise link product over ancillas of any cardinality (H.20.4).

H.19.6 Status.

- PROVED (Lean): H.19.1 lemmas, H.19.2, H.19.3, and the H.19.5 kernel statements.
- PROVED (paper): H.19.4.
- CITED: AFNB Def. 1 and Thm 2 [17]; the CDP link product [49].
- INTERPRETIVE: identifying "Hilbert space with a Hilbert basis indexed by Bool × κ" with $C^2 \otimes K$.
- OPEN (formal): items (a)–(d) of Section 9. *Round 13 update:* all four are closed in Lean with the caveats of H.20.7; H.19.4 is PROVED (Lean), and the INTERPRETIVE item is upgraded for H_k (H.20.5).

H.20 Round 13: closing the Round 12 formal gaps (Oct 24 2026) [labels: PROVED (Lean) / CITED / INTERPRETIVE / OPEN per item]

Lean files: lean/PFUL/Compression.lean, PureFiniteInf.lean, AFNBPure.lean, KrausAny.lean, InfiniteLink.lean, QubitTensor.lean, CounterexampleInfLink.lean (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/STATUS.md Round 13). There is no `sorry`, no `native_decide` and no new axiom. `#print axioms` gives only propext, Classical.choice and Quot.sound for every theorem named below (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/Round13_axioms.lean, lean/Round13_axioms.log). Gaps are labelled as in Section 9 (Round 12 version): (a) infinite-ancilla link product, (b) H.19.4 in Lean, (c) AFNB Thm 2, (d) normal CPTP with uncountable ancillas.

H.20.1 Gap (b): finite purity implies purity against Hilbert ancillas, for every V [PROVED (Lean)]. This is the proof of H.19.4, formalised.

- `exists_finite_compression σ a ha α α'`. Let a be a kernel on (O × κ) ← (I × κ) with orthonormal columns, with I ≃ O finite and κ of any cardinality, and let α, α' ∈ κ. Then there are a finite type n, a unitary matrix B on (O × n) ← (I × n) and i, j ∈ n with i = j ↔ α = α', such that Σ_b conj a(x,b)(y,α) a(x',b)(y',α') = Σ_b conj B(x,b)(y,i) B(x',b)(y',j) for all x, y, x', y'. Construction: take coordinates of the finitely many vectors a(x,·)(y,α), a(x,·)(y,α') in an orthonormal basis of their span in $\ell^2(\kappa)$, pad by two ancilla levels for i and j, and extend the resulting orthonormal family to an orthonormal basis (steps 2–3 of H.19.4).
- `isPureKer_of_isPure`, `isUnitaryKer_of_isPure`, `isPureHilbert_of_isPure : IsPure V → IsPureHilbert V`. The column Gram entry of `compose V a` depends on each a_k only through these cross Gram numbers, so it equals the corresponding entry of `compose V B`, which is δ_{cc'} by finite purity. Rows follow by applying the same argument to V† and a† (`compose_conjTranspose`).
- `isPure_iff_isPureKer`, `isPure_iff_isUnitaryKer`, `isPure_iff_isPureHilbert`: for every V : Proc P P, purity against finite ancillas, against isometric kernels, against unitary kernels and against arbitrary Hilbert ancillas are equivalent.

H.20.2 Gap (c): AFNB Theorem 2 in the process-matrix framework [PROVED (Lean) for $I_k \simeq O_k$; CITED for the general statement [17, Thm 2]].

- `exists_unitary_of_unitaryLink σ : UnitaryLink W → ∃ U, IsUnitaryM U ∧ W = choiPM U`, where choiPM U = |U⟩⟨⟨U| for U : P × ∏O_k → F × ∏I_k. The proof is AFNB's: close each slot k with the unitary that swaps the wire with a copy of it in the ancilla ($X_k = I_k$). The link is then |U⟩⟨⟨U| up to the relabelling σ.
- `unitaryLink_choiPM (hPF : |P| = |F|) U : IsValidPM (choiPM U) → UnitaryLink (choiPM U)`. A link of rank-one matrices is rank one (`link_rankOne`), so W ∗ |A⟩⟩⟨⟨A| = |M⟩⟩⟨⟨M|. Trace preservation of the link (validity) gives M†M = 1, and M is square because |P| = |F|, so MM† = 1.
- `isPurePM_iff σ hPF W : IsPurePM W ↔ IsValidPM W ∧ ∃ U, IsUnitaryM U ∧ W = choiPM U`. The parties are indexed by any finite type, so this is the multipartite form; AFNB state the theorem bipartite and note that the multipartite generalisation is straightforward (Appendix H audit, ref. 17).
- *Hypotheses.* `UnitaryLink` uses one ancilla X_k on both sides of party k, so the SWAP construction needs σ k : $I_k \simeq O_k$. AFNB allow different input and output ancillas, which removes this restriction there. Validity is a hypothesis on the right-hand side, as in AFNB.

H.20.3 Gap (d): Kraus theorem and normal-CPTP validity without countability [PROVED (Lean)]. The countability hypotheses of the Round 12 Kraus theorem entered only through a Gram–Schmidt construction of a Hilbert basis along an enumeration. Round 13 replaces this step with Mathlib's `exists_hilbertBasis` (Zorn's lemma).

- `KernelPSD.exists_factor_any` and `exists_kraus_of_choi_any`: a Choi kernel on alphabets of any cardinality, with PSD finite sections and the trace-preservation condition, is the Choi kernel of an isometric Kraus kernel.
- `exists_kraus_of_normalCPTP_any`, `isNormalCPTP_iff_kraus_any`: on ℓ^2(A) and ℓ^2(O) for arbitrary A, O, a map is normal CPTP iff it is a Kraus channel.
- `valid_normalCPTP_Vsb_any`: `valid_normalCPTP_Vsb` with no `Countable` hypothesis on X_k, X'_k.

H.20.4 Gap (a): a link product with ancillas of any cardinality [PROVED (Lean); entrywise, not an operator identity]. The entries of W ∗ C are finite sums over the wires of W (H.19.1), so the link product is defined for local Choi kernels C_k on ancilla types X_k, Y_k of any cardinality. Only positivity and trace preservation need care.

- `IsCPTPKer J`: J is PSD in Mathlib's sense (every finite section is PSD), and Σ_b J((a,b),(a',b)) = δ_{aa'} as an unconditional sum. `isCPTPKer_iff` shows that it agrees with `IsCPTPChoi` when the output ancilla is finite.
- `posSemidef_of_sections` and `link_posSemidef_any`: a link of PSD kernels is PSD, for any ancillas, by restricting to the finitely many ancilla values in a finite section.
- `psd_norm_le`: |J(p,q)| ≤ (J(p,p) + J(q,q))/2 for PSD J. Together with `hasSum_pi_prod_any`, this makes the partial-trace sums of the link absolutely convergent. `reduceKer` and `isCPTPChoi_reduceKer` restrict the input ancilla to the relevant values and trace out the output

ancilla, which gives a finite CPTP Choi matrix with the same link entries. This reduces validity to the finite case.

- `IsValidPMInf W`: $W \geq 0$ and $W * C$ is a CPTP kernel for all ancilla types X, Y and all CPTP kernels C_k. **`isValidPMInf_iff W : IsValidPMInf W ↔ IsValidPM W`**, for every finite W, with no further hypothesis.
- `UnitaryLinkInf W`: for all ancilla types X_k and all unitary kernels A_k (orthonormal rows and columns), $W * (|A_k\rangle\rangle\langle\langle A_k|)_k = |M\rangle\rangle\langle\langle M|$ with M a unitary kernel. `IsPurePMInf W := IsValidPMInf W ∧ UnitaryLinkInf W`. **`isPurePMInf_iff σ W : IsPurePMInf W ↔ IsPurePM W`**. For ⇐, AFNB Thm 2 (H.20.2) writes $W = |U\rangle\rangle\langle\langle U|$. Then $W * |A\rangle\rangle\langle\langle A| = |\mathrm{lmat}\ U\ A\rangle\rangle\langle\langle \mathrm{lmat}\ U\ A|$ (`link_choiPM_vecOp`), and lmat U A is a unitary kernel by the compression of H.20.1 (`isIsoKernel_lmat`, `isUnitaryKer_lmat`).
- `isValidPMInf_Wcl_iff`, `isPurePMInf_choiMat_Vsb`, and **`purification_conjecture_false_choiInf`**: Theorem H.12.1 with the predicates `IsValidPMInf` and `IsPurePMInf` in place of `IsValidPM` and `IsPurePM`.
- *What this is not.* For a channel with an infinite-dimensional ancilla the Choi operator is not trace class (H.19.5), and Lean does not define $W * J$ as an operator. The statement is about kernels: matrices indexed by arbitrary types, with PSD finite sections and unconditional sums. Unitary kernels are bounded unitaries by `unitary_of_unitaryKernel`. CPTP kernels correspond, via H.20.3, to Kraus channels, i.e. normal CPTP maps on ℓ^2. These are the two operator links, but the identity "$W * J$ as an operator" is not stated [OPEN as an operator statement].

H.20.5 $C^2 \otimes K_k$ as a tensor product [PROVED (Lean) for the local factor; INTERPRETIVE for the joint space].

- `qsplitEquiv`: Mathlib's algebraic tensor product $C^2 \otimes[\mathbb{C}] K$ with its tensor inner product is isometrically isomorphic to $K \oplus K$ (`PiLp 2`). Hence it is complete (`completeSpace_qubitTensor`), even when K is infinite-dimensional.
- `qubitBasis B`: a Hilbert basis of K indexed by κ gives a Hilbert basis $e_b \otimes B_j$ of $C^2 \otimes[\mathbb{C}] K$ indexed by Bool × κ (`qubitBasis_apply`).
- `isPure_qubitTensor`: for every pure V, Hilbert spaces K_k of any dimension, unitaries A_k of $C^2 \otimes[\mathbb{C}] K_k$, and any Hilbert space G with a Hilbert basis indexed by P × ∏κ_k, the link product is the matrix of a unitary of G.
- So the identification "$H_k = C^2 \otimes K_k$" of H.19.3 is now a theorem rather than an interpretation. The joint space $G = C^P \otimes K_1 \otimes K_2 \otimes K_3$ is still modelled as "any Hilbert space with a basis indexed by P × ∏κ_k" [INTERPRETIVE]. The precise obstruction is that Mathlib has no completed Hilbert tensor product, and the algebraic $K_1 \otimes K_2 \otimes K_3$ is not complete when two of the factors are infinite-dimensional. So the basis description cannot be replaced by Mathlib's tensor product there, as it can for $C^2 \otimes K_k$.

H.20.6 The Round 9 boundedness gap [OPEN, not attempted beyond scoping]. Round 11 proved automatic boundedness for unitary kernels (`unitary_of_unitaryKernel`). The remaining Round 8/9 gap is different. `IsNormalCPTP` assumes trace-norm boundedness, and a positive trace-preserving linear map on the trace class should be bounded automatically. On paper: $\|\Phi(T)\|_1 = \mathrm{Tr}\,\Phi(T_+) + \mathrm{Tr}\,\Phi(T_-) \leq \|T\|_1$ for self-adjoint $T = T_+ - T_-$, hence $\|\Phi\| \leq 2$. The Lean obstruction is the Jordan decomposition of a self-adjoint trace-class operator with $\|T\|_1 = \mathrm{Tr}\,T_+ + \mathrm{Tr}\,T_-$. This needs the spectral theorem for compact self-adjoint operators on an infinite-dimensional Hilbert

space, which Mathlib does not have. *Correction (Round 15, H.22.4): Mathlib does have it (`orthogonalComplement_iSup_eigenspaces_eq_bot`), and Schmidt.lean already uses it; the gap is unformalised but not obstructed.* The repository's trace class is the span of products of Hilbert–Schmidt operators, and does not provide this decomposition. *Closed (Round 16, H.23.2): the Jordan decomposition comes from Mathlib's continuous functional calculus (S^± = ½(|S| ± S)), and `IsCPTP.isNormalCPTP` is proved; the status label above is superseded.*

H.20.7 Status.

- PROVED (Lean): H.20.1 (gap b), H.20.2 under σ and |P| = |F| (gap c), H.20.3 (gap d), H.20.4 in kernel form (gap a), and H.20.5 for the local factor.
- CITED: AFNB Thm 2 [17] in its general form (unequal local dimensions).
- INTERPRETIVE: the joint space G as $C^P \otimes \bigotimes K_k$.
- OPEN: an operator-level link product for non-trace-class Choi operators; AFNB Thm 2 without σ, and its converse without |P| = |F|; automatic boundedness of positive TP maps (H.20.6; closed in Round 16, H.23.2).

H.21 Round 14: an explicit spacetime circuit and a routed graph for H.12, and further open items (Oct 24 2026) [labels: PROVED = this paper (exact arithmetic where stated); NUMERICAL = floating-point check; CITED = read in the arXiv primary source (IDs checked against the arXiv API); INTERPRETIVE; OPEN]

H.18.6 left two things open for H.12: an explicit circuit on time-delocalised subsystems (TDS), and a valid routed graph. Both are now given. The key is a closed form for H.12 (H.21.2): up to local unitaries it is the time reverse of the Lugano purification in which Bob's bit flip X is replaced by its square root √X. Code: code/stochastic/cyclic/embed/tds_h12.py, tds_h12.log, rg_h12.py, rg_h12.log.

H.21.1 Phase form, and WBO's general construction run concretely [phase form PROVED, exact; circuit NUMERICAL to $4\cdot10^{-14}$].

- *Phase form [PROVED, exact integer check].* Put Hadamard frames Hd on the past P and on the agents' inputs. Then H.12 becomes a *phase process* D: $|z\rangle_P|o\rangle_{AO} \mapsto \Phi(o, z)|z\rangle_{AI}|o\rangle_F$, with V_{H12} = (Hd)_{AI} D (Hd)_P and $\Phi(o, z) = i^{pre(z)} \cdot (-1)^{\{o_A(z_B \vee z_C)\}} \cdot i^{o_B z_A z_C} \cdot (-1)^{\{o_C z_B(1-z_A)\}}$, pre(z) = 3z_C + 2z_A + z_Bz_C + 3z_Az_C + z_Az_B + 2z_Az_Bz_C (mod 4). In words: the agents' inputs are a copy of the (rotated) past, and each agent's output only adds a phase that depends on the *other two* agents' inputs. There are no self terms. This is the cyclic dependency of H.12 written in closed form.
- *WBO's proof, run concretely [NUMERICAL].* WBO prove Prop. 1 (H.18.2) by fixing U_C and decomposing the remaining bipartite process into an "A before B" and a "B before A" part. We carried this out numerically for H.12:
  - Fix U_C (a qubit unitary with a qubit ancilla c′). $V * U_C$ is a bipartite unitary process with past P16 = (P, c′).
  - Its *sector algebra* is the set of operators X on P16 such that X ⊗ 1 commutes with every operator on A_I B_I pulled back through the process. It has dimension 8 and a two-dimensional centre (it is $M_2 \oplus M_2$). Its central projectors split P16 into an 8-dimensional "A first" sector and an 8-dimensional "B

first" sector, as in Barrett–Lorenz–Oreshkov and Yokojima et al. (refs. 43, 45). The algebra depends on U_C: two Haar-random U_C share only the identity.

- Matrix units of the M_2 algebra in each sector give WBO's isometries v_1, v_2, v_3. The middle registers have dimension 4 in both sectors, so WBO's padding qubits are not needed.
- The circuit is: ω_1 = [v_1 for A-first; v_1 for B-first] writing a control qubit Q; slot 1 (U_A if Q = 0, U_B if Q = 1); ω_2 (block-diagonal in Q); slot 2 (the other agent); ω_3. U_C enters only through the ω's.
- *Checks (20 Haar draws of all three agent unitaries with qubit ancillas).* The circuit equals the cyclic composition Cyc(V_{H12}; U_A, U_B, U_C) to $2.0\cdot10^{-14}$. The ω's are unitary to $2.7\cdot10^{-15}$. WBO's identity for C's time-delocalised subsystem (V = U1 ∗ id ∗ U2 with |Z| = 16, and U2†·[ω-chain]·U1† = $U_C \otimes 1_Z$) holds to $3.0\cdot10^{-14}$.
- This realisation is explicit but unstructured: the ω's are computed matrices that depend on U_C as a whole, which Prop. 1 allows. H.21.2 gives a structured one.

H.21.2 H.12 is a frame-rotated time reverse of a √X-Lugano process [PROVED, exact Gaussian-integer check].

- *Definition (√X-Lugano process).* Let G = √X = h S h = ½[[1+i, 1−i], [1−i, 1+i]], with h the qubit Hadamard and S = diag(1, i). G is symmetric and $G^2 = X$. With lug(a, b, c) = ((1−b)c, (1−c)a, (1−a)b) as in H.15.7e, set L_G: $|s\rangle_P|o\rangle_{AO} \mapsto (X^{lug_A(o)} \otimes G^{lug_B(o)} \otimes X^{lug_C(o)})|s\rangle_{AI} \otimes |o\rangle_F$. This is the Lugano purification L of H.15.7e.2 with Bob's flip X replaced by G. More generally write L_U for any qubit unitary U in Bob's place, so L = L_X.
- **Theorem H.21.2.** V_{H12} = (Hd X_C)_{AI} (Hd X_A)_F · L_G^T · (Hd)_{AO} (X_C Pre Hd)_P, where Pre = diag($i^{pre(z)}$) is a phase on the past and Hd = $h^{\otimes 3}$.
  - *Proof.* rg_h12.py checks the identity exactly: all entries of $8\cdot V_{H12}$ and of 128·RHS/16 are Gaussian integers, and they agree entry by entry. By hand: substitute $z_C \to 1 - z_C$ in the phase form of H.21.1. The output phases become $(-1)^{o_A\, f_A(z)}$, $i^{o_B\, f_B(z)}$ and $(-1)^{o_C\, f_C(z)}$, with f_A = 1 ⊕ lug_A, f_B = lug_B and f_C = lug_C. (For example $z_B \vee (1 - z_C) = 1 - (1 - z_B)\, z_C = 1 \oplus$ lug_A(z).) In the Hadamard frame on an output wire, a phase $(-1)^{o\, f}$ is the gate X^f and a phase $i^{o\, f}$ is the gate G^f. Collecting the constant flip from f_A, the substitution and the Hadamards gives the stated factors. ∎
  - *Consequence.* H.12 and H.13.2 are the same construction: H.13.2 is the frame-rotated time reverse of L_X (H.15.7e.2), and H.12 that of $L_{√X}$. This **corrects H.18.6**, which said, on the basis of H.15.8, that the explicit H.13.2 construction "does not carry over" to H.12. H.15.8 itself stays true: H.12 is not a phased permutation in the Hadamard frame, because G is not a permutation. But the construction does carry over once Bob's flip may be any unitary.
  - *Consistency with H.15.9(A) [PROVED, by the same invariant].* L_G is not a PF purification, so H.21.2 agrees with the NUMERICAL finding that H.12 is LU-equivalent to no L_g or L_g^T with g a PF.

H.21.3 An explicit TDS circuit for H.12 with time-local instances only [NUMERICAL to $7\cdot10^{-16}$; construction PROVED as in H.18.4(c)].

- *Forward circuit for L_G.* Take WBO's circuit for the Baumeler–Wolf process (H.18.4(b), tds_h13.py) and change one gate: in ω_2, branch Q = 0, the CNOT that writes Bob's flip becomes a controlled-G. Every other

gate is unchanged, so U_C enters only through its two time-local instances, U_C (in ω_1) and $U_C\ \sigma_x\ U_C\dagger$ (in ω_3). *Check:* the circuit equals Cyc(L_G; U_A, U_B, U_C) for 20 Haar draws, to $4.0\cdot10^{-16}$.

- *Reversal.* By H.18.4(c), the transposed circuit in reverse order realises ${L_G}^T$. Absorb the local factors of Theorem H.21.2 into the agents, $W\tilde{}_X = h\ W_X\ (h\ X^{[X = C]})$, and into a fixed preparation on P (X_C Pre Hd) and readout on F (Hd X_A). *Check:* the result equals Cyc(V_{H12}; W_A, W_B, W_C) for 20 Haar draws, to $6.8\cdot10^{-16}$.
- **So H.12 runs as an ordinary acyclic quantum circuit with each agent acting once on a time-delocalised subsystem, by an explicit circuit of the same shape as H.13.2's.** The placement in Minkowski space of H.18.5 applies verbatim.
- *Reading [INTERPRETIVE].* The only non-classical gate in the bare circuit is the controlled-√X. H.13.2's bare circuit is a classical permutation circuit, and all its quantumness sits in the frame changes. H.12 needs one genuinely quantum gate inside the loop as well.

H.21.4 A valid routed graph for H.12 [PROVED, with one CITED step].

- *The graph.* Take VOKB's routed graph for Lugano (their Fig. 27, ref. 18) and reverse it, as in Corollary H.15.7e.3. rg_h12.py re-encodes it: univocal, adjoint univocal, branches A, B, C: 2 each, X: 5, F: 1; 38 branch-graph arrows; the weak-loops principle holds. So it is valid in VOKB's sense.
- *The fleshing-out.* In VOKB's fleshing-out of Fig. 27, replace node B's CNOT (from l to p_B) by a controlled-G. The routes do not change, because the register p_B and Bob's input are not indexed in the graph (they sit in the agents' unindexed sectors). Exact check in Gaussian integers: each agent output has a unique consistent assignment, the F record determines the agents' outputs, and the composite is exactly L_G (and its transpose exactly ${L_G}^T$).
- *CITED step.* VOKB say explicitly (arXiv:2206.10042v3, Sec. 4.3) that the Lugano graph can be fleshed out with "arbitrary operations (as long as they follow the routes)", giving "a larger family of processes". So L_G is a member of VOKB's own family [CITED], and its validity follows from their theorem that fleshing out a valid routed graph gives a valid process. After the local unitaries of Theorem H.21.2, this is a valid routed circuit for H.12.
- *What is ours.* Only the identification of H.12 with this member of VOKB's family (Theorem H.21.2) and the exact checks. We do not claim the √X-Lugano process as a new object; we found no statement that it, or any member of VOKB's family other than Lugano, is purifiable-but-not-a-PF-blend in a classical frame.
- *Conjecture 1 of VOKB (H.15.7c).* Both counterexamples, H.12 and H.13.2, are now fleshings-out of valid routed graphs. So neither is a counterexample to VOKB's Conjecture 1. Theorem H.15.7d and Conjecture 2 predict that any valid graph for H.12 has loops in its branch graph, all of them weak. Our checker confirms the second half for this graph (every loop it finds is weak); it does not tabulate the loops, so the first half is not checked here.

H.21.5 Status of the H.12 spacetime items.

- PROVED: the phase form (H.21.1); Theorem H.21.2 (exact); the routed graph of H.21.4, with VOKB's fleshing-out theorem and family CITED.
- NUMERICAL: the generic WBO circuit (H.21.1, to $4\cdot10^{-14}$) and the structured circuit (H.21.3, to $7\cdot10^{-16}$).
- This closes the H.12 items left OPEN in H.18.6, H.18.7 and H.15.7c–e.

H.21.6 Classical fine-grained models for H.13.2: the question splits in two [both parts PROVED; elementary]. H.15.7b left OPEN whether a *classical* fine-grained model with multiple use, or with communicating sub-agents (VR Thm 5), reproduces H.13.2. H.18.5 answered the quantum half. The classical half turns out to depend entirely on what "multiple use" allows.

- **(a) Unrestricted multiple use: yes, for every valid classical process [PROVED].** Let p(i|o) be any valid three-party classical process (a point of Valid; it need not be purifiable). Let each agent k use any classical instrument $T_k(a_k, o_k \mid i_k, x_k)$, with setting x_k and outcome a_k. The following acyclic classical network reproduces the joint statistics $\Sigma_o\, p(i|o)\, \Pi_k\, T_k(a_k, o_k \mid i_k, x_k)$ exactly:
  1. For each agent k, two sub-agents k^0 and k^1 run the agent's instrument once each, with the same setting x_k, on the fixed inputs 0 and 1, with independent local randomness. Write $(a_k\text{^}j, o_k\text{^}j)$ for the result of sub-agent k^j.
  2. A central node N reads the six outputs $o_k\text{^}j$. They define a deterministic intervention $h_k(j) = o_k\text{^}j$. N samples i with probability $P(i \mid h) = \Sigma_o\, p(i|o)\, \Pi_k\, [o_k = h_k(i_k)]$.
  3. N announces i_k as agent k's input. Agent k's reported output and outcome are those of sub-agent k^{i_k}, the one that actually received input i_k. The other sub-agent's run is discarded.
  - *Proof.* $P(\cdot \mid h)$ is a probability distribution for every deterministic h: that is exactly the definition of Valid (fixed-point probability 1 for every deterministic local intervention). Summing over the discarded sub-agents' results, which are independent of everything else, leaves $\Sigma_o\, p(i|o)\, \Pi_k\, T_k(a_k, o_k \mid i_k, x_k)$. The network is acyclic: sub-agents, then N. ∎
  - So the H.15.7b question has the answer "yes" in its unrestricted classical form, for H.13.2 and H.12 and for every valid process, including the non-purifiable E_{ex1} (C.2). In particular the causal-inequality violations of H.15.7b and H.15.7d are reproduced, since they use classical instruments. The answer therefore says nothing about purity. Each agent's operation is applied twice, and which application counts is decided afterwards by N.
  - *Novelty.* None claimed. This is the standard trick of querying a classical operation on every input value. We expect it is folklore, but we did not find it stated for process functions or classical processes.
- **(b) Reversible single use on delocalised classical variables: no [PROVED, from D.6].** The classical analogue of a realisation on TDS (H.18.1) is a reversible classical circuit with a random source s, whose agents' operations are bijections h_k (with ancillas) and which, for each value of s, realises a classical reversible process W_s, i.e. the closed loop is a bijection for every choice of h. Then for each s the map $o \mapsto i$ of W_s is a process function, because a bijective closed loop needs exactly one consistent assignment for every local function. So the induced classical process is $\Sigma_s\, q(s)\, w_s \in \mathrm{conv}(PF)$, which is Proposition D.6 (and Barrett–Lorenz–Oreshkov Thm 6, ref. 45). H.13.2 and H.12 are outside conv(PF), so neither has such a model. The non-classicality of the H.18.4 and H.21.3 circuits is therefore necessary.
- **(c) What remains OPEN.** Intermediate notions: a classical model in which each agent's operation is applied once on a delocalised classical variable, but the circuit may be stochastic and irreversible (so that (b) does not apply), and in which the "post-selection" of (a) is excluded. We have not formulated such a notion precisely, so we do not claim an answer. *Update (Round 15, H.22.3):* counting time-local runs instead, the minimum budget for H.13.2 and H.12 is exactly four (one agent twice, the others once, in a dynamically chosen order); the version without any discarding stays OPEN.

H.21.7 A continuous path of pure boards from conv(PF) through H.12 to H.13.2 [purity PROVED with one CITED step and NUMERICAL; violations NUMERICAL; h12_family.py, h12_family.log].

- *The family.* For $\varphi \in [0, \pi]$ let $G_\varphi = \tfrac{1}{2}(1 + e^{i\varphi})\cdot 1 + \tfrac{1}{2}(1 - e^{i\varphi})\cdot X$, so $G_0 = 1$, $G_{\pi/2} = \sqrt{X}$ and $G_\pi = X$. Let V_φ be the right-hand side of Theorem H.21.2 with L_{G_φ} in place of L_G. Then $V_{\pi/2} = V_{H12}$ (checked to $3\cdot 10^{-16}$). In the Hadamard frame G_φ is $\mathrm{diag}(1, e^{i\varphi})$, so every V_φ is an X-type board with continuous phases.
- *Purity [PROVED with one CITED step; NUMERICAL check].* L_{G_φ} is a fleshing-out of VOKB's Lugano graph (H.21.4), so it is a valid unitary process [CITED, ref. 18, Sec. 4.3]; local unitaries and time reversal keep this. *Check:* for 25 values of φ and 5 Haar draws each, the closed loop is unitary to $3\cdot 10^{-15}$.
- *Classical restrictions [NUMERICAL].* Read V_φ in the computational frame and maximise each facet violation of conv(PF) over source states, as in H.13–H.14:
  - $\varphi = 0$: no facet is violated (the process lies in conv(PF)).
  - Every $\varphi > 0$ on the grid (steps of $\pi/24$) violates some facet. The maximum relative violation grows monotonically with φ: 0.0107 at $\varphi = \pi/24$, $0.1036 = (\sqrt{2} - 1)/4$ at $\varphi = \pi/2$ (the H.12 value of H.15.9(B)), and 0.1404 at $\varphi = \pi$ (the H.13.2 value of H.15.8). The maximum is always on orbit 91.
  - The number of violated orbits grows from 20 (small φ) through 40 ($\varphi = \pi/2$) to 60, then falls to 56 at $\varphi = \pi$.
  - Over the whole path, 60 orbits are violated. The 33 that never are consist of the 31 orbits that Z_4 boards never violate (H.13.4) plus orbits 85 and 90. So nothing on the path violates any of the 22 genuine never-crossed orbits (H.17.5) or the 8 orbits reached only by Z_8 boards (H.14.2).
  - Orbit 82 contains the H.12 certificate facet 1741. Its maximum on the path rises from 0 to 0.0800 at $\varphi = \pi/2$ and to 0.1036 at $\varphi = \pi$, which is its Z_4 maximum (J.3).
- *Reading.* H.12 and H.13.2 are two points on one continuous path of pure processes, which leaves conv(PF) as soon as the gate in Bob's place stops being the identity [NUMERICAL on the grid; small φ not resolved below $\pi/24$].
- *What this does and does not say about Purif (open item H.13/H.14.4).* It adds a new, continuous source of evidence that the 22 orbits might be valid on Purif, but the family is X-type, so it does not test non-X-type boards. *Update (Round 15, H.22.2): that caveat was decisive. With frames on the output wires, the endpoint process (time-reversed Lugano) crosses ten of the 22 orbits, a generalised Lugano board two more; 10 remain open.* A smooth curve inside a convex set says nothing about whether the set is a polytope, so the polytope question stays **OPEN**.

H.21.8 The H.12 bound gap: a lifted relaxation narrows it to [−1.27720, −0.70580] [lower bound PROVED, exact integer certificate; seesaw NUMERICAL; h12_lift.py, h12_lift_dual.py, h12_lift_verify.py, h12_lift_common.py and logs; h12_seesaw2.py, h12_seesaw2.log].

- *Lifted-A relaxation (defined here).* In the NS relaxation of H.15.9(C), each setting triple x gets its own operator family, so nothing forces A's two POVMs to exist together. The lifted relaxation puts A's two POVMs on two copies A, A′ of A's qubit. The variables are $Z_v \geq 0$ on A⊗A′⊗B⊗C (16×16), with $v = (c_{A|0}, c_{A|1}, x_B, x_C, c_B, c_C)$. They satisfy the following constraints:
  - for each (x_B, x_C), the sum over all outcomes is 1;
  - summing out $c_{A|1}$ (respectively $c_{A|0}$) leaves an operator of the form $X \otimes 1_{A'}$ (respectively $1_A \otimes X$);

    - the NS constraints for B and for C, as in H.15.9(C). The $x_A = 0$ statistics are read on A and the $x_A = 1$ statistics on A′.
    - Every product $E^A_{\cdot|0} \otimes E^A_{\cdot|1} \otimes E^B_{\cdot|x_B} \otimes E^C_{\cdot|x_C}$ is feasible, and its objective equals $y_A \cdot P$. This was checked on random POVM triples (agreement to 10^{-12}). So with the H.15.7d reduction, the minimum is a lower bound over all instruments.
    - The relaxation is at least as tight as NS, because every feasible point projects to an NS-feasible family.
- *Numerical values [NUMERICAL, SCS].* The primal gives −1.277228 (1,200 iterations, residuals $\le 3 \cdot 10^{-5}$). The independently formulated dual gives −1.2771490.
- **Certified bound [PROVED; exact integer arithmetic].** For every choice of instruments, $y_A \cdot P(\text{H.12}) \ge -41851085693392143/32768000000000000 \approx -1.2771938$.
    - *Certificate.* For any Hermitian multipliers $\Lambda_{x_B\, x_C}$ (normalisation), G (the twirl constraints, through $G - T_q\, G$ with T_q the Pauli twirl of qubit q) and D (B, C setting independence), the following identity holds on feasible Z: $y_A \cdot P = \Sigma\ \mathrm{Tr}\ \Lambda + \Sigma_v\ \mathrm{Tr}[S_v\, Z_v]$. Hence $y_A \cdot P \ge \Sigma\ \mathrm{Tr}\ \Lambda + 16\ \Sigma_{x_B,x_C}\ \min_v t_v$ whenever $S_v - t_v \cdot 1 \ge 0$.
    - *Rounding.* The SCS multipliers are rounded to Gaussian dyadics with denominator 2^{30} and made exactly Hermitian, and the twirls are applied exactly. The cost matrices (entries in $\mathbb{Q}(i,\sqrt{2})$) are replaced by dyadic matrices from 60-digit evaluation, with an error contribution below 10^{-15}; 10^{-12} is subtracted to cover it.
    - *Positivity check.* Then $2^{64} \cdot S_v$ is a Gaussian-integer matrix. For each of the 1,024 v, a dyadic t_v is certified by Sylvester's criterion on the 32×32 real form: every leading principal minor is positive, computed exactly by Bareiss elimination. The worst t_v is $-8.9 \cdot 10^{-7}$, so rounding costs about $6 \cdot 10^{-5}$.
- **Achievable side [NUMERICAL].** 120 further seesaw restarts (seeds 101 and 102, random POVM and random rank-1 projective starts) reach at best −0.6597, the same local optimum as before (H.15.9(C)), and −0.4832. None goes below −0.70580.
- **Status.** The optimum of y_A over all instruments lies in **[−1.27720, −0.70580]** [PROVED both ends]. *Update (Round 15, H.22.1): lifting B instead of A certifies $y_A \ge -1.20330$, so the interval is now [−1.20330, −0.70580]. Round 16, H.23.3: [−1.16564, −0.70580].* This improves the lower end from −1.58556 (NS+PPT) to −1.27720. Closing the gap remains **OPEN**. Natural next steps are the lifted relaxation with PPT constraints (about five times the memory of this run, beyond the box), lifting B and C as well, and an upper-side search beyond seesaw.
- *Novelty.* None is claimed for the method. Requiring one party's measurements for both settings to exist on copies is the idea behind symmetric-extension and inflation-type relaxations. Only the numbers for H.12 are new.

H.22 Round 15: the H.12 gap, the never-crossed orbits, and classical models with bounded reuse (Oct 24 2026) [labels as in H.21]

H.22.1 The H.12 gap: lifting B certifies $y_A \ge -1.20330$; lifting C and a structured search do not help [lower bound PROVED, exact integer certificate; the rest NUMERICAL; h12_lift_common.py, h12_lift_dual.py, h12_lift_verify.py with LIFTP=1, h12_lift_dual_B.log/.pkl, h12_lift_verify_B.log, h12_lift_dual_C_partial.log; h12_struct_search.py, h12_struct_search.log].

- *Lift-B and lift-C (defined here).* The lifted relaxation of H.21.8 copies one party's qubit so that the POVMs for both of its settings exist together. H.21.8 lifted A. Setting the environment variable LIFTP = 1 (or 2) relabels the parties exactly, so that B (or C) takes the lifted position; the objective y_A and the board are relabelled with them, and nothing else changes. The verifier relabels its exact 2^{-63}-grid copy of the board in the same way and checks it against the float board to 10^{-14}. Each lift is a valid relaxation by the argument of H.21.8, so each gives its own lower bound, and the best one counts.
- **Certified bound [PROVED; exact integer arithmetic, as in H.21.8].** For every choice of instruments, $y_A \cdot P(\text{H.12}) \geq -315437701416277769/262144000000000000 \approx \mathbf{-1.2032993}$.
    - The SCS dual of lift-B reached −1.2032564 (status optimal, 689 s). After rounding to Gaussian dyadics and exact twirling, the four worst t_v are between $-5.96\cdot10^{-7}$ and $-7.15\cdot10^{-7}$, all certified by Sylvester's criterion with Bareiss elimination. The rounding costs about $4\cdot10^{-5}$.
- *Lift-C [NUMERICAL, not certified].* The lift-C dual was stopped after 1,750 SCS iterations with its objective steady near −1.30, weaker than lift-A (−1.27720) and lift-B. So lifting B is the useful choice for y_A, which treats the parties asymmetrically.
- *Achievable side [NUMERICAL, negative].* h12_struct_search.py restricts every party and setting to structured measurements: a deterministic outcome, or a projective qubit measurement along one of the 13 cube axes (Pauli axes, the face diagonals reached by √X-type quarter turns, cf. H.21.2, and the body diagonals), with its two projectors on two of the four outcomes. That is 160 options per party and setting. 3,000 restarts of discrete coordinate descent reach −0.41656 at best; 30 continuous seesaw polishes started from the best discrete optima reach −0.705802, the known value, and nothing lower.
- **Status.** The optimum of y_A over all instruments lies in **[−1.20330, −0.70580]** [PROVED both ends]. The gap shrinks from 0.5714 to 0.4975. Closing it remains **OPEN**. Untried: lifting two parties at once (memory beyond the box), PPT constraints on the lift, and non-projective structured instruments. *(Round 16, H.23.3: intersecting lift-A with lift-B certifies $y_A \geq -1.16564$; interval now [−1.16564, −0.70580].)*
- *Novelty.* None for the method (as in H.21.8). Only the numbers for H.12 are new.

H.22.2 Twelve of the 22 never-crossed orbits are crossed by pure boards: the time-reversed Lugano process in rotated local frames, and a generalised Lugano board [violation PROVED, exact rational certificate; purity CITED (Guérin–Brukner) plus local unitaries; search NUMERICAL; never22_lugU.py, never22_lugU_1.log, never22_hitopt.py/.log, never22_hitcheck.py, never22_hitcheck2.py, never22_lugT_check.py/.log, never22_cert.py, never22_cert.log, never22_cert_lugT.log, rg_lugU.py/.log, never22_best.npy].

- *The search family (defined here).* Generalised Lugano boards L_{U_A,U_B,U_C}: $|s\rangle_P|o\rangle_{AO} \mapsto (U_A{}^{\text{lug_A}(o)} \otimes U_B{}^{\text{lug_B}(o)} \otimes U_C{}^{\text{lug_C}(o)})|s\rangle_{AI}|o\rangle_F$, with any qubit unitaries U_k ($L_{X,X,X}$ is the Lugano purification L of H.15.7e.2, $L_{X,\sqrt{X},X}$ is the board behind H.12, H.21.2). We take L_U or its time reverse $L_U{}^T$, and then put an independent SU(2) frame on every agent's input wire and on every agent's output wire (6 frames, 30 real parameters with the U_k). The objective is the largest relative violation, maximised over the source state, of any of the 5,120 facets in the 22 orbits.
    - *Why this family is new here.* H.17.6 rotated only the agents' input wires of X-type boards. A frame on an output wire destroys the lift form (F no longer records o in the measured basis), so these boards lie outside every family searched before.
    - *Purity of the family [PROVED, with the CITED step of H.21.4].* In VOKB's fleshing-out of the Lugano graph, node k applies a controlled-X from the routing index to an unindexed past qubit.

Replacing it by a controlled-U_k changes no route, and the consistent index assignment for each agent output does not involve the gates. So the composite is L_{U_A,U_B,U_C} for every choice of gates (rg_lugU.py: exact for Lugano and √X-Lugano, and to 0 deviation for 200 Haar triples; closed loops with random local unitaries are unitary to $2.6\cdot10^{-15}$, for L_U and $L_U{}^T$). Time reversal preserves validity (Guérin–Brukner App. D; VOKB Def. B.10), and local frames are absorbed into the agents' operations.

- *Search [NUMERICAL].* 4,000 random boards (seed 1): one violates the 22 orbits, by 0.00232 (orbits 14 and 25; time-reversed). Powell from it reaches a relative violation of **0.046472** on orbits 14 and 25, and simultaneously 0.005191 on each of orbits 4–11 (96 violated facets in each of 4–11, 48 in each of 14 and 25). Optimising orbit 14 alone from the same start (never22_hitopt) gives the same 0.046472.
- **Structure of the optimum [NUMERICAL, to the Powell tolerance $2.5\cdot10^{-6}$].** All three optimised node unitaries have eigenphase gap π, so $U_k = e^{ia_k}\, R_k\, X\, R_k\dagger$. Then $L_U = (R_A\otimes R_B\otimes R_C)_\{AI\}\, D_F\, L_X\, (R_A\dagger\otimes R_B\dagger\otimes R_C\dagger)_P$ with D an o-dependent phase on F (never22_lugT_check). Hence the optimum is, up to local unitaries on the agent wires, a unitary on the past and a phase on the future, the **time-reversed Lugano process $\mathbf{L_X{}^T}$** of Guérin and Brukner (ref. 38): no new node gate is needed, only input and output frames.
- **Theorem H.22.2 [PROVED; exact rational arithmetic].** Let $V = (F_I \otimes 1_F)\cdot L_X{}^T \cdot (F_O \otimes 1_P)$, where $L_X{}^T$ is the time-reversed Lugano purification (a 64×64 permutation matrix) and F_I, F_O are products of three qubit unitaries with Gaussian-rational entries (listed implicitly by never22_cert.py MODE=lugT from never22_best.npy). There is a Gaussian-rational source vector ψ such that the classical process $p(i|o) = \Sigma_f\, |\langle i\, f|V|o\, \psi\rangle|^2/\langle\psi|\psi\rangle$ violates one facet of each of the orbits **4, 5, 6, 7, 8, 9, 10, 11, 14 and 25**: relative values −0.0464708 (orbits 14 and 25) and −0.0051703 (orbits 4–11). V is a valid pure process (time-reversed Lugano is valid, Guérin–Brukner 2018 [CITED]; H.15.7e.2 [PROVED/CITED]; local unitaries). Hence **these ten orbits are not valid on Purif.**
  - *Certificate.* Each frame is made exactly unitary by the Cayley transform: $U = w(1 + iK)(1 - iK)^{-1}$ with $w \in \{\pm1, \pm i\}$ and K Hermitian with entries rounded to denominator 1000 from the float optimum (distance $6.3\cdot10^{-4}$ from it). The script then checks, all in exact Gaussian-rational arithmetic: $V\dagger V = 1$; $p \geq 0$, normalised, and every one of the 64 deterministic local interventions has fixed-point probability exactly 1; the facet functional, rationalised, reproduces the integer facet values on all 744 PFs exactly (as in validcert, H.17.5; Valid and aff(PF) both have dimension 37, so the functional is well defined on Valid); and its exact value at p is negative. The same check with the general L_U board (nodes rationalised too, purity via rg_lugU) also passes for all ten facets (never22_cert.log).
  - *Scope.* "Crossed" is meant as in J.1: some facet of the orbit is violated. This board violates 96 of the 384 facets in each of orbits 4–11 and 48 of the 192 in each of orbits 14 and 25. Whether every facet of these orbits is violated by some pure board depends on whether the symmetry group of the PF polytope used to form the orbits maps Purif into itself, which we have not checked. *Settled in Round 16 (Proposition H.23.1a): it does, so every facet of these orbits is violated on Purif.*
- **Consequences (corrections).**
  - The "22 genuine never-crossed orbits" of J.1, H.17.5 and H.15.4 item 7 were never crossed by the boards searched until Round 15; they are not all valid on Purif. With the addendum below, **the open list is now the 10 orbits 26, 28, 30, 31, 54, 57, 66, 69, 75, 81.** *Update (Round 21, H.28.1): orbits 26, 30 and 31 are crossed too; the open list is now the 7 orbits 28, 54, 57, 66, 69, 75, 81 (15 of 22 crossed). Round 22 (H.29): unchanged. Round 23 (H.30): unchanged.*

    - H.21.7's reading ("new, continuous evidence that the 22 orbits might be valid on Purif") is superseded for these ten orbits. The X-type path itself is unaffected: it still violates none of them.
    - H.15.4 item 7's guess that the 22 are "classical-like constraints that may bind every reversible quantum loop" is false for ten of them.
- **Addendum: orbits 53 and 79 [violation PROVED, exact rational certificate; purity PROVED with the CITED fleshing-out step; never22_lugU.py with ORBITS restricted to the 12 orbits left (seed 2), never22_best2.npy, never22_cert2.log, never22_purity2.py/.log].** With the objective restricted to the 12 orbits left after Theorem H.22.2, one of 4,000 random boards (seed 2) violates them by 0.00341, and Powell reaches 0.015474 on orbit 53 and 0.006727 on orbit 79 (it also violates orbits 14 and 25). Here the node unitaries are not reflections: U_A and U_B have eigenphase gap 0.31725π and U_C has gap π. So the reduction to Lugano above does not apply, and this is a genuinely generalised (time-reversed, framed) Lugano board. never22_cert.py in general mode (nodes and frames Cayley-rationalised, denominator 1000) certifies exactly that one facet of orbit 53 (index 10160; relative value −0.0154741) and one of orbit 79 (index 10137; relative value −0.0067548) are violated, with the same exact checks as for Theorem H.22.2. Purity rests on the fleshing-out argument (rg_lugU; VOKB Sec. 4.3 [CITED]), time reversal and local frames. Numerically, the closed loop with Haar local unitaries is unitary to $2.2\cdot10^{-15}$. **The never-crossed open list is now the 10 orbits 26, 28, 30, 31, 54, 57, 66, 69, 75, 81.**
- *Reading [INTERPRETIVE].* The frames matter: the same process in the computational frame gives a PF mixture (H.15.8.1), in the Hadamard frame it gives H.13.2, which crosses other orbits but not these, and in generic non-Clifford frames on both input and output wires it crosses ten "never-crossed" orbits. The never-crossed list measured the reach of the frames tried, not a property of Purif.
- *Novelty.* The process (time-reversed Lugano), its validity and its causal-inequality violation are due to Guérin and Brukner (2018). The facets are the paper's own PF-hull facets, so the statement that framed Lugano^T crosses orbits 4–11, 14 and 25, with exact certificates, is ours; we found no prior statement about these facets and claim nothing beyond it.

H.22.3 Classical fine-grained models with bounded reuse: one extra run of one agent is necessary and sufficient [PROVED, with one CITED step; NUMERICAL check; code/stochastic/cyclic/embed/class_reuse.py, class_reuse.log]. H.21.6 settled the two extremes (unrestricted multiple use: yes; reversible single use: no). Here we settle the natural counting version of the middle regime: how many time-local runs of the agents' classical instruments does a classical acyclic model need?

- *Setting (defined here).* A *classical model with run budget r* is an acyclic classical stochastic network (irreversible gates and fresh randomness allowed, classical control of which node acts next allowed) in which the agents' instruments $T_k(a_k, o_k \mid i_k, x_k)$ are black boxes, called r times in total, each call at one time-local slot on an input computed by the network. Afterwards the network announces each agent's input i_k, and the reported (a_k, o_k) must be the result of one of agent k's calls on input i_k. The model *reproduces* a classical process p if the joint law of (i, o, a) equals $\Sigma_o\, p(i|o)\, \Pi_k\, T_k(a_k, o_k \mid i_k, x_k)$ for every choice of instruments and settings. H.21.6(a) is the case r = 6 (each agent called on both inputs); Lemma H.15.7a covers r = 3 with each agent called once.
- **Theorem H.22.3.** Let p be any valid three-party classical process with binary inputs and outputs.
    - (a) *[PROVED, with one CITED step.]* A model with r = 4 reproduces p: agent C is called twice, on inputs 0 and 1, and A and B once each, in an order the network chooses at random as a function of C's two outputs.

    - (b) *[PROVED, from Lemma H.15.7a.]* No model with r = 3 reproduces p if p violates a causal inequality. This holds for the classical restrictions of H.13.2 and H.12 (H.15.7b, H.15.7d).
    - So for both counterexamples the minimum run budget is exactly 4: one extra run of one agent.
- *Proof of (a).*
    1. C's two calls give (a_C^0, o_C^0) and (a_C^1, o_C^1). Write $h_C(j) = o_C\text{^}j$; this is a deterministic local function of C.
    2. Define the *slice* $W_h(i_A, i_B \mid o_A, o_B) = \Sigma_\{i_C\}\ p(i_A, i_B, i_C \mid o_A, o_B, h(i_C))$. For each h it is a valid bipartite classical process: composing it with any deterministic interventions of A and B is composing p with deterministic interventions of all three, which gives total probability 1.
    3. Every valid bipartite classical process is causally separable: $W_h = W_h^{A\prec B} + W_h^{B\prec A}$, with both terms non-negative, the first not signalling from B to A and the second not from A to B (Oreshkov, Costa and Brukner, arXiv:1105.4464, Nat. Commun. 3, 1092 (2012), appendix "Causal order in the classical limit", proved there for process matrices diagonal in the pointer basis) [CITED].
    4. The network picks the branch "A first" with probability $\Sigma\ W_h^{A\prec B}$ (this is independent of o_A, o_B by the no-signalling constraints). In that branch it samples i_A from the normalised marginal, calls A, samples i_B given (i_A, o_A), and calls B. The "B first" branch is symmetric.
    5. Finally it samples i_C from $p(i_A, i_B, i_C \mid o_A, o_B, h(i_C)) / W_h(i_A, i_B \mid o_A, o_B)$, and reports C's call on input i_C. The discarded call is independent of everything else, so summing it out gives $\Sigma_o\ p(i|o)\ \Pi_k\ T_k$ exactly. The network is acyclic: C's calls, then the dynamically ordered A and B, then the announcement. ∎
- *Check [NUMERICAL].* class_reuse.py finds the decomposition of step 3 by linear programming for every slice and builds the network. The network's exact joint law is compared with the process for 20 random instrument triples on each of nine processes: the Lugano PF, and the classical restrictions of H.13.2 and of H.12 with four source states each ($|000\rangle$ and three random). The maximum deviation is $2.8 \cdot 10^{-17}$.
- *The parallel with the quantum circuits [INTERPRETIVE].* The quantum TDS circuits for H.13.2 (H.18.4) and H.12 (H.21.3) have the same resource count: C has two time-local instances and A, B act once each in a (coherently) controlled order. In the classical model C's second call is queried and then partly discarded; in the quantum circuit both instances of C are used coherently (U_C, then $U_C\ \sigma_x\ U_C\dagger$) and nothing is post-selected. So r = 4 is not a quantum advantage in the run budget. What the quantum circuit buys is that it needs neither discarding nor knowledge of C's full function.
- *Scope.* The construction extends to N parties by calling all but two agents on every input value; we have not studied whether that budget is minimal for N > 3. "Irreversible single use on delocalised classical variables" without any discarding stays **OPEN**, as in H.21.6(c), because we still have no precise definition of a delocalised classical variable outside the reversible case.
- *Novelty.* The ingredients are standard: querying a classical box on all inputs, and the causal separability of bipartite classical processes (OCB 2012). We found no statement of the run-budget count for classical processes that violate causal inequalities, but we claim no more than the combination.

H.22.4 Correction to H.20.6: Mathlib does have the spectral theorem for compact self-adjoint operators [CITED, checked in the pinned Mathlib; the boundedness gap itself stays OPEN].

- H.20.6 said that the Jordan decomposition needed for automatic boundedness "needs the spectral theorem for compact self-adjoint operators on an infinite-dimensional Hilbert space, which Mathlib does not have". That is wrong. The Mathlib pinned by this repository (lean-toolchain v4.34.1; Mathlib commit d13f23b)

contains, in Mathlib/Analysis/InnerProductSpace/Spectrum.lean, `ContinuousLinearMap.orthogonalComplement_iSup_eigenspaces_eq_bot` (for IsCompactOperator T and T.IsSymmetric, the eigenspaces have trivial orthogonal complement) and `ContinuousLinearMap.finite_dimensional_eigenspace` (nonzero eigenspaces are finite-dimensional). Both came in with Mathlib PR #36520 (commit 36f4d76, checked in the package's git history).

- The repository already uses the first one: PFUL/Schmidt.lean (Oct 22 2026) builds a Hilbert basis of eigenvectors of |T| from it and proves the Schmidt decomposition with $\Sigma\, s_n = \|T\|_1$. H.20.6 (Round 13) was therefore inconsistent with the repository's own Lean files.
- *What the gap actually is.* For self-adjoint trace-class T, apply the same theorem to T itself (compact, by `isCompactOperator_of_mem`) to get an eigenbasis with real eigenvalues λ_n, set $T_+ = \Sigma_{\lambda_n>0}\, \lambda_n |v_n\rangle\langle v_n|$ and $T_- = -\Sigma_{\lambda_n<0}\, \lambda_n |v_n\rangle\langle v_n|$, and show both are trace class with $\mathrm{Tr}\, T_+ + \mathrm{Tr}\, T_- = \Sigma|\lambda_n| = \|T\|_1$. Then $\|\Phi(T)\|_1 \le \mathrm{Tr}\, \Phi(T_+) + \mathrm{Tr}\, \Phi(T_-) = \|T\|_1$ for positive trace-preserving Φ, and $\|\Phi\| \le 2$ on general T. This is routine given Schmidt.lean, but it has **not** been formalised this round; the status of the gap is **OPEN, with no known Mathlib obstruction**.
- *Update (Round 16, H.23.2): closed in Lean.* The formalisation does not use the eigenbasis: Mathlib's continuous functional calculus gives T_+, T_- directly.

H.23 Round 16: the never-crossed orbits, automatic boundedness in Lean, and the H.12 gap (Oct 24 2026) [labels as in H.21]

H.23.1 The never-crossed orbits: orbit-level crossing for the twelve crossed orbits, the generalised Lugano family is exhaustive for XOR boards, and further searches find nothing [symmetry and enumeration PROVED by exhaustive check; searches NUMERICAL; the 10 orbits stay OPEN; embed/h16_orbit_sym.py/.log, embed/h16_enum_xor.py/.log, embed/h16_permboards.py/.log, embed/h16_gen_search.py, h16_gen_run.py, h16_lugboard.py, h16_gen_lug.log, never22_lugU_3_open10.log].

- **Proposition H.23.1a (orbits are Purif-symmetric) [PROVED, exhaustive check].** The 384-element group G (physics/facets/G.npy) used to form the facet orbits (h13/analyze.py) is exactly the group generated by party permutations, input-bit flips and output-bit flips acting on the 744 PF tables p(i|o) (h16_orbit_sym.py: the generated group and G.npy coincide as sets of permutations of the 744 PFs). For each of the 22 orbits of J.1, the G-orbit of one facet (through its set of tight PFs, which determines the facet) is the whole orbit. Every generator is realised on pure processes by a local unitary (Pauli X on one agent's input or output wire, absorbed into the agent) or by relabelling the parties, so it maps valid pure processes to valid pure processes, and Purif onto itself; the facet functional transforms with it and the relative violation is unchanged.
  - *Consequence.* H.22.2's open scope question is settled: **every facet** of orbits 4–11, 14, 25, 53 and 79 (3,584 facets) is violated by some board in Purif, namely the certified board of Theorem H.22.2 or of the addendum transformed by a local X frame and a party relabelling.
  - *Consequence for the open orbits.* For each of the 10 open orbits it suffices to test one representative facet; the 1,536 facets fall into 10 such classes (orbit sizes 192, 192, 192, 192, 96, 192, 96, 192, 96, 96). *Update (H.28.1):* orbits 26, 30 and 31 are now crossed; 7 orbits (960 facets) remain open.
- **Proposition H.23.1b (XOR boards) [PROVED, exhaustive enumeration; h16_enum_xor.py].** Consider classical deterministic boards $i = s \oplus f(o)$ on three binary parties with f_k depending only on o_{-k} (the form that makes the Lugano-type lift valid). Exactly 744 of the 4,096 choices are valid for every s, and they are

the 744 PFs. The 64 with no constant f_k have every f_k a single minterm (truth table 1, 2, 4 or 8 on o_{-k}) or its complement (7, 11, 13 or 14), and each is the Lugano function up to party relabelling, input negation and complementation of outputs; the other 680 have a constant f_k, so that party acts first and the rest is a bipartite PF; these are causal, 192 of them with an order that depends on the first party's output (h16_enum_xor.log: 256 of the 744 admit no fixed order, 64 of them non-causal). Input negation and output complementation are Pauli-X frames. Hence the framed generalised Lugano family L_U, $L_U{}^T$ of H.22.2 already contains the lift of every XOR board in every local frame, and the controlled-root-of-Pauli boards are the case $U_k = X^{1/m}$ (up to frames), so neither family can add new boards.

- **Search beyond XOR [NUMERICAL].**
  - *Generalised Lugano with frames, restricted to the 10 open orbits.* Seed 3 (8,000 random boards plus Powell from the five best; never22_lugU.py with ORBITS set to the 10, never22_lugU_3_open10.log) finds no violation: the largest violation found is 0 (boards on which a facet is tight), never positive.
  - *Reversible non-XOR permutation boards.* $V|o, s\rangle = |f_s(o)\rangle_{AI}|o\rangle_F$ with every f_s a PF and $s \mapsto f_s(o)$ a bijection for each o (h16_permboards.py). Of 200 random such boards (backtracking sampler), none is XOR and none is valid as a quantum process: the Araújo et al. projector residual $\|\Pi_V\, W - {}_{(}\mathrm{all}_{)}\, W\|^2$ (M. Araújo, C. Branciard, F. Costa, A. Feix, C. Giarmatzi and Č. Brukner, Witnessing causal nonseparability, New J. Phys. 17, 102001 (2015), arXiv:1506.03776) is between 14 and 70.1 (h16_permboards.log). So classical reversible validity for every s does not give quantum validity here, and this family gives no candidates.
  - *Unrestricted penalty search.* Over all 64×64 unitaries V ($P \otimes AO \to AI \otimes F$), maximising a soft maximum of the open-orbit violations minus μ times the projector residual, μ ramped from 10 to 10^5, started from three random framed Lugano boards (Adam, 3,000 steps each). The residual did not converge (final residuals 0.131, 0.166 and 0.239; largest open-orbit value −0.0051, i.e. no violation), so the runs end at invalid processes and say nothing either way. A generic hit would in any case be hard to certify exactly.
- **Status [OPEN].** The 10 orbits 26, 28, 30, 31, 54, 57, 66, 69, 75, 81 are neither crossed nor proved valid on Purif. We did not find a proof route: the natural candidate, an SOS certificate that the facet functional is non-negative on the classical restriction of every W with $\Pi_V\, W = W$ (Araújo et al. 2015) and $W^2 \propto W$, is a degree-two problem in the 2^{12}-dimensional W with a rank constraint, out of reach of the tools used here.
- *Novelty.* The symmetry group of the PF polytope, the projector characterisation of validity (Araújo et al. 2015) and the Lugano process (Baumeler and Wolf [15]; its purification, Araújo et al. [17]) are known. The two propositions are bookkeeping facts about this paper's facets and boards.

H.23.2 The Round 8/9 boundedness gap is closed in Lean: positive trace-preserving maps on the trace class are trace-norm bounded, so `IsNormalCPTP` ⇔ `IsCPTP` [PROVED (Lean); lean/PFUL/AutoBounded.lean, lean/PFUL/AutoBoundedKraus.lean, lean/Round16_axioms.lean/.log; the sharp constant CITED, not formalised].

- *Statement.* Let H, K be complex Hilbert spaces of any dimension and Φ a map from bounded operators on H to bounded operators on K that sends the trace class to the trace class, is linear there, preserves the trace and sends positive trace-class operators to positive operators (`PFUL.TraceClass.IsPTP`; complete positivity is not needed). Then for every trace-class T
  - $\|\Phi(T)\|_1 \le \|T\|_1$ if T is self-adjoint (`IsPTP.traceNorm_le_selfAdjoint`), and

    - $\|\Phi(T)\|_1 \le 2\|T\|_1$ in general (`IsPTP.traceNorm_le`). Hence every `IsCPTP` map is `IsNormalCPTP` (`IsCPTP.isNormalCPTP`), and the two predicates are equivalent (`isNormalCPTP_iff`).
- *Proof (as formalised).*
    1. *Jordan decomposition* (`jordan`). For self-adjoint trace-class S, take S^+ and S^- from Mathlib's continuous functional calculus (`CFC.posPart_sub_negPart`, `CFC.posPart_add_negPart`, `CFC.posPart_nonneg`, `CFC.negPart_nonneg`). Then $S^+ - S^- = S$ and $S^+ + S^- = |S|$, so S^± = ½(|S| ± S) are trace class, because |S| is (`absOp_mem`, Round 7) and the trace class is a subspace.
    2. For positive trace-class P, $\|P\|_1 = \mathrm{Tr}\, P$ is real and non-negative (`traceNorm_of_isPositive`, `trace_of_isPositive`, from $\|T\|_1 = \mathrm{Tr}|T|$ and $|P| = P$).
    3. For self-adjoint S: $\|\Phi S\|_1 \le \|\Phi S^+\|_1 + \|\Phi S^-\|_1 = \mathrm{Tr}\,\Phi S^+ + \mathrm{Tr}\,\Phi S^- = \mathrm{Tr}\, S^+ + \mathrm{Tr}\, S^- = \mathrm{Tr}|S| = \|S\|_1$.
    4. For general T, write T = R + iJ with R = ½(T + T†) and J = −(i/2)(T − T†) self-adjoint, and $\|R\|_1, \|J\|_1 \le \|T\|_1$ (`traceNorm_adjoint_le`, from Tr A† = conj Tr A, `trace_adjoint`, and the variational formula for $\|\cdot\|_1$). Then $\|\Phi T\|_1 \le \|\Phi R\|_1 + \|\Phi J\|_1 \le 2\|T\|_1$. All nine new theorems depend only on propext, Classical.choice and Quot.sound (Round16_axioms.log); there is no sorry, admit or native_decide.
- *Corrections to H.20.6 and H.22.4.* Neither the spectral theorem for compact operators nor the Schmidt decomposition was needed: the continuous functional calculus that Mathlib already provides for bounded operators on a Hilbert space (a C*-algebra) gives the Jordan decomposition directly, and the trace-class bookkeeping was already in the repository. H.22.4's plan via an eigenbasis of T would also have worked, but it is longer.
- *Consequences [PROVED (Lean)].*
    - `isCPTP_iff_kraus_any`: on ℓ^2 of any cardinality, a map is CPTP iff it is a Kraus channel, with no boundedness assumption (Round 13's `isNormalCPTP_iff_kraus_any` with the normality hypothesis removed).
    - `PFUL.Counterexample.valid_CPTP_Vsb_any`: the Switchboard (H.12) is valid against arbitrary CPTP local channels on ancillas of any cardinality (Round 13's `valid_normalCPTP_Vsb_any` without normality).
    - Section 9 caveat (4) and research item 4's "automatic boundedness" are therefore closed. Caveats (1)–(3) are unchanged.
- *Scope.* The constant 2 is not sharp. For positive trace-preserving Φ, in fact $\|\Phi\|_{1\to 1} = 1$: the dual map Φ* on B(K) is positive and unital, so $\|\Phi^*\| = \|\Phi^*(1)\| = 1$ by the Russo–Dye theorem (B. Russo and H. A. Dye, Duke Math. J. 33, 413 (1966); see V. Paulsen, *Completely Bounded Maps and Operator Algebras*, Cambridge 2002, Cor. 2.9), and $\|\Phi\| = \|\Phi^*\|$ by trace duality [CITED; not formalised]. The constant 1 is not needed for anything in this paper: boundedness alone is what `IsNormalCPTP` asks for. We have also not formalised that Φ* is normal (weak*-continuous); that also follows from boundedness on paper.
- *Novelty.* Automatic boundedness of positive maps between the trace classes is classical (it follows, for example, from the Russo–Dye argument above, or from the Jordan decomposition exactly as here). What is new is only the formalisation against the repository's own trace class, and the resulting removal of the normality hypothesis from the Round 12–13 theorems.

H.23.3 The H.12 gap: intersecting lift-A and lift-B certifies $y_A \ge -1.16564$ [lower bound PROVED, exact integer certificate; solver values NUMERICAL; embed/h16_liftAB_scs.py, h16_liftAB_verify.py, h16_liftAB_linkcheck.py and their .log files]. Target 3 of Round 16.

- *Relaxation.* We impose two lifted families at once: Z^A on (A, A′, B, C), the lifted-A relaxation of H.21.8, and Z^B on (B, B′, A, C), the lift-B relaxation of H.22.1. Each family keeps all of its own constraints. They are linked by requiring the same induced no-signalling family: $F^A_\{x,c\} = F^B_\{x,c\}$ for all 8 settings x and 64 outcome triples c, where $F^L_\{x,c\} = ½\ \mathrm{Tr}_{\text{unused copy}}\ \Sigma_\{\text{unused outcome}\}\ Z^L$, read in the (A, B, C) qubit order. A product of instruments gives such a pair: both families induce $M^A_\{x_A,c_A\} \otimes M^B_\{x_B,c_B\} \otimes M^C_\{x_C,c_C\}$. h16_liftAB_linkcheck.py checks this identity with random POVMs and random multipliers (agreement 3.6e-15) [NUMERICAL]. Since lift-A and lift-B each contain every instrument strategy (H.21.8, H.22.1), so does their intersection, and its value is at least the larger of the two.
- *Dual and certificate.* The dual adds Hermitian 8×8 multipliers $\Lambda_\{x,c\}$ for the linking equalities. The cost of family A becomes $C_v + K^A_v(\Lambda)$, the cost of family B becomes $-K^B_v(\Lambda)$, with $K^L_v(\Lambda) = \Sigma_\{x_L\}$ emb($\Lambda_\{x,c\}$, copy x_L)/2, and the rest is the dual of H.21.8 for each family. For any multipliers: $y_A \cdot P = \Sigma_L\ (\Sigma\ \mathrm{Tr}\ \Lambda^L + \Sigma_v\ \mathrm{Tr}[S^L_v\ Z^L_v])$, because the linking terms cancel on the intersection.
    - The model has 2,048 PSD blocks of size 16×16 and 559,104 real variables. It was assembled directly as a sparse SCS problem, because cvxpy did not finish compiling either the primal (h16_lift_AB.py, more than 35 min) or the dual (h16_liftAB_dual.py, more than 25 min at 6.7 GB). Both cvxpy runs were stopped.
    - SCS (eps 10^{-5}) gives dual value −1.16321 in 1,122 s.
    - Validation: run on family A alone, the same code reproduces the Round 14 lift-A value (−1.27717) and certifies −1.27820 with h16_liftAB_verify.py.
    - h16_liftAB_verify.py follows h12_lift_verify.py. It rounds every multiplier parameter to 2^{-30}, applies the twirl and linking maps exactly in integers, and certifies a lower eigenvalue bound for every block by Sylvester's criterion (Bareiss).
    - **Result [PROVED, exact integer certificate]:** min over all instruments of $y_A \cdot P \geq -7639159350592491 1/65536000000000000 \approx$ **−1.16564**.
- **Status.** The optimum of y_A over all instruments lies in **[−1.16564, −0.70580]** [PROVED both ends]. The gap shrinks from 0.4975 to 0.4598. The achievable side is unchanged (seesaw −0.70580, NUMERICAL as a value, PROVED as a strategy). Closing the gap remains **OPEN**. Still untried: adding the lift-C family (memory), PPT constraints on the lifts, and an eps 10^{-6} solve (the certified value loses about 0.0024 to the eps 10^{-5} eigenvalue slack).
- *Literature.* The construction is a hierarchy-style relaxation: copies of a party's system so that its incompatible measurements coexist, plus consistency constraints between different liftings. It is in the spirit of NPA and moment-matrix hierarchies (Navascués, Pironio, Acín 2007/2008) and of the SDP relaxations of instrument-based causal inequalities. We do not claim that the hierarchy converges [CITED for the method; INTERPRETIVE for the comparison].

H.23.4 Conjecture F.5.7: the countably controlled case [PROVED, paper; NUMERICAL sanity check]. Target 4 of Round 16. Proposition F.5.10 (Appendix F) extends F.5.9 from finitely to countably many cells. The closed loop $M = \Sigma_c \otimes_k P_{k,c_k}\ V_k\ S_{\omega_k(c)}$ converges strongly and is unitary for all local unitaries with ancillas, and grid discretisations adapted to the cells and translations converge strongly to it. The column identity M*M = 1 now has a short proof that needs no decomposition into deterministic functions: expectations in product states are classical stochastic local maps, the process-function property makes the expected fixed-point count 1, and polarisation in each tensor factor finishes the argument. Example [PROVED]: $w(o) = \omega(\lfloor o \rfloor)$ on $\mathbb{R}^3$, with ω Lugano on parities and unbounded odd translation amounts. It is non-causal, countably controlled and not finitely

controlled (`embed/f510_check.py`, 3,000 random local maps, always exactly one fixed point [NUMERICAL]). **Still OPEN:** non-causal w that is not countably controlled, e.g. continuous dependence on the outputs.

H.24 Round 17: uniform limits for F.5.7, rigidity of classically controlled boards, and the H.12 gap (Oct 24 2026) [labels as in H.21]

H.24.1 Conjecture F.5.7 beyond countable control: uniform limits give a canonical isometric closed loop [PROVED, paper; unitarity OPEN]. Target 3 of Round 17. Proposition F.5.11 (Appendix F) takes Euclidean output spaces and a measurable process function w that is a uniform limit of countably controlled process functions w_n. The F.5.10 unitaries M_n then converge strongly to an isometry M that does not depend on the approximating sequence. The key estimate is $\|(M_n - M_m)\psi\| \le (e^{N\varepsilon K} - 1)\|\psi\|$ for ψ band-limited to momenta in [−K, K], with $\varepsilon = \|w_n - w_m\|_\infty$ and N the total output dimension. It comes from a Taylor expansion of the translations: on the common refinement of the cells, the multiplication operators Δ(o)^α commute with the cell projections. M is unitary exactly when the adjoints $M_n^*\varphi$ stay tight in momentum. This is the remaining obstruction, and we have neither a proof nor a counterexample. Example [PROVED]: the Lugano pattern on the parities of the integer parts, with activated amounts given by arbitrary uniformly continuous functions of the other outputs. This is a non-causal process function, and it is not countably controlled when the amounts take uncountably many values. It is the uniform limit of its dyadic roundings, so F.5.11 applies. **Status:** F.5.7 is now reduced to the tightness question for this class. Process functions that are not uniform limits of countably controlled ones, for example with a jump set that no countable partition captures up to null sets, remain OPEN, as before. Literature: Giacomini, Castro-Ruiz and Brukner (2016) for continuous-variable process matrices. The analytic-vector estimate is standard.

H.24.2 The never-crossed orbits: classically controlled qubit boards are rigid [NUMERICAL; embed/h17_ctrl_boards.py/.log; the 10 orbits stay OPEN]. Target 2 of Round 17. H.23.1 showed that the generalised Lugano family is exhaustive among XOR boards. Here we test the next natural non-XOR family, *classically controlled boards*: $i_k = U_{k,\, o_{\{-k\}}}\, s_k$, where each party's qubit unitary depends on the other two outputs. Validity is the Araújo et al. projector penalty of H.23.1, and values around 1e-29 mean valid.

- Generic control, with four independent Haar unitaries per party: invalid in 3/3 draws (penalty 74 to 99).
- Control by the next party only: invalid in 3/3 draws (42 to 58).
- Two-valued Lugano routing, with one Haar unitary on the activated Lugano cell and another elsewhere: valid in 3/3 draws ($\approx 2\cdot10^{-29}$).
- Lugano routing with the inactive cells refined into distinct Haar unitaries, or even into distinct diagonal phases: invalid in 2/2 draws each (43 to 86).

So, within this family, validity seems to force the control to factor through the Lugano activation bit. The valid members are Lugano boards dressed with local unitaries, and H.23.1 already searched those (`never22_lugU_3_open10.log`) without crossing any of the 10 orbits 26, 28, 30, 31, 54, 57, 66, 69, 75, 81. This is evidence, not a proof. The sample is small, and the boards and the purification argument of H.23.1a were not combined into a proof that the orbits hold on Purif. **Status:** all 10 orbits remain OPEN. Neither a crossing nor a proof was found this round. Literature: the validity criterion is from Araújo, Feix, Navascués and Brukner (Quantum 1, 10, 2017). Classical control of local operations by a process function follows Baumeler and Wolf (2016).

H.24.3 The H.12 upper end: a massively multistart search does not beat −0.70580 [NUMERICAL; embed/h17_batch_search.py, h17_batch_search_s11.log, h17_batch_search_s12r1.log]. Target 1 of Round 17, achievable side. By H.15.7d every instrument strategy reduces to 4-outcome qubit POVMs $E_{a,o|x}$, so higher-dimensional instruments cannot help, and the search runs over exactly that set. `h17_batch_search.py` optimises batches of 1024 random POVM products with Adam: 1500 steps, learning rate 0.05 then 0.01, POVMs parametrised as normalised Gram products. As a check, it reproduces −0.7058021862 on the Round 14 seesaw optimum (h12_bound_warm_E.npy). Two runs were made:

- general rank, seed 11;
- rank-1 POVM elements, seed 12.

Each was stopped after 3 of 8 planned rounds, i.e. 3 × 1024 starts each, to free the CPU for the lift solve. Both reach exactly −0.705802 in every round, and nothing lower. The general-rank run also finds a second local optimum at −0.65969. The rank-1 run reaches −0.705802 from 0.7–1.7% of starts. The value is therefore very likely the true optimum of the instrument problem, but this is not proved: the interval for min $y_A \cdot P$ stays [−1.16564, −0.70580] unless H.24.4 improves the lower end. Literature: seesaw and multistart local optimisation for process-matrix and causal-inequality problems are standard (e.g. Branciard et al., New J. Phys. 18, 013008, 2016).

H.24.4 The H.12 lower end: the three-family intersection lift-A ∩ lift-B ∩ lift-C [set up; solve INCOMPLETE; no new certificate; embed/h17_lift_scs.py, h17_lift_verify.py, h17_lift_scs_ABC_partial.log]. *Update (Round 19, H.26.2): the solve finished and certifies −1.15861 exactly.* Target 1 of Round 17, relaxation side. `h17_lift_scs.py` generalises the direct sparse SCS assembly of H.23.3 to any set of lifted families. Each family other than A is tied to A by its own linking multiplier $\Lambda^L_\{x,c\}$: family A carries $+K^L$ for every link, and family L carries $-K^L$ for its own. The same weak-duality identity as in H.23.3 then holds, with the link terms cancelling pairwise on the intersection. The direct (LDL) solver would need about 10 GB, which would endanger the running glue_k4 job, so the run uses SCS's indirect (CG) solver at eps 10^{-5}. In about 50 minutes it reached only iteration 250. There the dual objective was ≈ 1.16, the same as the converged A ∩ B value 1.16564 to this precision, with primal and dual residuals $1.6 \cdot 10^{-4}$ and $7.1 \cdot 10^{-4}$ [NUMERICAL, unconverged]. The exact verifier `h17_lift_verify.py` adapts h16_liftAB_verify.py to the multi-link keys, but has not yet been run, since there is no converged solution to check. The job is left running under nohup and writes /tmp/r17/lift_ABC.pkl when it finishes. *Update (Round 19, H.26.2):* it finished, and the exact verifier certifies $y_A \geq -1.15861$. **Status: the certified interval stays [−1.16564, −0.70580] (H.23.3, H.24.3). Whether lift-C closes any of the gap is OPEN. The early iterates give no sign that it does.

H.24.5 Lean [not attempted this round]. Target 4 of Round 17. The finite combinatorial core of the F.5.10 column argument is the expected fixed-point count $\Sigma_s \prod_k q_k(w(s)_k, s_k) = 1$ for stochastic local maps q_k. It is already machine-checked as `PFUL.Column.sum_prod_eq_one` for finite alphabets, with the cell alphabet of F.5.9 as the special case. Not formalised: the countable-cell version, the polarisation step, F.5.11, and the sharp Russo–Dye constant (still CITED, H.23.2). All remain open for Lean.

H.25 Round 18: the H.12 optimum is a certified strict local minimum, unitary closed loops for activation-controlled w, the ABC lift (Oct 24 2026) [labels as in H.21]

H.25.1 Conjecture F.5.7: activation-controlled process functions [PROVED, paper]. Target 3 of Round 18. Proposition F.5.12 (Appendix F) covers process functions with three properties:

- in each product region of the output space, at most one party is active;
- the active party's own output is unconstrained;
- its translation amount is an arbitrary measurable function of the other outputs, while the inactive amounts are constant.

For such w, the closed loop M = Σ_R Π_R D_R (⊗_{j≠κ} V_j $S_{ω_j}$) is unitary for all local unitaries, where D_R is the decomposable operator with fibres V_κ $S_{h_R(o_\{-κ\})}$}. M is also the strong limit of countably controlled closed loops along any almost-everywhere approximation of the amounts.

- *Rows:* the Lugano-type exclusivity (E) makes the terms orthogonal.
- *Columns:* the projection onto a region commutes with D_R, so the amounts drop out of M*M entirely. M*M then equals the column sum of the skeleton (amounts set to 0), which is 1 by F.5.10.

The continuous-amount Lugano example of F.5.11 qualifies for **any** measurable amounts. There the column identity is the polynomial identity ẽ_B õ_C + ẽ_C õ_A + ẽ_A õ_B + ẽ_A ẽ_B ẽ_C + õ_A õ_B õ_C = 1 in commuting projections. So the momentum-tightness condition of F.5.11 (iii) holds in that example, and the canonical isometry is unitary. This also covers amounts that are discontinuous everywhere, which are not uniform limits.

Still OPEN: regions in which several parties' amounts vary, or in which the active party's own output is constrained. In particular, unitarity for general uniform limits, such as Lipschitz w, is still open. Literature: direct integrals and decomposable operators (Dixmier 1957; Reed–Simon IV). For coherent classical control of quantum operations by process functions, see Baumeler, Costa, Ralph, Wolf and Zych (2019) and Araújo et al. (2017).

H.25.2 The H.12 upper end: the −0.70580 strategy is an exact strict local minimum within its family, and block-optimal over all POVMs [critical point and value PROVED by interval Krawczyk test; strict local minimality PROVED (exact rational Sylvester test plus interval radius bound); block optimality NUMERICAL; global optimality OPEN; embed/h18_h12_local.py/.log]. Target 2 of Round 18.

Structure [NUMERICAL, then exact]. After polishing, both Round 17 searches give the same optimum up to relabelling, and it has a simple structure:

- Every party outputs its own setting, $o_k = x_k$.
- The bit a_k comes from a projective qubit measurement along a unit Bloch vector $n_{k,x}$.

On this family, $y_A \cdot P$ is a cubic polynomial f(n) = $Σ_x$ Σ_μ W_x[μ] ∏_k (1, n_{k,x_k})[μ_k] on $(S^2)^6$. Its coefficients are W_x[μ] = $d_{x,\mathrm{supp}\ μ}$·⟨ψ_{o(x)}|σ_μ|ψ_{o(x)}⟩, where d is the y-weighted sign sum over a.

Exact critical point [PROVED].

- Newton on the 24-variable Lagrange system g_i + λ_i n_i = 0, $|n_i|^2$ = 1, at 60 digits, converges quadratically (residual $5 \cdot 10^{-61}$).
- A Krawczyk test in interval arithmetic (mpmath.iv) shows that a box of radius 10^{-30} contains a unique exact critical point. The coefficients are widened by 10^{-55} to cover their 60-digit rounding.
- Its value lies in [−0.705802238872487294515238787953 7, −0.705802238872487294515238787897 7].

Second order [PROVED].

- The Lagrangian Hessian projected on the tangent spaces has eigenvalues 0.5347 to 2.664.
- Hp − 0.2673·1 is positive definite by an exact rational Sylvester test.
- The interval Hessian over the box has radius ≤ 10^{-30}, far below the margin.
- So this is a strict local minimum of $y_A \cdot P$ among strategies with deterministic outputs and projective qubit measurements.

Block optimality [NUMERICAL]. For each party and setting, the SDP over all 4-outcome POVMs with the other parties fixed improves the value by at most $4 \cdot 10^{-12}$. So no single party, in any one setting, can do better with any instrument.

Closed form [NUMERICAL, negative]. A 50-digit integer-relation search (PSLQ via mpmath.findpoly) finds no integer polynomial of degree ≤ 10 with coefficients ≤ 10^4 having this root, and no $\mathbb{Q}(\sqrt{2})$-linear form. The value is algebraic, as a critical value of a polynomial system with coefficients in $\mathbb{Q}(\sqrt{2})$, but apparently of high degree, unlike the $\mathbb{Q}(\sqrt{2})$ value of H.15.7d. The Bloch vectors look generic.

Status. −0.70580 is certified as an exact local optimum within the natural family, and as a Nash point over all instruments. Global optimality, i.e. closing [−1.16564, −0.70580], remains **OPEN**. A relaxation tight at −0.70580 is not in sight: the best lifted relaxation is at −1.16564 (H.24.4). *Update (Round 19): the three-family lift gives −1.15861 (H.26.2), and within the family a level-2 moment relaxation is tight (H.26.3).* Literature: the Krawczyk operator (Krawczyk 1969; Moore, Kearfott and Cloud, *Introduction to Interval Analysis*, 2009) and mpmath's interval arithmetic.

H.25.4 The never-crossed orbits: where a proof must come from, and entangling dressings of Lugano are invalid [validity-only obstruction PROVED (exact rational certificate; reproduces H.17.5 for the 10 open orbits); dressing family NUMERICAL; the 10 orbits stay OPEN; embed/h18_orbits_valid.py/.log, embed/h18_entangled_boards.py/.log]. Target 4 of Round 18.

- *Proof route tested: validity alone [PROVED, negative].* Suppose a proof that a representative facet holds on Purif used only that the process matrix is valid, for example an SDP certificate over mixed valid W with a positivity or validity dual. Such a proof would also cover diagonal W, whose statistics are exactly the classical valid processes, so it would prove the facet on the Baumeler–Wolf polytope Valid. h18_orbits_valid.py rules this out for each of the 10 orbits. It builds Valid from normalisation plus the 64 deterministic-intervention constraints $\Sigma_i\, p(i|f(i)) = 1$, minimises the representative facet (H.23.1a) by LP, and checks the minimiser exactly: it is a rational valid process, and its exact affine coordinates over 38 affinely independent PFs give the facet value from the integer facet values on PFs. For all 10 orbits the minimum relative value is exactly **−1/6**. This matches the H.17.5 validcert values; here it is recomputed independently, for the representatives. So any proof has to use purity, i.e. the rank-one (unitary-dilation) condition, in an essentially non-convex way. Two further facts point the same way. Valid ≠ conv(PF): Valid has 64 facets and 710,760 vertices. And the Lemma B factorisation (H.17.17) is a statement about Pauli boards, not about general unitaries. The natural "unitarity of the lift + Lemma B" route therefore reaches only boards already in the H.17 classification. We did not find a way to make it cover general Purif.

- *New non-XOR family: entangling dressings [NUMERICAL, negative].* Boards $|s\rangle_P|o\rangle \mapsto G\cdot(\otimes_k U_k^{\mathrm{lug_k(o)}})|s\rangle_I\,|o\rangle_F$, where G is a fixed entangling gate on the three input wires. Local gates G are absorbed into the frames already searched in H.23.1. The Araújo et al. validity penalty (h16_gen_search.penalty; ≈10^{-29} means valid) is as follows, over 3 draws each:

- G = 1 (control): $5–8·10^{-30}$, valid;
- G Haar on all three inputs: 26–46;
- G Haar on inputs A and B: 12–33;
- G random diagonal phases: 13–31;
- G = CZ on AB: 11–20;
- Lugano itself (U = X) with CZ_AB or Haar(4)_AB: 32–40.

Every entangling dressing tested is invalid. Even a diagonal (computational-basis) phase gate, which does not change the classical routing, destroys validity, because the parties can measure in rotated frames. Together with H.24.2 this suggests that within qubit boards the valid ones are, up to local frames, exactly the generalised Lugano boards already searched by H.23.1 (never22_lugU_3_open10.log, no crossing). This is evidence, not a theorem.

- *Status*. All 10 orbits (26, 28, 30, 31, 54, 57, 66, 69, 75, 81) remain **OPEN**. A proof must use purity non-convexly. The remaining crossing candidates lie beyond single-qubit-per-wire Lugano dressings, e.g. qudit wires or process functions with more than one active party per region. Literature: Baumeler and Wolf (New J. Phys. 18, 035014, 2016) for the classical polytope and its deterministic-intervention description; Araújo, Feix, Navascués and Brukner (Quantum 1, 10, 2017) for validity and the purification postulate.

H.26 Round 19: the four-term threshold is proved, the ABC lift raises the H.12 lower end, the H.12 strategy is optimal to within $2.7·10^{-4}$ in its family (Oct 24 2026) [labels as in H.21]

H.26.1 "Four terms per outcome is the minimum" [PROVED, exhaustive exact search, per-class-pair model; h17/glue_k4.py, glue_k4.log, glue_k4_done.jsonl]. Target 2 of Round 19. The four-class search of H.17.17, launched in Round 8 and run in the background since, has finished. All 2,722 canonical geometries are done (2,896,784 jobs), with 0 candidates and 0 UNRESOLVED jobs. Together with the class bound (at most four classes; H.17.17, also in Lean) and the ≤3-class closures (H.17.9, H.17.13–H.17.15), every admissible board with at most three Pauli terms per outcome is a PF blend. So four terms per outcome is the minimum for a board outside conv(PF). By H.13.2, four terms do suffice.

- *Audit of the completeness claim [PROVED by exhaustive check; h17/glue_k4_audit.py, glue_k4_audit.log].* The counts in the logs and the checkpoint need reading carefully:
  - The index g in glue_k4_done.jsonl is the **raw position** of a labelled geometry in glue_k4_tuples.json (21,906 entries, all distinct; rerunning glue_k4enum.py reproduces the file byte for byte). It is not an orbit id.
  - Independently recomputing the orbit key of all 21,906 geometries under cube translations × G_{48} gives exactly **2,722 orbits**. glue_k4_canon.json contains exactly one geometry from each orbit, and nothing else.
  - glue_k4_done.jsonl has 2,889 records with distinct g in 0..21,892: all **2,722 canonical geometries**, plus 167 non-canonical ones from the first run of the log ("21706 to do"), which started in raw order before the canonical filter. The restarts ("2541 to do", "2437 to do") are the canonical geometries still outstanding at each restart, and the final SUMMARY line counts only the last restart.
  - Every canonical geometry has a record, and no record (canonical or not) has a candidate or an UNRESOLVED job. Jobs over the canonical set total 2,896,784.
  - So the coverage is complete. Running one geometry per orbit suffices, because the symmetries are PROVED (H.17.15(d)).

- *Scope.* This holds in the per-class-pair model of H.17.13–H.17.16: supports of V_yV_x† are over-approximated by the H.17.12 pattern lists and filtered by Lemmas A–C, and the leaf test is the one in glue_k4.py. An over-approximation can only add jobs, so a clean run is sound for the model. Two things are not proved: that the model captures every admissible board without the pattern classification's hypotheses, and a formal (Lean) check of the enumeration.
- *Literature.* No comparable term-count threshold for purifiable processes is known to us. The Pauli-support viewpoint follows the stabiliser/Pauli-group literature (e.g. Gottesman 1997), and purifiability is from Araújo, Feix, Navascués and Brukner (2017).

H.26.1a How the exhaustive proof works, with a worked example (Oct 25 2026) [exposition of H.26.1; the statement is PROVED in the per-class-pair model; worked-example numbers are exact reruns; h17/glue_k4_example.py, glue_k4_example.log (g = 3424), glue_k4_example_37.log (g = 37), glue_k4_example_orbit.py/.log, glue_k4_repro.log]. This subsection explains why "0 candidates and 0 UNRESOLVED over 2,722 geometries" proves H.26.1. It says what is computed, what is exact, and what is assumed, and it walks through one geometry by hand.

(a) The statement and the model.

- **Statement [PROVED, per-class-pair model].** Every admissible board with at most three Pauli terms per outcome is a PF blend: $p_\varphi \in \mathrm{conv}(PF)$ for every source state φ. Since H.13.2 gives an admissible four-term board outside conv(PF), four terms per outcome is the minimum. *Wording note:* the search does not look for "three-term decompositions" of anything. It looks for a **counterexample**, a ≤3-term board that is not a PF blend, and shows there is none.

- **Boards.** $U_o = P_o\, V_{\kappa(o)}$ for the 8 outputs $o \in \{0,1\}^3$. P_o is a Pauli string (the left Pauli) and $V_{\kappa(o)}$ is a class operator of one of the three shapes of H.17.15(a): 1, $\alpha + i\beta A$, or $\alpha + i(\beta A + \gamma B)$ with A, B anticommuting.

- **What the search sees.** The search sees only *support data*:

  - (i) the class map $o \mapsto \kappa(o)$, and each class's label;
  - (ii) the seven left Paulis $P_1, \ldots, P_7$, with $P_0 = I$ (a common left Pauli changes nothing; H.17.17);
  - (iii) for each pair of classes $c \neq d$, the support S_{cd} of $V_d V_c^\dagger$.

  The real parameters α, β, γ are forgotten. Every test the proof uses is a function of these data alone: admissibility through the Pauli rule (H.8.1), hardness, and SH_grp^r through Lemma D.

- **The model.** "Per-class-pair" means that each S_{cd} may be any pattern on the H.17.12 list for its two labels, chosen independently for each pair, subject only to Lemmas A–C. H.17.12(b), (c) are PROVED, so the lists contain every support that real parameters can produce. They may also contain supports that no parameters produce (over-approximation). So every real board's data occur in some job, and extra jobs can only add work.

- **The proof, in four steps.** Suppose some board B in the model is not a PF blend.

  1. B is *hard*. Otherwise a W-level-last party (H.1) or an operator-first party (H.6.2) makes it a PF blend.
  2. SH_grp^r fails for **every** absorbed class r. If it held for one r, H.17.11a would make B a PF blend.

3. B has at most four classes, and ≤3 classes are closed (H.17.9, H.17.13–H.17.15). So B has exactly four classes, each on two vertices, and each non-identity class sits on an edge along its rigid direction (Theorem H.17.17, also in Lean).
4. The search shows that no four-class support data pass 1 and 2. This contradicts the assumption.

(b) From a large question to a finite list.

- **Why a reduction is needed.** The data space is finite but large. There are 1,072 labels per class, 64 Paulis for each of 7 vertices ($64^7 \approx 4.4 \cdot 10^{12}$), and several patterns per class pair.

- **Geometries.** Step 3 fixes the shape. A *labelled geometry* is a pairing of the 8 vertices into 4 classes (105 pairings), with a label for each class. It must satisfy the class bound and Lemmas A and B: across every class-changing edge along q, some admissible pattern of the two labels is q-constant. Vertex 0 carries a non-identity class whose label is a G_{48}-orbit representative. This gives 21,906 labelled geometries (glue_k4enum.py).

- **Symmetries.** The group Γ has 8 × 48 = 384 elements:

  - the cube translations $o \mapsto o \oplus t$, which relabel the outcomes of the parties in t;
  - G_{48}, which permutes the qubits by π and S-conjugates the qubits in a mask m. It acts on Pauli strings and, through π, on cube coordinates and differences D at the same time (H.17.15(b), (d)).

  Every $\gamma \in \Gamma$ maps admissible boards to admissible boards and PF blends to PF blends (H.17.15(d) [PROVED]). It also preserves hardness and the SH_grp tests, which are defined from the same supports, X-parts and differences D (a direct check from the definitions, argued here rather than machine-checked). γ preserves Pauli multiplication up to phase, so it maps the pattern list of (a, b) onto that of (γa, γb), and it maps the Lemma A–C filters onto themselves. Hence if a geometry $\Lambda' = \gamma\Lambda$, then γ is a bijection from the jobs of Λ to the jobs of Λ′ that carries counterexamples to counterexamples. **Every member of an orbit has the same answer**, so one geometry per orbit is enough.

- **Canonical representatives.** glue_k4canon.py applies all 384 elements of Γ to a geometry and renames the class ids in order of first appearance. The **orbit key** is the lexicographically smallest resulting tuple. The **canonical representative** of an orbit is its first geometry in enumeration order. There are 2,722 orbits, and glue_k4_canon.json lists their representatives (raw indices into glue_k4_tuples.json).

- **Empirical check of "same answer" [exact rerun] (glue_k4_example_orbit.log).** Running glue_k4.work on every member of two orbits, not just the representative, gives the same answer each time:

  - all 8 members of the orbit of g = 3424 give 1 job each, with 0 candidates and 0 UNRESOLVED;
  - all 24 members of the orbit of g = 37 give 3 jobs each, with 0 candidates and 0 UNRESOLVED;
  - the 167 non-canonical geometries from the first run are clean as well (H.26.1, audit).

(c) What one job checks, and why "0 and 0" is a proof.

- **A job.** A job is one canonical geometry together with one choice of S_{cd} for each of its 6 class pairs. The choices must survive Lemma A ($|S| \geq 2$), Lemma B (a pair adjacent along q has a q-constant support), Lemma C (triple consistency: $S_{ab} \subseteq S_{ac} \cdot S_{bc}$ and cyclically) and the exact K = K′ list of H.17.12(b).

- **Unknowns and constraints.** The unknowns are $P_1, \ldots, P_7$. Each ranges over the 64 Pauli strings, encoded as 6-bit integers s = x + 8z. For every ordered pair u ≠ w the board must obey the Pauli rule: no string of $P_u \oplus P_w \oplus S_{\kappa(u)\kappa(w)}$ may be non-identity on every party of D = u ⊕ w. This is a 64 × 64 Boolean table for each pair.

- **Solver steps.** One job is solved in four steps:

    1. **Quick exit.** Run arc consistency on the Pauli rule alone. If some domain becomes empty, the job has no admissible board and is closed.
    2. **Root.** Any counterexample fails SH_grp^r for r = κ(0) at some pair (u_0, w_0) (step 2 of (a)). So the solver loops over the 28 pairs. For each pair it adds the Lemma D failure condition, which is a Boolean function of $x(P_{u0} \oplus P_{w0})$, as one more constraint. A counterexample is found under at least one of its failing pairs.
    3. **Search.** Arc consistency deletes a value only if it has no compatible value in some other domain, so it never deletes part of a complete solution. A depth-first search then fixes the vertex with the smallest domain, tries every remaining value, and re-runs arc consistency. Every complete assignment satisfying all constraints is reached; these are the leaves.
    4. **Leaf test.** At a leaf the solver discards the board if it is non-hard (W-level-last or operator-first party), or if SH_grp^r **holds** for some class r (Lemma D for all four classes). Both outcomes are PF blends.

- **Candidates and UNRESOLVED.** A *candidate* is a leaf that survives the leaf test. A job is *UNRESOLVED* if its DFS exceeds the node budget (BUDGET = 2,000,000 nodes, summed over the job's roots) before it finishes.

- **Why "0 and 0" is a proof.** A job with no candidate that is not UNRESOLVED has had its whole search space covered. So no counterexample has that job's data. If this holds for every job of every canonical geometry, then by (a) and (b) no counterexample exists in the model.

- **Exact or floating point? [exact; honest accounting].** Every step of glue_k4enum.py, glue_k4canon.py, glue_k4.py, glue_k4_audit.py and glue_k4_example.py is integer or Boolean arithmetic:

    - Pauli strings are bit vectors, and products up to phase are XORs;
    - the Pauli rule test is a bitwise AND;
    - the affine hulls of Lemma D are computed over F_2;
    - the numpy arrays are Boolean.

    There is no floating point and no tolerance anywhere in the proof chain. Phases and real parameters enter only through which supports are possible, and that was settled earlier: H.17.12(b) analytically, and H.17.12(c) by an exact enumeration with exact Pauli phases ±1, ±i. Floating point does appear in the H.17 numerics: the board searches, the NUMERICAL Lemma D cross-check on saved boards, and the facet checks a candidate would have needed. None of these is used by the proof.

- **What the computation relies on.** It relies on the correctness of the code, which is not formally verified, unlike the class bound (Lean). The mitigations are:

    - the independent audit (d);
    - the LOOSEN control, which shows the search does find hard boards when they exist;

- the brute-force cross-check of the worked example (e);
- the orbit-member reruns (b);
- byte-identical re-enumeration (f).

(d) Completeness: raw versus canonical indices.

- **The possible confusion.** The search processes the 2,722 canonical geometries, but its checkpoint glue_k4_done.jsonl records each geometry by its **raw** index g, its position among the 21,906 entries of glue_k4_tuples.json. The log also prints "geometries N to do" at each restart: 21,706 at the first run, which started in raw order before the canonical filter existed, then 2,541 and 2,437 at restarts with the filter. The final SUMMARY counts only the last restart: 2,437 geometries and 2,719,567 jobs in 57,025 s on 3 cores. So no single log line says "2,722".

- **The resolution [PROVED by exhaustive check] (glue_k4_audit.py, glue_k4_audit.log).** The audit:

  - recomputes the orbit key of all 21,906 geometries, with its own key and bookkeeping code but the same group code (G, cls_act, pbits of t3sym.py);
  - finds exactly 2,722 orbits, with exactly one canonical entry in each;
  - finds a done record for 2,722 of the 2,722 canonical geometries, totalling 2,896,784 jobs, with no record (of 2,889, including 167 non-canonical) having a candidate or an UNRESOLVED job.

  The 167 non-canonical records are extra, not missing coverage.

(e) Worked example: geometry g = 3424 [exact rerun] (glue_k4_example.log).

- **The data.** glue_k4_tuples.json entry 3424 is cls = [[1, 8], [], [4, 32], [2, 16]], with pairing [(0,1), (2,5), (3,7), (4,6)]. In words, writing qubits as A B C and vertices as bit strings o_A o_B o_C:

class	vertices	edge	label	operator
0	000, 100	e_A	(XII, ZII)	α + i(β XII + γ ZII)
1	010, 101	none (identity class; need not be an edge)	()	1
2	110, 111	e_C	(IIX, IIZ)	α′ + i(β′ IIX + γ′ IIZ)
3	001, 011	e_B	(IXI, IZI)	α″ + i(β″ IXI + γ″ IZI)

  Each non-identity class acts on a single qubit, and sits on the edge along that qubit's direction (Lemma H).

- **Canonicalisation.** The orbit of this geometry under Γ meets the enumeration in 8 labelled geometries: 3424, 3430, 3598, 3604, 4576, 4582, 6205 and 6211. All 8 have the same orbit key. 3424 comes first in enumeration order, so it is the canonical representative, and the only one in glue_k4_canon.json.

- **Its single job.** Each class pair has only one admissible pattern, so the geometry spawns exactly **1 job**:

  - S_{01} = {III, XII, ZII} (V_1V_0† = V_0†);
  - S_{13} = {III, IXI, IZI} and S_{12} = {III, IIX, IIZ}, likewise;
  - S_{02}, S_{03} and S_{23} are 9-string product supports such as S_{03} = {III, XII, ZII, IXI, IZI, XXI, XZI, ZXI, ZZI}. Their Klein groups meet only in 1, so no cancellation is possible (H.17.12(a)).

- **The solver on this job:**

    - After plain arc consistency the domain sizes of P_0, …, P_7 are [1, 1, 4, 16, 16, 4, 16, 16].
    - For r = class 0, the Lemma D failure condition is possible at 24 of the 28 root pairs. Arc consistency empties 16 of them. The DFS searches the other 8: (2,3), (2,7), (3,4), (3,6), (4,5), (4,7), (5,6) and (6,7).
    - The search uses 1,368 DFS nodes and reaches 512 leaves, far below the budget.
    - **All 512 leaves are rejected because SH_grp^r holds for r = class 1 (the identity class)**, so each is a PF blend by H.17.11a. None is rejected for non-hardness.
    - The instrumented solver is a line-by-line copy of glue_k4.solve with counters, and its verdict is asserted equal to glue_k4.solve's. The checkpoint record is {'g': 3424, 'jobs': 1, 'cand': [], 'unres': 0}.

- **Brute-force cross-check [exact; independent of arc consistency and of the root logic, though it uses the same Pauli-rule tables and Lemma D formula].** Enumerating all P_1, …, P_7 directly gives exactly **64 admissible boards**, all of them hard. Each fails SH_grp^r for classes 0, 2 and 3, at 8 pairs each, and passes it for class 1. The two counts agree: 512 = 8 roots × 64 boards, because each board fails the class-0 test at all 8 searched root pairs.

- **Why the identity class rescues these boards.** Take the board with all P_o = I. Absorbing class 1 (V = 1) leaves W_o = V_κ(o), so Aff_o is spanned by the X-parts of the class's own strings: A for class 0, C for class 2, B for class 3. Each class sits on the edge along its own qubit. For every pair of vertices in different classes, D = o ⊕ q contains a qubit that neither class touches (checked for all 24 such pairs), so no vector of Aff_o ⊕ Aff_q covers D, and SH_grp^1 holds. Absorbing class 0 instead, the ratios V_κ(o)V_0† have the larger 9-string supports, and the test fails at 8 pairs. *The choice of absorbed class matters, which is why the leaf asks for failure for every r.*

- **The search is not vacuous here.** The LOOSEN = 1 control on this job (leaf = any hard admissible board) finds one immediately, all P_o = I. These hard boards are excluded by the SH test, not by an empty search space.

- **A contrast, g = 37 (glue_k4_example_37.log).** Classes (XII) on {000, 100}, identity on {010, 110}, (IXI) on {001, 011}, and (IXI, IZI) on {101, 111}.

    - This geometry spawns 3 jobs (S_{23} ∈ {III, IXI, IZI, IYI}, {IXI, IZI, IYI}, {III, IZI, IYI}).
    - Each job has 256 admissible boards (brute force) and reaches 1,024 = 4 × 256 leaves.
    - Every leaf is discarded because **party C is operator-first**: no class acts on qubit C. So this geometry is closed by H.6.2, not by SH_grp. The LOOSEN control finds 0 hard boards.

- **Four terms, by contrast.** The H.13.2 board, which is not a PF blend (certificate facet 16962), cannot be written in this model at all: its outcome unitaries have four Pauli terms, so they are not of the shapes in (a). The threshold sits exactly at the boundary of the model's shapes.

(f) How to reproduce [exact; box timings].

- **Commands.** Run from code/stochastic/cyclic/switchboard/h17, with Python 3 and numpy:

    - `python3 glue_adj.py` writes /tmp/glue_adj.pkl (rigid sets and neighbour lists);
    - `python3 glue_k4enum.py` writes glue_k4_tuples.json;
    - `python3 glue_k4canon.py` writes glue_k4_canon.json.

These three take about 166 s in total on one core. A fresh scratch rerun reproduces all three outputs byte for byte (glue_k4_repro.log).

- **The search.** `NPROC=3 nohup nice -n 5 python3 glue_k4.py >> glue_k4.log 2>&1 &` is resumable from glue_k4_done.jsonl. The last segment, 2,437 geometries, took 57,025 s (about 15.8 h) on 3 cores. Earlier segments covered the rest.
- **Checks.**
  - `python3 glue_k4_audit.py` takes about 30 s.
  - `python3 glue_k4_example.py 3424` (and `… 37`) takes about 30 s, mostly spent recomputing orbit keys.
  - `python3 glue_k4_example_orbit.py` takes about 65 s.
- **sha256 of the inputs and outputs:**
  - glue_k4_tuples.json 9accd2a0…a2650;
  - glue_k4_canon.json 69f0f830…93b64;
  - glue_k4_done.jsonl cac852c2…7794f;
  - glue_k4.log 8fe7a885…cbd7;
  - glue_k4_audit.log 9d72fce7…83fa;
  - /tmp/glue_adj.pkl e0595bed…2ace;
  - glue_k4.py 46a6b430…a78d.

  The full hashes are in glue_k4_repro.log and in the commit history.

(g) What the result does not say.

- **Scope.** It is PROVED in the per-class-pair model only. Two things are assumed, not proved here:
  - that every ≤3-term outcome unitary of an admissible board has one of the three shapes with the H.17.12 pair supports (the model's hypotheses);
  - that the code is correct; it is not formally verified, and only the class bound and Lemma H are in Lean.
- **It is about boards.** It says nothing about non-Switchboard processes, about more than three parties, or about H.12's causal-inequality value.
- **Labels.** Labels as in H.21:
  - the class bound and the symmetries are PROVED (paper, and Lean for the class bound);
  - the enumeration, canonicalisation, search and audit are PROVED by exact computation;
  - the worked-example counts are exact reruns;
  - the cross-checks of H.17.12(d) and Lemma D on saved boards are NUMERICAL and are not used.
- **Literature.**
  - Exhaustive computer proofs that combine a symmetry reduction with a complete, budgeted search and an independent audit are a standard pattern; the four-colour theorem (Appel and Haken 1977; Robertson, Sanders, Seymour and Thomas 1997) is the classic example.
  - Arc consistency is from constraint satisfaction (Mackworth 1977).
  - We claim only this application.

H.26.2 The H.12 lower end: lift-A ∩ lift-B ∩ lift-C certifies $y_A \geq -1.15861$ [lower bound PROVED, exact integer certificate; solver values NUMERICAL; embed/h17_lift_scs.py, h17_lift_verify.py, h17_lift_scs_ABC.log, h17_lift_verify_ABC.log]. Target 1 of Round 19, completing H.24.4. The three-family solve, started in Round 17 with SCS's indirect solver at eps 10^{-5}, finished as "solved" after 9,067 s (about 1,000 iterations; residuals $2.8\cdot10^{-5}$ and $1.8\cdot10^{-5}$ at iteration 750). Its primal objective was −1.155758, and the float dual bound, with eigenvalue deficits subtracted, was −1.1586026.

- *Exact verification [PROVED].* h17_lift_verify.py rounds every multiplier to the dyadic grid 2^{-30}, applies all maps exactly in integers, and certifies each cone shift by Bareiss–Sylvester, as in H.23.3. The family contributions are +1.391271 (A), −1.632892 (B) and −0.916989 (C). Result: **min over all instruments of $y_A \cdot P \geq -15186122631849044 7/131072000000000000 \approx -1.1586092$**.
- **Status.** The optimum of y_A over all instruments lies in **[−1.15861, −0.70580]** [PROVED both ends]. The gap shrinks from 0.4598 to 0.4528. Adding the third family gains only 0.0070, against 0.038 for the second (H.23.3). So the lift-family hierarchy seems to saturate far from −0.70580: one more copied party per family will not close the gap. A relaxation that sees the rank-one (projective) structure of the optimum, as in H.26.3, is needed.

H.26.3 The H.12 upper end: within the deterministic-output projective family, nothing beats −0.70607, and −0.70580 is attained [family bound PROVED for all 64 output patterns by exact SOS certificates; level-2 tightness NUMERICAL; optimality over all instruments OPEN; embed/h19_h12_lasserre.py/.log, h19_h12_sos_cert.py, h19_h12_sos_cert_21.log, h19_h12_sos_cert_41.log, h19_h12_sos_cert_patterns.log, h19_h12_sos_cert_patterns_full.log]. Target 3 of Round 19.

- *Cost of interval branch-and-bound [estimate, not run].* On $(S^2)^6$ f is affine in each $n_{k,x}$ separately, so one party's two vectors can be minimised in closed form ($c - |g_0| - |g_1|$). That leaves 8 angles. To separate −0.70580 from the next local optimum (−0.65969) with first-order interval bounds needs boxes of width about 10^{-2}, i.e. about $(2\pi/10^{-2})^8 \approx 10^{22}$ boxes. This is infeasible on the box, so a moment relaxation was used instead.

- *Family.* Deterministic outputs $o_{k,x}$ (64 patterns O), with projective a-measurements along unit vectors $n_{k,x}$. By multilinearity this also covers outputs drawn at random independently of the qubit, with the measurement chosen per output. For each O, f_O is a cubic in 18 variables on $(S^2)^6$.

- *Level-2 moment relaxation [NUMERICAL].* The relaxation has a 190×190 moment matrix (monomials of degree ≤ 2) and the sphere equalities localised up to degree 4, solved with SCS. Results:

  - The two smallest bounds are −0.7058023, for patterns 21 (o = x for every party, the H.25.2 optimum) and 41 (its mirror image).
  - Next is −0.6596879 (patterns 22 and 42), which matches the second local optimum −0.65969 found by the Round 17 search.
  - All other patterns are ≥ −0.5681.

  So the relaxation is numerically tight at both known local optima.

- *Exact certificates [PROVED for the patterns listed in the log].* h19_h12_sos_cert.py solves the dual, $f_O - \lambda = m^T G m + \Sigma_i\, h_i(|n_i|^2 - 1)$ with $G \succeq \varepsilon\cdot 1$. It rounds the coefficients of f_O, which lie in $\mathbb{Q}(\sqrt{2})$, to rationals with total error ≤ $2\cdot10^{-29}$, rounds G and h to dyadics, and moves the coefficient residual exactly into G. It then

proves G − (ε/4)·1 positive definite by integer Bareiss elimination. Patterns 21 and 41 were run with ε = 10^{-5}, and **each gives min f ≥ −0.7060707**, against the achieved −0.7058022 (H.25.2). The other 62 patterns were run with ε = $2\cdot10^{-4}$ and are all certified; the smallest of their bounds is −0.6650886 (patterns 22 and 42). Every one of the 64 certificates passed both exact checks (identity and positive definiteness); see h19_h12_sos_cert_patterns.log.

- **What is proved [PROVED].** Let $\mathscr{F}$ be the set of strategies in which every party k, for each setting x, emits an output $o_{k,x}$ determined by x, and obtains a by a two-outcome qubit POVM $E_{a|k,x} = (1 + (-1)^a n_{k,x}\cdot\sigma)/2$ with $|n_{k,x}| \le 1$. That is, the POVM is projective or unsharp, but unbiased (Tr E_a = 1). All 64 output patterns are included. Because $y_A\cdot P$ is affine in each $n_{k,x}$ separately, the minimum over the balls equals the minimum over the spheres, which is the certified one. By the same multilinearity, the bound also covers every convex mixture of such strategies per party and setting, e.g. outputs drawn at random independently of the qubit. On $\mathscr{F}$, **min $y_A\cdot P \in [-0.7060707, -0.7058022]$**: the lower end comes from the SOS certificates and the upper end from the explicit H.25.2 strategy. Numerically (level-2 values) the minimum on $\mathscr{F}$ is −0.70580 exactly, attained only at patterns 21 and 41, and the runner-up is −0.65969.

- **What is not proved.** This is **not** global optimality over all instruments. Optimality over **all** instruments stays **OPEN**. By H.15.7d every strategy reduces to 4-outcome qubit POVMs $E_{a,o|k,x}$, and $\mathscr{F}$ misses three kinds of them:

  - biased two-outcome a-measurements, including the trivial one a = const;
  - POVMs whose output o is correlated with the qubit outcome (e.g. o = a);
  - rank-one 3- and 4-outcome POVMs.

  Treating the first two kinds as output labelings of a projective measurement already gives $16^6 \approx 1.7\cdot10^7$ polynomial systems, and the third needs a relaxation in about 96 variables. Neither was attempted. Block optimality over all POVMs at the H.25.2 point is NUMERICAL only (H.25.2). The interval over all instruments remains [−1.15861, −0.70580] (H.26.2). Literature: Lasserre (SIAM J. Optim. 11, 796, 2001); Parrilo (Math. Program. 96, 293, 2003); exact rounding of SOS certificates as in Peyrl and Parrilo (Theor. Comput. Sci. 409, 269, 2008).

H.27 Round 20: the ten open orbits against PF-wired quantum boxes (Oct 25 2026). The target is the ten facet orbits of conv(PF) that no pure process has yet been shown to violate: 26, 28, 30, 31, 54, 57, 66, 69, 75 and 81, which together contain 1,536 facets. Each orbit's representative facet reaches exactly −1/6 on Valid (H.25.4), so any crossing, and any proof that the facet holds on Purif, must use purity. H.27.1 proves that a large, explicitly purifiable family never crosses these orbits: every forward PF lift, in any dimension, with any node unitaries, frames and source. H.27.2 reports a numerical search over the time-reversed counterpart of that family, which is the family that crossed the other twelve orbits in H.22.2. The orbits stay open.

H.27.1 Forward PF lifts are PF-wired quantum boxes, and no PF-wired no-signalling box crosses the ten open orbits [reduction PROVED; certificate PROVED, exact rational LP duals; whole-hull statement NUMERICAL; embed/h20_common.py, h20_fwd_enum.py/.json/.log, h20_fwd_ns.py/.log, h20_fwd_cert.py/.log, h20_fwd_cert_all.py/.log, h20_fwd_ns_all.py/.log].

- *The family (defined here).* A **forward PF lift** starts from a process function $w: \prod_k A_k \to \prod_k X_k$ on finite alphabets. It is the board $V|s\rangle_P|a\rangle_{AO} = (\bigotimes_k U_{k,w_k(a)})|s\rangle_{AI} \otimes |a\rangle_F$. Each node wire AI_k may have any finite

dimension, $U_{k,x}$ are arbitrary unitaries on it, the source ρ on P is arbitrary, and the agents act as everywhere in this paper: agent k measures its input with any POVM $\{M\hat{}k_{i_k}\}$ (outcome $i_k \in \{0,1\}$) and prepares a state σ_k(o_k) on its output wire for the classical output $o_k \in \{0,1\}$. The family contains the Lugano purification L, every *untransposed* generalised Lugano board L_U of H.22.2 in every frame, the translation lift of every PF (Section 1, Appendix F), and their controlled-unitary dressings.

- *Every statistic of the family lies in Purif [PROVED].* Give each agent an extra input register X_k, and feed it from the translation lift $|e\rangle|a\rangle \mapsto |e + w(a))_X|a\rangle_F$ with source $|0\rangle$. That lift is a valid pure process (Section 1, Appendix A; F.1–F.3 for group alphabets). Inside its own laboratory, agent k first applies the controlled unitary $\Sigma_x |x\rangle\langle x|_{X_k} \otimes U_{k,x}$ to (X_k, AI_k), then runs its instrument on AI_k and ignores X_k. That is a local operation, so the result is again a quantum process with a purification. Its statistics equal those of V, because F already records a, so X_k carries no coherence that the agent could use.
- **Lemma H.27.1a (reduction to PF-wired boxes) [PROVED].** Because F records a, the statistics of a forward PF lift are $p(i|o) = \Sigma_a\, q(a|o)\, P_Q(i \mid w(a))$. Here $q(a|o) = \prod_k \langle a_k|\sigma_k(o_k)|a_k\rangle$ is local stochastic pre-processing, and $P_Q(i|x) = \mathrm{Tr}[\rho \otimes_k U_{k,x_k}\dagger\, M\hat{}k_{i_k}\, U_{k,x_k}]$ is a tripartite **quantum box** with settings x_k. For a fixed box, a facet value is multilinear in (q_A, q_B, q_C), so its minimum is attained at deterministic q_k, $a_k = h_k(o_k)$. Then $p(i|o) = P_Q(i \mid w'(o))$ with $w' = w \circ h$, a **refined process function**: binary outputs, setting $x_k = w'_k(o_{-k})$, such that every local 2-colouring g of the settings makes $g \circ w'$ a binary PF, which it is because a PF composed with local maps is a PF. Only the partition of the four values of o_{-k} into the fibres of w'_k matters, since the setting labels can be absorbed into the box. An exhaustive enumeration of partition triples (h20_fwd_enum.log) gives **186 refined PFs, 20 of them maximal**, meaning not a coarsening of another. A box on coarser settings is a box on finer settings that ignores the distinction, so the 20 maximal ones suffice. Eight have block counts (2,2,2): these are the Lugano function up to relabellings. The other twelve have a party with a single block, which acts first.
- **Theorem H.27.1 [PROVED; exact rational arithmetic].** For every one of the 20 maximal refined PFs w′, every **no-signalling** box P(i|x) (binary outcomes, settings = blocks), and every facet of orbits 26, 28, 30, 31, 54, 57, 66, 69, 75 and 81, the classical process P(i|w′(o)) satisfies the facet. Hence **no forward PF lift crosses any of the ten open orbits**, and neither does any mixture of forward PF lifts. This holds for every PF on any finite alphabets, every dimension, every node unitary, every frame and every source.
  - *Proof (h20_fwd_cert_all.py).* Write g(P) for the facet value of $P \circ w'$. It is affine in P. The NS polytope's affine hull is spanned by the local deterministic boxes D, and each $D \circ w'$ is a PF. So g is the unique affine function on the NS space that takes the integer facet value of the PF $D \circ w'$ at D, and its coefficients c, c_0 are solved exactly in rationals. HiGHS minimises $c \cdot P$ over the NS polytope and returns a support and a float dual. The script then solves $A_Z{}^T\, y = c_Z$ exactly on the support Z, verifies in Fraction arithmetic that every reduced cost $c - A^T y$ is ≥ 0, and checks that $b \cdot y + c_0$ equals the minimum over local boxes (0 or 1 in integer facet units). Then $g(P) \geq b \cdot y + c_0 \geq 0$ for every NS box. All 20 × 10 (refined PF, representative facet) pairs pass ("ALL 20 x 10 CERTIFIED"; h20_fwd_cert.log repeats the check for the eight Lugano-type PFs). Party permutations and bit flips map refined PFs to refined PFs and boxes to boxes, so the family is invariant under the 384-element group and one facet per orbit covers all 1,536 (H.23.1a).
  - *The NS minimum equals the local minimum in every case.* So within forward PF lifts, quantumness of the box, and even post-quantum no-signalling correlations, buy nothing on these orbits.
- *Whole hull [NUMERICAL].* For the eight Lugano-type refined PFs, a float LP over all 29,344 facets gives an NS minimum $\geq -4.5 \cdot 10^{-15}$ (h20_fwd_ns_all.log). Numerically, then, Lugano-wired no-signalling boxes

never leave conv(PF). The twelve single-block PFs give causally wired boxes, which are expected to be causal and hence PF blends; that was not computed for all facets. This is consistent with H.15.8: H.12's time reverse, a frame-rotated *forward* √X-Lugano board, stays inside conv(PF), while H.12 itself, a time-reversed board, does not.

- *Reading [INTERPRETIVE].* Every crossing of conv(PF) by a pure process in this paper (H.12, H.13.2, H.22.2) uses a time-reversed or frame-rotated time-reversed Lugano-type board. H.27.1 explains half of this: forward PF wiring of any box, quantum or not, cannot cross the ten open orbits, and numerically cannot cross any facet. Whatever crosses them, if anything does, must use coherence in the agents' inputs that is not recorded in F.

*H.27.2 Time-reversed PF lifts with qudit node wires: no crossing found [family purity PROVED with the CITED time-reversal step; search NUMERICAL; embed/h20_trev_search.py, h20_trev_validate.log, h20_trev_open_*.log, h20_trev_summary.py/.log, h20_trev_best.npz].**

- *The family.* Take a forward lift of a maximal refined PF w′ as in H.27.1, with binary output wires, node wires of dimension D_k and node unitaries $U_{k,x}$, and reverse it in time (V^T). The agents now read the binary old-output wire in an SU(2) frame e_k (outcome i_k), and write a state $\varphi_k(o_k)$ on the old node wire. The source ψ lives on the 8-dimensional old F. The statistics are $p(i|o) = \psi^\dagger G_{io}\, \psi$ with $G_{io}[a,b] = \prod_k \mathrm{conj}(e_k(i_k)_\{a_k\})\, e_k(i_k)_\{b_k\}\, \langle U_{k,w'_k(a)}\, \varphi_k(o_k),\, U_{k,w'_k(b)}\, \varphi_k(o_k)\rangle$. Equivalently, the outputs o choose a Schur-product (dephasing) channel $\rho \mapsto \rho \circ K_o$ on a shared three-qubit state, where K_o is a correlation matrix built from the Gram matrices of the vectors $U_{k,x}\, \varphi_k(o)$. The agents then measure their qubits in fixed frames. $D_k = 2n_k$, with n_k the number of blocks, loses no generality: any Gram matrix of the $2n_k$ vectors $U_{k,x}\varphi_k(o)$ is realised in that dimension. Projective measurements suffice: a trivial measurement makes that party first, and the remaining two-party process is a PF blend (Appendix G).
- *Purity.* A refined PF is a PF with non-binary inputs: for any local intervention, the composite is a binary PF and so has a unique fixed point. Its forward lift is therefore a valid pure process (Section 1, Appendix A, plus the controlled-unitary step of H.27.1), and so is its time reverse (Guérin–Brukner 2018, App. D [CITED]; as in H.22.2).
- *Search.* We used L-BFGS (torch, float64) on the Rayleigh quotient $\psi^\dagger M\psi / \psi^\dagger\psi$, jointly in ψ and the board, with $M = \Sigma\, T_f\, G + c_f\, 1$ for the orbit's representative facet f. We reported the exact minimum over ψ, the smallest eigenvalue, at the end. Each (refined PF, orbit) pair got 300 random starts at three scales. Minimising the smallest eigenvalue directly was unreliable: it stalls on the 0 plateau of classical-like boards and missed orbit 14 entirely in 480 starts (h20_trev_validate2.log, h20_trev_validate3.log).
- *Validation on the crossed orbits [NUMERICAL].* The search finds the crossings that are already known.
  - With the eigenvalue objective (all 20 refined PFs, 10 starts each; h20_trev_validate.log, an earlier representative-facet version of the script), it crosses orbits 4–11 at relative value −0.0339663.
  - With the Rayleigh objective and 300 starts (h20_trev_validate4.log), it reaches −0.0464717 on orbits 14 and 25, H.22.2's optimum exactly (Lugano-type w′ = index 10), −0.0154744 on orbit 53 (H.22.2 certified −0.0154741) and −0.0098036 on orbit 79 (H.22.2 certified −0.0067548).
  - The larger per-facet values on orbits 4–11 and 79 do not contradict H.22.2, whose boards were optimised jointly over several orbits. They are float optima and are not certified. On orbits 4–11 the value −0.0339663 is a per-facet optimum found with qudit node wires ($D_k = 4$). Whether qubit node wires reach it was not tested; the QD=2 switch exists in the script but was not run.
- **Result on the ten open orbits [NUMERICAL, negative].** Searches finished for 8 of the 20 maximal refined PFs: the Lugano-type indices 4, 5, 7, 10, 11 and the single-block indices 12, 13, 16

(h20_trev_open_*.log, h20_trev_summary.log), with 300 starts per (refined PF, orbit). The runs for Lugano-type indices 6, 14, 15 and for the remaining nine single-block indices were stopped before finishing, so they are **not** covered. On every completed pair the best relative value is 0 to the 10^{-8} rounding of the log: the representative facet is reached (tight) but never crossed. On the single-block PFs, orbits 54, 57 and 75 do not even reach 0 (best value 1/3). **No time-reversed PF lift in this search crosses any of the ten orbits.** *Update (Round 21, H.28):* the completed search on all 20 refined PFs crosses orbit 26 (w' = index 6, 1 of 300 starts), and the phase-board subfamily crosses orbits 26, 30 and 31, all exactly certified (Theorem H.28.1). The general search missed orbits 30 and 31. Because only five of the eight Lugano-type variants were run, the representative-facet search does not yet cover every facet of each orbit up to symmetry.

- *Caveats.* These are local searches with random starts, and the validation shows that hits can be rare: orbit 14 needed about 300 starts. A negative result therefore bounds what this optimiser finds, not what the family contains. The family does not include agent instruments whose prepared state depends on the measured outcome, nor boards that are not PF-controlled, nor mixtures of forward and time-reversed wiring on different parties.

H.27.3 Status of the ten orbits after Round 20 [summary; labels as stated; superseded by H.28.3: orbits 26, 30, 31 are now crossed].

- *Crossed with certificate:* none.
- *Bound proved:* for all ten orbits, a **partial** result. Every facet holds on the forward-PF-lift family and its convex hull (Theorem H.27.1, PROVED). This is not a proof that the facets hold on all of Purif, which stays **OPEN**.
- *Numerical best value:* all ten orbits: best value found 0 (tight, not crossed) on time-reversed PF lifts (H.27.2, 8 of 20 refined PFs completed), and provably ≥ 0 on forward PF lifts (H.27.1). Untouched: none, but the coverage of H.27.2 is partial.
- *Not attempted this round:* an NPA-type quantum bound, which is moot because the NS bound already closes the forward family; a purity-based SDP/SOS relaxation of all of Purif; and perturbative searches around the $-1/6$ point of Valid.
- *What would close an orbit.* A crossing would need a time-reversed, or otherwise not-F-recorded, board beyond H.27.2's search. A proof of validity on Purif would need an argument covering time-reversed lifts. By H.22.2 such an argument must distinguish these ten orbits from the twelve that time-reversed Lugano does cross.

H.28 Round 21: orbits 26, 30 and 31 are crossed by PF phase boards; seven orbits remain open (Oct 26 2026). Round 21 targeted the ten open orbits of H.27. Three of them are now crossed, each with an exact certificate checked by two independent programs: orbits 26, 30 and 31. That makes **15 of the 22 genuine never-crossed orbits crossed** (twelve in H.22.2 plus these three). The seven still open are 28, 54, 57, 66, 69, 75 and 81, which hold 960 facets. All crossings come from one simple subfamily of the time-reversed PF lifts of H.27.2, the *PF phase boards* defined in H.28.1.

H.28.1 PF phase boards cross orbits 26, 30 and 31 [crossing PROVED, exact Gaussian-rational certificates from two independent checkers; purity PROVED for the certified boards by an exact validity check, and for the whole family by H.27.2 with the CITED time-reversal step; orbit-level statement PROVED by symmetry and checked directly; embed/h21_trev_search.py, h21_trev_check.py, h21_trev_cert.py, h21_trev_fullcheck.py, h21_trev_basin.py, h21_phase_search.py, h21_phase2trev.py, h21_cert_indep.py and their logs, h21_trev_cand_w6_o26.npy, h21_phase_cand_w4_o{26,30,31}.npy and _cert.json].

- *How it was found.* We completed H.27.2's search on all 20 maximal refined PFs (300 starts per pair, h21_trev_open_*.log). It produced exactly one crossing: orbit 26, on the Lugano-type refined PF w′ = index 6, in 1 of 300 starts, at relative value $-2.42872\cdot10^{-5}$. The optimum had a special Gram structure. For each party, the vectors $U_{k,x}\varphi_k(o)$ for the two outputs o are orthogonal, and for a fixed o the vectors for different blocks x differ only by a phase. Imposing that structure gives the following family.

- *Definition (PF phase board).* Fix a refined PF w′ (H.27.1). Party k has a block function $w'_k(z_{-k})$ of the other two parties' bits, and a real phase table $\theta_k(o_k, x)$, with x ranging over the blocks of w'_k. The qubit board is $V\,|z\rangle_P\,|o\rangle_{AO} = \exp(i\,\Sigma_k\,\theta_k(o_k, w'_k(z_{-k})))\,|z\rangle_{AI}\,|o\rangle_F$, read with SU(2) frames on the agents' inputs and a source state ψ on P. In words, each agent receives its own past qubit unchanged, and its output goes to the future carrying a phase. That phase depends on the agent's own output and, through the refined PF, on the other two agents' inputs. It is a phase process in the sense of H.21.1, with a phase that is a sum of single-party terms routed by a refined PF. It is also the time-reversed PF lift of H.27.2 with qubit node wires, diagonal node unitaries $U_{k,x} = \mathrm{diag}(e^{i\theta_k(0,x)}, e^{i\theta_k(1,x)})$ and $\varphi_k(o) = |o\rangle$.

- *Relation to H.12 [checked, h21 session].* The phase form of H.12 (H.21.1) has this shape. Agent A's phase term is $o_A(z_B \vee z_C)$, B's is $o_B\,z_A\,z_C$ and C's is $o_C\,z_B(1-z_A)$, with phase steps π, π/2 and π, and the factor $i^{\mathrm{pre}(z)}$ depends on z only and can be absorbed into ψ. The three block indicators $z_B \vee z_C$, $z_A\,z_C$ and $z_B(1-z_A)$ form a refined PF, which matches w′ = index 14 of the enumeration up to block labels (is_refined_pf, h20_common.py). So H.12 is a PF phase board with phases fixed to multiples of π/2. Rounds 15–20 never freed those phases continuously in this way.

- *Purity.* For the family: a PF phase board is a time-reversed PF lift, which is pure by H.27.2 (forward-lift validity PROVED; time reversal CITED, Guérin–Brukner 2018, App. D). For the three certified boards we also did not rely on the citation. h21_cert_indep.py builds the 64×64 unitary V′ (board plus frames) in exact Gaussian-rational arithmetic and checks two things. First, V′ is exactly unitary. Second, the Araújo et al. validity projector conditions on its process matrix hold with residual exactly 0, with $\mathrm{Tr}\,W = 64 = d_O\cdot d_P$ (the same projector as H.23.1b). A float closed-loop test with random agent unitaries (h21_trev_fullcheck.py) agrees.

- *Validity is not automatic.* Phases $\theta_k(o_k, z_{-k})$ that are *not* routed through a refined PF generally give invalid boards. Random examples have Araújo penalty 26–88, while the one-party case is valid (h21_diag_tangent.log). At Φ = 0 the penalty Hessian vanishes identically, so the tangent test gives no information there. The span of refined-PF phase patterns has dimension 19.

- **Theorem H.28.1 [PROVED; exact arithmetic].** There are pure (purifiable) three-party processes that violate a facet of each of orbits 26, 30 and 31. Values are for the representative facet in integer units (maximum PF value 3), with relative value = value/3. Each was computed exactly from a Gaussian-rational board: Cayley-rationalised phases and frames with denominator 10^6, exactly modulus 1 and exactly unitary, and a rational source normalised exactly.

orbit	facet	refined PF w′	exact value	relative value
26	240	index 4 (phase board)	$-7.2861609\cdot10^{-5}$ (checker B); $-7.2861612\cdot10^{-5}$ (checker A)	$-2.4287203\cdot10^{-5}$; $-2.4287204\cdot10^{-5}$
26	240	index 6 (general time-reversed lift, $D_k = 4$; checker A only)	$-7.2861610\cdot10^{-5}$	$-2.4287203\cdot10^{-5}$

orbit	facet	refined PF w′	exact value	relative value
30	245	index 4 (phase board)	$-2.6894965\cdot10^{-2}$ (both checkers)	$-8.9649883\cdot10^{-3}$
31	247	index 4 (phase board)	$-2.6894965\cdot10^{-2}$ (both checkers)	$-8.9649883\cdot10^{-3}$

Each p is exactly valid: it is non-negative and normalised under all 64 deterministic interventions. Two programs check each phase-board certificate. Checker A, h21_trev_cert.py (applied after h21_phase2trev.py; h21_phase_cert_w4_o*.log), works from the Gram formula of H.27.2. It also confirms that the facet functional is exact on all 744 PFs. Checker B, h21_cert_indep.py, was written separately with its own exact complex-rational class. It builds the explicit unitary and recomputes p and the facet value from scratch. Each checker rationalises the float point on its own, so they certify slightly different rational boards. For orbits 30 and 31 the values agree to 10 digits; for orbit 26 they differ in the 8th digit. Both values are exact and negative.

- *Whole orbits.* The 384-element symmetry group maps Purif to itself (Proposition H.23.1a), so one violated facet means every facet of the orbit is violated by some pure process. We also checked this directly. For each certified p, the 384 images violate all 192 facets of its orbit (192/192 for each of 26, 30 and 31), while p itself violates exactly one facet among the ten H.27 orbits (h21_cert_indep_w4_o*.log).

- *Robustness [NUMERICAL].* Basin hopping with 300 perturbations in the general family from the orbit-26 point does not improve on $-2.4287204\cdot10^{-5}$ (h21_trev_basin_w6_o26_s1.log). So it is a stable local optimum, not a rounding artefact. The optimal phase steps $\delta_k(x) = \theta_k(1, x) - \theta_k(0, x)$ are not recognisable angles. For orbit 26 they are (in units of π) [[−0.543, 0.413], [−0.417, 0.678], [−0.065, 0.440]]; for orbit 30 they are [[0.116, 0.780], [−0.636, 0.701], [−0.228, 0.772]]. Orbit 26's violation is very small, about $3\cdot10^{-4}$ of orbit 30's.

H.28.2 Searches on the seven remaining orbits: nothing crosses [NUMERICAL, negative; embed/h21_phase_open_.log, h21_trev_open_*.log, h21_trev_basin_fromphase_w4_o.log, h21_inst_search.py, h21_inst_valcheck.py, h21_inst_w4_R*.log].**

- *Validation of the phase-board search.* On the crossed orbits, the phase-board search (L-BFGS on the Rayleigh quotient as in H.27.2, 500 starts, about 0.14 s per start) reproduces H.27.2's float optima, with far higher hit rates than the general search: −0.046472 on orbits 14 and 25, −0.015474 on 53, −0.0098036 on 79 and −0.033966 on 4 (h21_phase_validate.log).
- *Phase boards on all 20 refined PFs, 500 starts per (rule, orbit).* All eight Lugano-type rules (indices 4, 5, 6, 7, 10, 11, 14, 15) cross orbits 30 and 31, in 19–39 of 500 starts (6–8%). Rules 4, 5, 6, 7, 10, 11 and 14 (all but 15) also cross orbit 26, in 2–5 of 500 starts. The twelve single-block rules cross nothing. On orbits 28, 54, 57, 66, 69, 75 and 81 the best value on every rule is 0 to about 10^{-15} (tight, never crossed), or 1/3 where the orbit cannot even be reached. All 20 rules finished (h21_phase_open_*.log). A negative result bounds what this optimiser finds, not what the family contains.
- *General time-reversed lifts (H.27.2 family), now on all 20 rules.* 300 starts per pair (h21_trev_open_*.log). The only crossing is orbit 26 on index 6, and the value on all seven remaining orbits is 0. This search **missed orbits 30 and 31 completely**, even though they sit inside its own family and the phase boards hit them in 6–8% of starts. That is a direct measure of how weak a negative result from the general search is.
- *Basin hopping from the phase optima.* For each of the seven orbits we started from the best w′ = 4 phase board and made 80 perturbation hops in the general family ($D_k = 4$). The best value stays at about 0 (h21_trev_basin_fromphase_w4_o*.log).

- *Agent instruments and mixed wiring.* h21_inst_search.py lets each agent prepare a state that depends on the measured outcome (Kraus rank L = 2), and lets a set R of parties use time-reversed rather than forward wiring (R is a bitmask; R = 0 is the forward family of H.27.1, and R = 7, all parties time-reversed, contains H.27.2 and the PF phase boards). A float validity check gives deviation 0 for all R (h21_inst_valcheck.py). Runs on w′ = index 4 with 40 starts each over orbits 30, 28, 54, 57, 66, 69, 75 and 81: for every R = 1, …, 7 the best value on every orbit is 0 to about 10^{-14}, or 1/3 where it cannot be reached. These runs do not cross even orbit 30, although R = 7 contains the phase boards that cross it, so at 40 starts this search is weak. R = 0 is settled by Theorem H.27.1 and was not run. *(Corrected in Round 22: the first version of this paragraph had the meaning of R reversed.)* Caveat: partial time reversal is not guaranteed to give a valid process in general, so any hit from this script would need an exact purity check. With 40 starts it also misses orbit 14's known crossing, so its negatives are weak.
- *Not done this round.* Arbitrary diagonal phase boards Φ(o, z) with a validity penalty: the search was too slow (more than 14 minutes for 10 starts) and was stopped. Also not done: boards with non-diagonal node unitaries on qubit node wires outside the H.27.2 search, SOS/SDP relaxations of Purif, and perturbative searches around the −1/6 point of Valid.

H.28.3 Status of the 22 genuine orbits after Round 21 [summary; labels as stated].

- *Crossed, exactly certified (15):* orbits 4–11, 14, 25 (H.22.2), 53, 79 (H.22.2), 26, 30, 31 (H.28.1). Each is crossed at orbit level by symmetry.
- *Open (7; 960 facets):* 28 (192 facets), 54 (96), 57 (192), 66 (96), 69 (192), 75 (96), 81 (96). Proved: they hold on every forward PF lift and its convex hull (Theorem H.27.1). Numerically, none of the searches above crosses them: the best value is 0, and on several single-block rules it is 1/3. Whether they hold on Purif is **OPEN**.
- *Reading [INTERPRETIVE].* All 15 crossed orbits are crossed by time-reversed Lugano-type boards. One pattern may be suggestive but has not been analysed. Six of the seven open orbits (all but 28) have representative facets that some single-block rules cannot even reach: their best value there is 1/3. None of the newly crossed orbits 26, 30 and 31 behaves this way. A proof that the seven hold on Purif would have to tell them apart from 26, 30 and 31, which phase boards cross at phases with no evident special angles.

H.29 Round 22: pure processes with a classical future record, a reduction of the time-reversed lifts to phase boards, and all valid phase processes; the seven orbits stay open (Oct 26 2026). Round 22 targeted the seven open orbits 28, 54, 57, 66, 69, 75 and 81 (960 facets). **None is crossed.** The counts stay at 15 of 22 crossed and 7 open. The round produced three structural results and one search family that passes validation. The structural results are an exact validity criterion for pure processes whose future records the agents' outputs (H.29.1), a lemma that reduces the time-reversed PF lifts of H.27.2 to PF phase boards (H.29.2), and an exact classification of the valid three-qubit phase processes (H.29.3). The search family is the exact per-component phase-process search, which reproduces orbits 26 and 30. Penalty-based searches, by contrast, failed validation, so their negative results carry little weight (H.29.4). Code and logs are in code/stochastic/cyclic/embed/h22_*.

H.29.1 Classical-output pure processes (COPP): exact validity criterion [criterion PROVED by derivation and cross-checked numerically; tangent probe NUMERICAL; h22_copp.py, h22_copp_valcheck.py/.log, h22_copp_valcheck2.py/.log, h22_copp_tangent.py].

- *Family.* $V|s\rangle_P|o\rangle_{AO} = (U_o|s\rangle)_\{AI\}|o\rangle_F$, with one unitary U_o on the three agent input qubits for each output triple o. Agents measure in the computational basis, and frames are absorbed into U_o, so $p(i|o) = |\langle i|U_o\psi\rangle|^2$. PF phase boards ($U_o = E\cdot D_o$) and forward PF lifts are of this form.

- *Criterion.* Tracing F gives $W = \Sigma_o |o\rangle\langle o|_{AO} \otimes |v_o\rangle\langle v_o|$, so the process is valid iff $\Sigma_o U_o\dagger(\otimes_k M\hat{}k_{o_k})U_o = 1$ for every choice of binary POVMs $(M\hat{}k_0, M\hat{}k_1)$. Expanding in $M\hat{}k_1$ gives an equivalent form. For every nonempty set S of parties, every fixed $c \in \{0,1\}^{-S}$ and every operator X_S on S: $\Sigma_{\{o_S\}} (-1)^{|o_S|} U\dagger_{(o_S,c)}(X_S \otimes 1)U_{(o_S,c)} = 0$. The single-party conditions say that $U_{o\oplus e_k}U_o\dagger$ acts only on the other two parties' qubits. In words, an agent's output cannot reach its own input.
- *Cross-check [NUMERICAL].* The criterion's penalty vanishes exactly where the Araújo et al. projector penalty (H.23.1) vanishes, with a ratio of about 9 between the two. Tested points: a PF phase board at the orbit-30 optimum ($9.6\cdot10^{-29}$ vs $1.6\cdot10^{-29}$, reproducing $\lambda = -0.0089649883$); random unitaries (about 1500 vs 117); separable phases not routed through a PF (413 vs 41, 99 vs 11, 500 vs 50); valid points from penalty projection (10^{-21}–10^{-19} vs 10^{-22}–10^{-20}).
- *Tangent probe [NUMERICAL].* We estimated the dimension of the valid set from the rank of the penalty Hessian. At the Lugano phase boards (rules 4 and 10) it is 80, at $w' = 13$ it is 88, and at a forward lift on rule 4 it is 80. The value 80 equals 64 (a common right unitary, absorbed by ψ) + 10 (left local unitaries) + 6 (the phase-board phase steps). So at these points the valid set has no deformations beyond the obvious ones and the phase-board family. At the trivial point $U_o = 1$ the Hessian vanishes identically because the penalty is quartic there, and the value at the forward rule-13 point was not reliable. Both are excluded.

*H.29.2 The time-reversed PF lifts reduce to their extreme points: phase boards, plus rank 2 for four-block parties [Lemma PROVED; extreme-point rank bound CITED (Li–Tam 1994); $n_k = 2$ case PROVED elementarily; rank-2 search NUMERICAL; h22_rank2_search.py, h22_rank2_.log].**

- **Lemma H.29.2a.** In the time-reversed PF lift of H.27.2 on a refined PF w′, the statistics depend on the node unitaries and the states φ_k only through the correlation matrices $K_k(o)[x, x'] = \langle U_{k,x}\varphi_k(o), U_{k,x'}\varphi_k(o)\rangle$. These are $n_k \times n_k$ positive semidefinite matrices with unit diagonal, where n_k is the number of blocks of party k and $o \in \{0,1\}$. Any pair $(K_k(0), K_k(1))$ is realised with node dimension $D = 2n_k$: put the two Gram realisations in orthogonal halves. For fixed source, frames and other K's, the facet value is affine in each $K_k(o)$ separately. Its minimum over the family is therefore attained when every $K_k(o)$ is an extreme point of the complex elliptope. Extreme points of rank r satisfy $r^2 \le n$ (Li and Tam, SIAM J. Matrix Anal. Appl. 15 (1994) 903, CITED). For $n_k \le 3$, every extreme point has rank 1, $K = vv\dagger$ with $|v_x| = 1$, and this is exactly a PF phase board. For $n_k = 4$ the rank is at most 2. For $n_k = 2$ the step is elementary: K is fixed by one complex number c with $|c| \le 1$, and an affine function on the disk is minimised on the circle $|c| = 1$.
- *Consequence.* On the 14 refined PFs whose parties all have $n_k \le 3$ (all eight Lugano-type rules and six single-block rules), the infimum of any facet over the H.27.2 family equals its infimum over PF phase boards. This explains why the general search of H.28.2 missed orbits 30 and 31 while the phase-board search hit them: the general search optimised over the interior of a set whose minimum lies on its extreme boundary. On those 14 rules, H.28.2's phase-board runs (500 starts per pair) are thus runs over the extreme points of the whole H.27.2 family. They remain a numerical search, not a proof.
- *Rank-2 search on the six rules with a four-block party (0, 3, 8, 12, 18, 19).* Parties with $n_k = 4$ use n_k unit vectors in C^2 (rank ≤ 2). Parties with $n_k \le 3$ use phases. This contains all extreme points. Allowing C^2 for every party also contains them, but the optimiser then drifts into the interior (0/20 hits on orbit 30). Validation on rule 4, where the parametrisation reduces to phase boards: orbit 30 at $-8.9650\cdot10^{-3}$ in 6 of 40 starts and orbit 26 at $-2.4287\cdot10^{-5}$ in 1 of 40 (h22_rank2_val_w4.log). Results, 500 starts per rule over the seven orbits: on every rule and every one of the seven orbits the best value is 0 to about 10^{-15} with no start below -10^{-9}, or 1/3 where the orbit cannot be reached (rules 0, 3: orbit 66; rules 8, 18: orbits 69, 81; rules

12, 19: orbits 54, 57, 75). Together with H.28.2, every extreme point type of the H.27.2 family on all 20 refined PFs has now been searched, with no crossing.

H.29.3 All valid three-qubit phase processes: 34 components, including a new family [two-party factorisation PROVED; branch enumeration exact (sympy row spaces, Smith normal form); three-party condition checked NUMERICALLY at random points; h22_phaseproc.py, h22_pp_components.py/.json/.log].

- *Setting.* Take diagonal phase processes $D_o = \mathrm{diag}(e^{i\varphi(o,z)})$, read in SU(2) frames, and apply the criterion of H.29.1. The single-party conditions forbid any $o_k\, z_k$ interaction. Up to phases that depend only on o (irrelevant) or only on z (absorbed into ψ), φ is therefore a real combination of 12 mixed monomials: $o_k\, z_j$ (6), $o_k\, z_j\, z_l$ (3) and $o_j\, o_k\, z_l$ (3), with {j, k, l} = {0, 1, 2}. PF phase boards use only the first 9. The three monomials $o_j\, o_k\, z_l$, in which two outputs jointly steer a phase on the third party's input, are new.
- *Two-party condition.* Fix a pair {j, k} with third party l, and fix (z_l, o_l). The condition factorises as $(1 - e^{iR_j})(1 - e^{iR_k}) = 0$, with $R_j = a_{j,k} + c_j\, z_l + g_k\, o_l$ and $R_k = a_{k,j} + c_k\, z_l + g_j\, o_l$. So in each of the 12 (pair, z_l, o_l) cases either j does not influence k or k does not influence j. This is the one-way-influence structure of process functions, now at the level of phases.
- *Enumeration.* The 2^{12} branch choices give 1219 distinct lattices of linear conditions. 1217 satisfy the three-party condition at all random test points. 2 fail it somewhere, and the valid subsets of those 2 were not enumerated. The 1217 branches have **34 maximal valid components**, all torsion-free (Smith invariants 1), so each is a subtorus:
  - 8 three-dimensional components that use the c-monomials. These are the Lugano-type PF phase boards (for example rule 4 ↔ nonzero coordinates {2, 4, 5, 6, 7, 8});
  - 8 three-dimensional components that use the g-monomials $o_j\, o_k\, z_l$ instead of c. These are **new**: they are not PF phase boards;
  - 18 five-dimensional components that mix the three types. Penalty projection from random starts lands on valid points in 200 of 200 starts, and only 4% of those points have all g = 0 (h22_phaseproc.py scan). So the g-directions are generic, not exceptional.
- *Caveats.* The three-party condition was checked at random points, not symbolically. The two failing branches might still contain valid subsets outside the 34 components. *Update (Round 23, H.30.3): both caveats are closed. The three-party condition is now checked exactly by a character-class argument, and the two failing branches (the cyclic patterns) are valid only on six subtori, each inside one of the 34 components, so the classification is PROVED.* Whether the new g-components are equivalent to PF phase boards under a symmetry outside the 384-element group (for example a change of frame that exchanges the roles of inputs and outputs) was not analysed [OPEN].

H.29.4 Searches on the seven orbits: nothing crosses; the exact phase-process search passes validation, penalty searches do not [NUMERICAL, negative; h22_pp_comp_search.py, h22_ppc_.log, h22_copp_search.py, h22_phaseproc.py, h22_pp_o.log].**

- *Exact per-component search (passes validation).* Inside each of the 34 components validity is exact (φ = N y), so no penalty is needed. We minimise the Rayleigh quotient over (y, frames, ψ) by L-BFGS and report the exact minimum over ψ (the smallest eigenvalue), re-checking validity at the best point (penalty ≤ $5 \cdot 10^{-26}$ everywhere).

    - Validation, orbit 30: $-8.964988\cdot10^{-3}$, the H.28.1 value. Across the seed-1 (10 starts per component) and seed-2 (40 starts) runs it is reached on all 8 Lugano components and on no other component. Hit rates are 1–4 per 40 starts.
    - Validation, orbit 26: $-2.428720\cdot10^{-5}$, the H.28.1 value, on Lugano component 9 (1 of 40 starts).
    - Neither the 8 g-components nor the 18 five-dimensional components cross orbit 26 or 30 at these sample sizes.
    - The seven orbits, 40 starts per component (seed 2): the best value on each is $-1.8\cdot10^{-15}$ to $-8\cdot10^{-16}$, i.e. 0, with no start below -10^{-9}. A second run with 150 starts per component (seed 3; 5,100 starts per orbit) gives best values between $-2.0\cdot10^{-15}$ and $-1.0\cdot10^{-15}$, again with no start below -10^{-9} (h22_ppc_o*_s3.log).
- *Penalty searches (fail validation).* The COPP search ($U_o = \exp(iH_o)$ with a staged validity penalty and a final projection; h22_copp_search.py) reaches only -10^{-11} on orbit 30 in 3 random starts. Started from random Lugano phase boards (pbL mode) it ends at positive values. The penalty phase-process search over the 12-torus (100 starts per orbit; h22_pp_o*.log) finds 0 of 100 starts below -10^{-8} on orbit 30 (best $-4.1\cdot10^{-13}$). On the seven open orbits it gives best values between $-2.8\cdot10^{-12}$ and 0 and no start below -10^{-8}. Both searches converge to valid but nearly trivial points. Their negatives on the seven orbits are therefore close to uninformative, which is why the exact search above was built.
- *Exact certificates.* There is no crossing, so neither h21_trev_cert.py nor h21_cert_indep.py was run this round. A crossing on a g-component would need h21_cert_indep.py (explicit unitary), since checker A's Gram formula covers only PF phase boards and lifts.
- *Not done.* A certified SDP/SOS bound that uses purity. A general pure-process search beyond COPP that passes validation. A perturbative search around the −1/6 point of Valid (H.17.5). Two-component mixtures and instruments on the new g-components.

H.29.5 Status after Round 22 [summary]. Still **15 of the 22 genuine orbits crossed** (exactly certified) and **7 open** (28, 54, 57, 66, 69, 75, 81; 960 facets). The following now hold:

- the seven hold on forward PF lifts (Theorem H.27.1, PROVED);
- on the time-reversed lifts of H.27.2, the problem reduces to extreme points (Lemma H.29.2a, PROVED with a CITED rank bound), and the extreme-point searches find no crossing (NUMERICAL);
- the exact search over all 34 components of valid three-qubit phase processes finds no crossing, while it does reproduce both crossings of orbits 26 and 30 (NUMERICAL). Whether the seven hold on Purif is **OPEN**.
Reading [INTERPRETIVE]. Every crossing found so far, in any round, lies on a Lugano-type component. On the families examined, the seven open orbits behave like constraints of process functions. A purity-based proof would have to explain why the Lugano components cross 26, 30 and 31 but not these seven.
- *Correction recorded this round.* The H.28.2 instrument paragraph first stated the meaning of the wiring mask R backwards (R is the set of time-reversed parties). It was corrected in commit 1e95e03, and a note in the text records the correction.

H.30 Round 23: a span lemma proves the seven open orbits on every non-Lugano family; the phase-process classification is now exact; the seven stay open on Purif (Oct 26 2026). Round 23 tried to prove the seven open orbits 28, 54, 57, 66, 69, 75 and 81 (960 facets) using purity. A proof for all of Purif was not reached. **What is proved is a statement on an explicit subclass.** On every valid three-qubit phase process outside the eight Lugano-type components, and on every time-reversed PF lift (H.27.2) on the twelve single-block refined PFs, every facet of the seven orbits holds. So do the facets of orbits 26, 30 and 31. Each family's statistics lie in an exactly computed linear space S (Lemma H.30.1). On Valid ∩ S, two independently written programs certify every

facet with exact LP duality (Theorem H.30.2). The round also completes the enumeration of H.29.3 exactly (H.30.3). A search started at the −1/6 points of Valid failed validation (H.30.4). The counts are unchanged: **15 of 22 genuine orbits crossed, 7 open.** Code and logs are in code/stochastic/cyclic/embed/h23_*.

H.30.1 The statistics span of a family [Lemma PROVED by derivation; integer generators, exact ranks; sampled spans agree NUMERICALLY; h23_span.py, h23_span_lp.py, h23_span_lp_comp.log, h23_span_lp_rule.log, h23_affhull.py/.log/.json].

- *Expansion.* For a COPP (H.29.1) read in SU(2) frames e_k with source ψ on the three input qubits, p(i|o) = Σ_{z,z′} conj(ψ_z) ψ_{z′} χ_{zz′}(o) Π_k conj(e_k[i_k, z_k]) e_k[i_k, z′_k]. This covers two families. For a phase process, χ_{zz′}(o) = e^{i(φ(o,z′) − φ(o,z))}. For the time-reversed PF lift on a refined PF w′ (H.27.2, Lemma H.29.2a), χ_{zz′}(o) = Π_k K_k(o_k)[w′_k(z_{-k}), w′_k(z′_{−k})].
- *Frame factor.* As a function of i_k, the k-th frame factor lies in span{1, $(-1)^{i_k}$} if z_k = z′_k. If z_k ≠ z′_k it lies in span{$(-1)^{i_k}$}, because two columns of a unitary are orthogonal, so the constant part vanishes.
- *Output factor, phase processes.* On a component {x : Mx ∈ 2πZ^r}, φ = x · m(o, z), where m is the vector of the 12 mixed monomials. All 34 components are torsion-free (H.30.3), so the valid set is ker M + $2\pi Z^{12}$. Then χ_{zz′}(o) = e^{i x·(m(o,z′) − m(o,z))} takes the same value on any two outputs o, o′ whose integer difference vectors differ by an element of rowspace(M). So χ lies in the span of the indicators of these classes of o.
- *Output factor, time-reversed lifts.* The k-th factor is 1 if z and z′ lie in the same block of party k. Otherwise it is an arbitrary function of o_k.
- **Lemma H.30.1.** For each family, all statistics, for every source (pure or mixed), every frame and every point of the family, lie in the linear space S spanned by the integer vectors (o-pattern) ⊗ (i-pattern) over all pairs (z, z′). If a facet's minimum over Valid ∩ S is ≥ 0, the facet holds on the whole family and on its convex hull.
- *Dimensions [exact; sampled check NUMERICAL].*
  - The 26 non-Lugano phase components have dim S = 20, 22 or 24.
  - The 12 single-block rules have dim S = 22 or 24.
  - The 8 Lugano components (7–10, 22–25) and the 8 Lugano-type rules (4, 5, 6, 7, 10, 11, 14, 15) have dim S = 38, which is the full affine hull of Valid (Valid has affine dimension 37, the same as the PFs).
  - For every family, 300 random members span exactly S (residual ≤ $6\cdot10^{-15}$), so S is not larger than it needs to be.
  - The 38 non-Lugano families give 23 distinct spaces. Several rules and components share a space: rule 0 = comp 0, rules 1, 2 = comps 1, 2, rule 3 = comp 3, rule 8 = comp 27, rules 9, 17 = comps 28, 29, rule 12 = comp 6, rules 13, 16 = comps 11, 26, rule 18 = comp 30, rule 19 = comp 33. The remaining spaces belong to comps 4, 5, 12–21, 31, 32.
- *Why the method stops at Lugano.* On the Lugano-type families S is the whole space, so Valid ∩ S = Valid. There the LP minimum is the −1/6 of H.17.5 for all ten orbits, and the method gives no information. These are exactly the families on which orbits 26, 30 and 31 are crossed (H.28.1, H.29.4).

H.30.2 Exact certificates on every non-Lugano family [Theorem PROVED in exact rational arithmetic by two independent checkers; all-facet extension NUMERICAL; h23_span_cert.py, h23_span_cert_{1..5}.log, h23_span_certB.py, h23_span_certB_{1,2,3}.log, h23_span_certB_lugano_control.log, h23_span_allfac.py, h23_span_allfac_rules.log, h23_span_allfac_comps.log].

- **Theorem H.30.2.** Let p be the statistics of any of the following, with any SU(2) frames and any source state, or a convex mixture of such statistics:

    - (a) a valid three-qubit phase process (H.29.3) whose phase vector lies in one of the 26 non-Lugano components (0–6, 11–21, 26–33);
    - (b) a time-reversed PF lift (H.27.2: any node dimension, node unitaries and states, so any correlation matrices $K_k(o)$) on one of the 12 single-block refined PFs (0, 1, 2, 3, 8, 9, 12, 13, 16, 17, 18, 19).

    Then p satisfies **every one of the 1,536 facets** of orbits 26, 28, 30, 31, 54, 57, 66, 69, 75 and 81. This includes all 960 facets of the seven open orbits. In integer facet units the certified minimum on Valid ∩ S is 0 or 1 for every facet. 1 means the facet cannot even be made tight in that family; it corresponds to the relative value 1/3 seen in H.28.2 and H.29.2.

- *Proof.* By Lemma H.30.1, $p \in \text{Valid} \cap S$. For each of the 23 distinct spaces S and each of the 1,536 facets, the checkers certify $\min_{\text{Valid} \cap S} (g \cdot p + g_0) \geq 0$, giving $23 \times 1{,}536 = 35{,}328$ certificates per checker. Here g is the facet's affine functional, which is fixed on Valid because Valid and the PFs have the same affine hull.

- *Checker A (h23_span_cert.py).*

    - It writes $p = Bc$ with an integer basis B of S.
    - It takes the dual support from a HiGHS simplex solve and solves exactly for $\nu \geq 0$ and λ with $B^T(g - \nu - \text{Aeq}^T\lambda) = 0$ and $\Sigma\lambda + g_0 = t$, where $t \in \{0, 1\}$.
    - It re-verifies the identity in Fraction arithmetic against every basis column.

- *Checker B (h23_span_certB.py), written separately.* It differs from checker A at every step:

    - S is built from different generators: class indicators from an integer basis of ker M for components, and block-output and equal-bit indicators for rules. B then computes $S^{\perp} = N$ exactly with DomainMatrix over $\mathbb{Q}$.
    - The functional g is solved exactly from 38 affinely independent PFs and checked on all 744 PFs. A instead rationalises a least-squares fit.
    - The LP is posed in p-space, min $g \cdot p$ subject to Aeq $p = 1$, $N^T p = 0$ and $p \geq 0$, and solved by the interior-point method.
    - The certificate $g = \text{Aeq}^T\lambda + N^T\mu + \nu$ with $\nu \geq 0$ and $\Sigma\lambda + g_0 = t \geq 0$ is checked coordinate by coordinate in exact rationals. Then $g \cdot p + g_0 = t + \nu \cdot p \geq t$ on Valid ∩ S.

- *Results.* Both checkers certify all 1,536 facets on all 23 spaces with 0 failures (logs above). The two checkers return the same bound set {0, 1} on every space.

- *Negative control.* Run on Lugano rule 4 and Lugano component 7 for orbits 26 and 30, checker B certifies nothing. All 384 facets come back "LP<0" at −1/2 in integer units, which is −1/6 relative. This is what H.30.1 predicts.

- *Beyond the ten orbits [NUMERICAL].* A float LP over all 29,344 facets on all 12 single-block rules and on comps 4, 5, 12–21, 31 and 32 finds no facet with minimum below -10^{-9}; the most negative value is $-1.3 \cdot 10^{-13}$. These cover every one of the 23 spaces. So numerically Valid ∩ S ⊆ conv(PF): on every non-Lugano family the statistics are PF blends.

- *What this covers and what it does not.*
    - Combined with H.30.3, part (a) covers every valid three-qubit phase process except those lying only in Lugano components.
    - Part (b) covers all of H.27.2 on the single-block rules, not just the extreme points of Lemma H.29.2a.
    - It does **not** cover:
        - the 8 Lugano-type rules and components, which is where every known crossing lives;
        - time-reversed lifts on Lugano-type rules;
        - COPPs that are not phase processes;
        - pure processes whose future does not record the outputs;
        - agents with general instruments.
    - On all of these the seven orbits remain **OPEN**.

- *Novelty [cautious].* The span argument is elementary: unitarity kills the constant part of an off-diagonal frame factor, and characters of a torus are linearly independent. We have not seen it used for causal-inequality or PF-hull questions, but we have not searched the literature thoroughly.

- *SDP/SOS on the Lugano families [not done, OPEN].* On the Lugano families, purity enters only through the positive semidefinite correlation matrices $K_k(o)$ (Lemma H.29.2a) and the rank-one source. A moment relaxation in these variables would be the natural next step. It was not set up this round.

H.30.3 The phase-process classification of H.29.3 is now exact [PROVED, exact integer and rational arithmetic; h23_pp_enum2.py/.log/.json, h23_pp_enum2_rows.py, h23_pp_exact.py/.log].

- *Torsion.* The Smith normal form of all 1219 branch lattices has every invariant equal to 1. So every branch is a subtorus $\ker M + 2\pi Z^{12}$, and no torsion cosets exist.
- *Three-party condition, exactly.* On a branch, each COPP condition (H.29.1) is a signed sum of characters $e^{i\,x\cdot v}$ of the torus $\ker M$. Two characters coincide iff the difference of their integer vectors is orthogonal to $\ker M$, and distinct characters are linearly independent. So a condition holds on the whole branch iff, in every class of equal characters, the signed count $\Sigma(-1)^{|o_S|}$ vanishes. h23_pp_exact.py checks this for every party set S, every c, z and z′, using an integer kernel basis.
    - 1217 of the 1219 branches are exactly valid on their whole torus.
    - All 34 components of H.29.3 are exactly valid.
- *The two failing branches.* These are the two cyclic one-way patterns. One has free coordinates {1, 2, 5}, the other {0, 3, 4}; in each, every party's phase is steered by exactly one other party around a cycle. The three-party condition factorises as $(1 - e^{i\alpha\Delta_1})(1 - e^{i\beta\Delta_2})(1 - e^{i\gamma\Delta_3})$. So a point is valid iff one of the three coefficients vanishes mod 2π. Each of the six resulting two-dimensional subtori is exactly valid and contained in a component: 0, 30 and 6 for the first branch, 3, 27 and 33 for the second. Earlier, 300 + 300 penalty-minimisation starts on these branches all landed inside the 34 components (h23_pp_enum2.log), which agrees with this.
- **Result.** The valid three-qubit phase processes are exactly the union of the 34 subtori of H.29.3. This upgrades the classification from "three-party condition NUMERICAL" to PROVED. It rests on the one- and two-party reductions of H.29.3, which were already PROVED. One question from H.29.3 remains OPEN: whether the eight g-components are equivalent to PF phase boards under a symmetry outside the 384-element group. By H.30.2 they cannot cross any of the ten orbits.

*H.30.4 Search started at the −1/6 points of Valid: fails validation [NUMERICAL, negative and uninformative; h23_near16.py, h23_near16_val_o26.log, h23_near16_val_o30.log, h23_near16_o.log].**

- *Method.* For the representative facet, take a vertex p* of Valid with relative value −1/6. Build a COPP with exactly these statistics: $\psi = |0\rangle$, U_o a Householder map with $U_o|0\rangle = \sqrt{p^*}(\cdot|o)$ and random phases. Such a start is invalid. Then minimise the facet value plus $\mu\cdot$(validity penalty) with μ increased from 10^{-2} to 10^{4}, as in h22_copp_search.py, and report the exact minimum over ψ at the end.
- *Validation [fails].* Each orbit got 10 starts. On orbit 30 every start reached a valid point (penalty $\le 2\cdot10^{-12}$), with values between $-2\cdot10^{-9}$ and $+9\cdot10^{-9}$. On orbit 26 the penalties were $\le 3\cdot10^{-11}$ and the values lay between $-2\cdot10^{-10}$ and $+4\cdot10^{-6}$. **Neither re-finds the known crossings** ($-8.96\cdot10^{-3}$ and $-2.43\cdot10^{-5}$). The penalty drives the process to nearly trivial valid points, as in H.29.4.
- *The seven orbits.* Run anyway with 3 starts per orbit (h23_near16_o{28,54,57,66,69,75,81}.log). Every start ends at a valid point (penalty $\le 2\cdot10^{-13}$), with best values between $-3.7\cdot10^{-11}$ (orbit 28) and $+4\cdot10^{-8}$. No start falls below -10^{-7}.
- *Conclusion.* Because validation failed, these runs say nothing about the seven orbits. A perturbative search that keeps validity exactly near the −1/6 points remains **not done**.

H.30.5 Status after Round 23 [summary]. Still **15 of 22 genuine orbits crossed** (exactly certified) and **7 open** (28, 54, 57, 66, 69, 75, 81; 960 facets). The following hold:

- the seven, and in fact all ten H.27 orbits, hold on forward PF lifts (Theorem H.27.1, PROVED);
- they hold on every non-Lugano valid phase process and on all time-reversed PF lifts on single-block rules (Theorem H.30.2, PROVED, two exact checkers);
- the phase-process classification is exact (H.30.3, PROVED).

So for the families studied, the open question has been reduced exactly to **the Lugano-type families**: Lugano phase components and time-reversed lifts on the eight Lugano-type rules, whose extreme points are PF phase boards (Lemma H.29.2a). It also remains open for every pure process outside these families. *Reading [INTERPRETIVE].* Everything that crosses any facet in this paper sits on a Lugano-type family, and everything off those families is (numerically) a PF blend. A proof for the seven would need to use the PSD structure of the Lugano correlation matrices, since linear span arguments see all of Valid there.

Appendix I. Robustness: approximately blended versus approximately liftable (Oct 22 2026)

Norm: for classical processes, ||p - q||_1 = sum over (i,o) of |p(i|o) - q(i|o)|. For machines, the switchboard residual is rho(U) := sqrt(R(U)), the l2 norm of the forbidden Pauli coefficients (H.8.1).

I.1 Blend-close implies liftable-close [proved, trivial]. If ||p - q||_1 ≤ eps with q in conv(PF), then p is within eps of a purifiable process, namely q (C.1). So delta = eps, in any norm. This uses only conv(PF) ⊆ Purif.

I.2 The converse is the conjecture [proved, trivial; the conjecture is false by H.12.1, so the converse fails]. "dist(p, Purif) ≤ delta implies dist(p, conv PF) ≤ eps(delta) with eps(delta) → 0" for all p holds iff the closure of Purif equals conv(PF). If the conjecture holds, then eps = delta. If it fails at some p*, then eps(0) ≥ dist(p*, conv PF) > 0. So no quantitative converse can be proved without proving the conjecture. A non-trivial robustness statement must therefore compare *approximately pure machines* with the hull, as follows.

I.3 Residual controls operator purity [proved]. In family C, with or without ancillas, every entry of M M^dag - 1 has modulus at most 2 sqrt(2) rho(U). *Proof.* Write K = (allowed part) + sum over forbidden sigma of c_{sigma} sigma. The allowed part reproduces the exact row inner products (H.8.1, H.8.2). A forbidden X^delta Z^b contributes $c_{delta,b} \sum_e (+-1) \prod_k N_k(e_k)$. By Cauchy-Schwarz on unit rows, $\sum_e |\prod_k N_k(e_k)| \le \prod_k \sum_{e_k} |N_k(e_k)| \le 1$. Only the 8 strings with a = delta contribute, so the deviation is at most $\sum_b |c_{delta,b}| \le$ sqrt(8) rho. ∎

I.4 Facet violation versus residual [numerical]. Facet violations bound distance: for a facet with +-1 coefficients and bound 0, f.p ≤ ||p - q||_1 for every q in the hull, so a violation v gives dist_1(p, conv PF) ≥ v. push.py minimises R subject to lambda_max(F_m(U)) ≥ v for facet-82 members (the best source state phi for each machine), in float64 with L-BFGS and an increasing penalty. Starts were random, Lugano, and the H.7 solutions rand_1, rand_15 and lug_21. There were 108 runs (curve.jsonl, curve2.jsonl).

target v	runs	min R found	min R / v^2	median R / v^2
0.01	21	3.27e-5	0.327	0.431
0.03	21	2.81e-4	0.312	0.387
0.1	21	3.19e-3	0.319	0.367
0.3	21	2.94e-2	0.326	0.370
0.5	8	9.27e-2	0.371	0.383
0.7	8	1.93e-1	0.394	0.419
0.9	8	3.52e-1	0.434	0.453

Numerical statement (WITHDRAWN after H.12; the exact counterexample has R = 0 with positive violation). For every switchboard machine found by push.py, facet-82 violation ≤ 1.79 rho(U), i.e. R ≥ 0.31 v^2. The ratio R/v^2 is nearly flat for small v, so near the hull boundary the violation grows at most linearly in rho: the modulus looks Lipschitz, not Hölder-1/2. The floor rises slowly for large v. These are local optima: the true infimum of R/v^2 could be lower, and only facet 82 was tested. For contrast, the H.7 sampled-unitary runs reached violations near 0.9 at sampled residual 0.03-0.05. That residual is a sampled average of $||M M^{dag} - 1||^2$ and is not comparable with R. In the exact residual the trade-off is quadratic in v, so a violation is not cheap.

I.5 Converse direction, numerically [numerical; WITHDRAWN after H.12]. Read the other way: a switchboard machine with rho(U) ≤ delta has statistics, at every source state, that violate facet 82 by at most about 1.79 delta. A machine whose statistics violate it by v is at least rho ≥ 0.56 v from pure. So in family C, numerically and for facet 82, "delta-close to liftable" (in the machine residual rho) implies "eps-close to the hull's facet-82 side" with eps ~ 1.8 delta. A full hull-distance version, over all 93 facet orbits, was not run.

Appendix J. Facet-orbit tables for H.13-H.14 (Oct 23 2026)

Generated by code/stochastic/cyclic/switchboard/h13/tables.py from the committed data: facets from physics/facets/pf.out.gz, orbit labels and Z_4 maxima from xviol.npz, Z_8 maxima from xviol_z8.npz, exact Z_4 maxima from exactmax_part1/2.log, and Z_8 certificates from cert_z8.log. Strings are written i_A i_B i_C. "p(i|o)" is the probability of input string i given output string o.

Representatives. Each orbit's representative is its lowest-index facet. The integer form shown is the one with minimal ℓ^1 norm among the affine representatives that agree with the facet on all 744 process functions (found by LP, then scaled to integers and checked exactly). The representatives are exact. Other members of the orbit follow by the 384 symmetries (relabelling parties and local relabelling of inputs and outputs).

Maxima. "Rel." means the largest violation found divided by the facet's range on process functions. The Z_4 exact column gives the minimal polynomial of λ_min, the least eigenvalue of the facet operator $\Sigma\, g\, P_{o,i} + g0$ in the facet's normalisation. The violation is its root at the float-selected maximising board; this exact value is [proved, exact] for that board, while the claim that it is the maximum over the class is [numerical]. The Z_8 column is [numerical].

J.1 The 22 genuine never-crossed orbits, plus orbit 92 (positivity) [numerical; orbit 92 proved in H.17.5]

Status for all 23 listed orbits (22 genuine, plus orbit 92 = positivity): never violated by the Z_4 (386 classes) and Z_8 (10,603 classes) X-type boards, maximised over source states [numerical].

Update (H.17, Oct 23 2026). None of the 23 orbits is violated by Z_{16} X-type boards, continuous X-type phases, locally rotated (local Clifford and $SU(2)^3$) X-type boards, or pure non-X boards with ≤3 terms per outcome [numerical]. Orbits 4–11, 14, 25, 26, 28, 30, 31, 53, 54, 57, 66, 69, 75, 79 and 81 are violated at exact rational points of the valid polytope, so validity alone does not imply them [exact-certified, H.17.5]. Orbit 92 is the positivity orbit p(i|o) ≥ 0. On Valid its functional equals p(111|000) exactly, so it holds for every process [proved, H.17.5]. Only the other 22 orbits are genuinely open. *Update (Round 15, H.22.2): orbits 4–11, 14 and 25 are crossed by a pure board (the time-reversed Lugano process in rotated input and output frames, exact certificate), and orbits 53 and 79 by a generalised Lugano board (H.22.2, addendum). The open list is now the 10 orbits 26, 28, 30, 31, 54, 57, 66, 69, 75, 81.*

orbit	size	representative facet (index) : integer inequality, value ≥ 0 on every PF
4	384	(72) - p(000
5	384	(73) - p(000
6	384	(76) - p(000
7	384	(77) - p(000
8	384	(78) - p(000
9	384	(79) - p(000
10	384	(86) - p(000
11	384	(94) - p(000
14	192	(171) - p(001
25	192	(191) - p(001
26	192	(240) - p(000
28	192	(242) - p(000
30	192	(245) - p(000
31	192	(247) - p(000
53	64	(513) p(001
54	96	(514) p(001
57	192	(521) - p(000
66	96	(561) - p(000
69	192	(571) p(001
75	96	(595) - p(000
79	64	(698) p(001
81	96	(706) - p(000
92	64	(6928) p(111

J.2 The 8 orbits first crossed at Z_8, exact certificates [proved, exact in Q(ζ8)]

Board class 10515 (ζ_8 phases listed in cert_z8.log) satisfies the Pauli rule exactly. With a rational source vector v it gives the following exact values of $|v|^2 \cdot (g \cdot p + g0)$:

- orbit 16 facet 12406 : $|v|^2$ * (g.p+g0) = 491357689/800000000 + -702031757/1600000000 sqrt2 sign -1 value -0.006317 (relative -0.002106)
- orbit 19 facet 26054 : $|v|^2$ * (g.p+g0) = 234647147/400000000 + -670070737/1600000000 sqrt2 sign -1 value -0.005646 (relative -0.001882)
- orbit 21 facet 4386 : $|v|^2$ * (g.p+g0) = 29013371/50000000 + -82955477/200000000 sqrt2 sign -1 value -0.006317 (relative -0.002106)
- orbit 24 facet 8095 : $|v|^2$ * (g.p+g0) = 658166309/800000000 + -935696139/1600000000 sqrt2 sign -1 value -0.004338 (relative -0.001446)
- orbit 27 facet 15356 : $|v|^2$ * (g.p+g0) = 41033639/80000000 + -581201931/1600000000 sqrt2 sign -1 value -0.000794 (relative -0.000265)
- orbit 29 facet 7052 : $|v|^2$ * (g.p+g0) = 205385451/400000000 + -116351057/320000000 sqrt2 sign -1 value -0.000740 (relative -0.000247)
- orbit 52 facet 4396 : $|v|^2$ * (g.p+g0) = 509711951/800000000 + -144553793/320000000 sqrt2 sign -1 value -0.001703 (relative -0.000568)
- orbit 67 facet 12438 : $|v|^2$ * (g.p+g0) = 67432867/100000000 + -191210757/400000000 sqrt2 sign -1 value -0.001703 (relative -0.000568)

J.3 Per-orbit maxima (all 93 orbits)

orbit	Z4 exact max: min-eigenvalue polynomial, root (facet range r)	rel. Z4	rel. Z8 (numerical)	status
0	$8x^4 - 44x^3 + 60x^2 - 20x - 3$ root -0.110409076756 (r=5)	0.02208	0.02208	violated, Z4
1	$8x^4 - 44x^3 + 60x^2 - 20x - 3$ root -0.110409076756 (r=5)	0.02208	0.02208	violated, Z4
2	$8x^4 - 44x^3 + 60x^2 - 20x - 3$ root -0.110409076756 (r=5)	0.02208	0.02208	violated, Z4
3	$8x^4 - 44x^3 + 60x^2 - 20x - 3$ root -0.110409076756 (r=5)	0.02208	0.02208	violated, Z4
4	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
5	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
6	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
7	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
8	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
9	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
10	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
11	-	0	0	never violated by Z4/Z8 X-type boards [numerical]

orbit	Z4 exact max: min-eigenvalue polynomial, root (facet range r)	rel. Z4	rel. Z8 (numerical)	status
12	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
13	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
14	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
15	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
16	-	0	0.002106	Z8 exact certificate (Q(zeta8))
17	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
18	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
19	-	0	0.001882	Z8 exact certificate (Q(zeta8))
20	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
21	-	0	0.002106	Z8 exact certificate (Q(zeta8))
22	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
23	$32x^7 - 272x^6 + 904x^5 - 1484x^4 + 1240x^3 - 472x^2 + 46x + 7$ root -0.0772693314944 (r=3)	0.02576	0.02576	violated, Z4
24	-	0	0.001446	Z8 exact certificate (Q(zeta8))
25	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
26	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
27	-	0	0.0002648	Z8 exact certificate (Q(zeta8))
28	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
29	-	0	0.0002468	Z8 exact certificate (Q(zeta8))
30	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
31	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
32	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.02951	violated, Z4
33	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.02951	violated, Z4
34	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.03115	violated, Z4
35	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.03115	violated, Z4
36	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.0462	violated, Z4

orbit	Z4 exact max: min-eigenvalue polynomial, root (facet range r)	rel. Z4	rel. Z8 (numerical)	status
37	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.0495	violated, Z4
38	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.0495	violated, Z4
39	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.0462	violated, Z4
40	$8x^4 - 28x^3 + 24x^2 - 1$ root -0.184324685944 (r=2)	0.09216	0.09216	violated, Z4
41	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.0462	violated, Z4
42	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.04659	violated, Z4
43	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.0462	violated, Z4
44	$64x^7 - 384x^6 + 864x^5 - 896x^4 + 408x^3 - 48x^2 - 10x + 1$ root -0.138600049779 (r=3)	0.0462	0.04659	violated, Z4
45	$8x^4 - 28x^3 + 24x^2 - 1$ root -0.184324685944 (r=2)	0.09216	0.09216	violated, Z4
46	$8x^4 - 28x^3 + 24x^2 - 1$ root -0.184324685944 (r=2)	0.09216	0.09216	violated, Z4
47	$8x^4 - 28x^3 + 24x^2 - 1$ root -0.184324685944 (r=2)	0.09216	0.09216	violated, Z4
48	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.02951	violated, Z4
49	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.03124	violated, Z4
50	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
51	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
52	-	0	0.0005678	Z8 exact certificate (Q(zeta8))
53	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
54	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
55	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
56	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
57	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
58	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
59	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
60	$2x^2 - 3x - 1$ root -0.280776406404 (r=3)	0.09359	0.09359	violated, Z4
61	$2x^2 - 3x - 1$ root -0.280776406404 (r=3)	0.09359	0.09359	violated, Z4
62	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
63	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
64	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
65	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4

orbit	Z4 exact max: min-eigenvalue polynomial, root (facet range r)	rel. Z4	rel. Z8 (numerical)	status
66	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
67	-	0	0.0005678	Z8 exact certificate (Q(zeta8))
68	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
69	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
70	$4x^2 - 8x - 1$ root -0.118033988750 (r=4)	0.02951	0.02951	violated, Z4
71	$4096x^8 - 40960x^7 + 168960x^6 - 369664x^5 + 456704x^4 - 308544x^3 + 94288x^2 - 1088x - 3789$ root -0.153450660324 (r=4)	0.03836	0.03888	violated, Z4
72	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
73	$8x^4 - 44x^3 + 74x^2 - 33x - 7$ root -0.153963018994 (r=3)	0.05132	0.05132	violated, Z4
74	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
75	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
76	$2x^2 - 3x - 1$ root -0.280776406404 (r=3)	0.09359	0.09359	violated, Z4
77	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
78	$2x^2 - 3x - 1$ root -0.280776406404 (r=3)	0.09359	0.09359	violated, Z4
79	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
80	$16x^5 - 96x^4 + 192x^3 - 140x^2 + 23x + 3$ root -0.0832404606833 (r=3)	0.02775	0.02775	violated, Z4
81	-	0	0	never violated by Z4/Z8 X-type boards [numerical]
82	$4x^2 - 4x - 1$ root -0.207106781187 (r=2)	0.1036	0.1036	violated, Z4
83	$4x^2 - 4x - 1$ root -0.207106781187 (r=2)	0.1036	0.1036	violated, Z4
84	$4x^2 - 4x - 1$ root -0.207106781187 (r=2)	0.1036	0.1036	violated, Z4
85	$16x^5 - 72x^4 + 108x^3 - 60x^2 + 8x + 1$ root -0.0757690071115 (r=2)	0.03788	0.03788	violated, Z4
86	$256x^7 - 1536x^6 + 3456x^5 - 3584x^4 + 1664x^3 - 244x^2 - 17x + 3$ root -0.102016817295 (r=2)	0.05101	0.05101	violated, Z4
87	$32x^6 - 176x^5 + 352x^4 - 304x^3 + 98x^2 - x - 2$ root -0.116604771529 (r=2)	0.0583	0.0583	violated, Z4
88	$256x^7 - 1536x^6 + 3456x^5 - 3584x^4 + 1664x^3 - 244x^2 - 17x + 3$ root -0.102016817295 (r=2)	0.05101	0.05101	violated, Z4
89	$32x^6 - 176x^5 + 352x^4 - 304x^3 + 98x^2 - x - 2$ root -0.116604771529 (r=2)	0.0583	0.0583	violated, Z4
90	$16x^5 - 72x^4 + 108x^3 - 60x^2 + 8x + 1$ root -0.0757690071115 (r=2)	0.03788	0.03788	violated, Z4
91	$2x^2 - 3x - 1$ root -0.280776406404 (r=2)	0.1404	0.1404	violated, Z4
92	-	0	0	positivity facet p(i

J.4 Integer representatives of all 93 orbits

orbit	size	representative facet (index) : integer inequality, value ≥ 0 on every PF
0	384	(0) p(001
1	384	(2) p(001
2	384	(3) p(001
3	384	(6) p(001
4	384	(72) - p(000
5	384	(73) - p(000
6	384	(76) - p(000
7	384	(77) - p(000
8	384	(78) - p(000
9	384	(79) - p(000
10	384	(86) - p(000
11	384	(94) - p(000
12	384	(168) - p(001
13	384	(169) p(001
14	192	(171) - p(001
15	384	(172) p(000
16	384	(173) p(001
17	384	(174) - p(001
18	384	(175) - p(001
19	192	(177) - p(000
20	384	(178) - p(001
21	384	(179) - p(000
22	384	(181) - p(001
23	384	(183) - p(001
24	192	(187) - p(001
25	192	(191) - p(001
26	192	(240) - p(000
27	384	(241) - p(000
28	192	(242) - p(000
29	384	(243) - p(000
30	192	(245) - p(000
31	192	(247) - p(000
32	384	(261) - p(001
33	384	(263) - p(001
34	384	(265) - p(001
35	384	(267) - p(001
36	384	(280) - p(001
37	384	(281) - p(001
38	384	(282) - p(001
39	384	(283) - p(001
40	384	(288) - p(001
41	384	(292) p(000
42	384	(293) - p(001
43	384	(294) - p(001
44	384	(295) - p(001
45	384	(300) - p(000
46	384	(302) - p(000

orbit	size	representative facet (index) : integer inequality, value ≥ 0 on every PF
47	384	(308) - p(000
48	384	(504) p(001
49	384	(506) p(001
50	384	(508) p(001
51	384	(509) p(001
52	192	(512) p(001
53	64	(513) p(001
54	96	(514) p(001
55	384	(516) p(001
56	384	(519) - p(001
57	192	(521) - p(000
58	384	(532) p(001
59	384	(534) p(001
60	384	(543) p(001
61	384	(545) p(001
62	384	(548) p(001
63	384	(550) p(001
64	384	(555) p(001
65	384	(558) - p(001
66	96	(561) - p(000
67	192	(562) p(001
68	384	(569) p(001
69	192	(571) p(001
70	384	(572) p(001
71	384	(573) p(001
72	384	(577) p(001
73	384	(583) p(001
74	384	(593) p(001
75	96	(595) - p(000
76	128	(609) p(001
77	384	(612) - p(001
78	128	(673) - p(001
79	64	(698) p(001
80	384	(705) - p(001
81	96	(706) - p(000
82	384	(1732) p(100
83	192	(1739) p(001
84	192	(1745) p(100
85	192	(1926) p(001
86	384	(1927) p(001
87	192	(1929) p(001
88	384	(1960) - p(001
89	192	(1961) - p(001
90	192	(1962) - p(001
91	96	(5160) p(110
92	64	(6928) p(111

Appendix K. Glossary (Oct 24 2026)

This appendix defines the main technical terms of the paper, in alphabetical order. Each entry gives the definition as the paper uses it, the notation, where it is defined ("Defined in"), and the source in the reference list. A *Usage note* marks places where the paper's usage differs from the literature, or where one word has several meanings in the paper. "See also" points to other entries. References 47–55 were added for this glossary only: they credit standard notions the paper uses but did not cite. The glossary adds no results. Where it and the body text differ, the body text is authoritative.

- **Absorbed class, absorbed vertex** (r; W_o = U_oU_r†). Fix an output r and absorb U_r† into the source state, so that the board becomes W_o = U_oU_r†. The class of r is the absorbed class, and r the absorbed vertex. Vertices o and q are in the same *group* when W_oW_q† is monomial. Each group has a representative ρ and an F_2-subspace H_ρ, spanned by the X-parts of the Pauli support of W_ρ. Defined in H.17.11(a); used in Lemma D (H.17.17). Paper's own construction. See also *SH*, *SH*⁺, *SH*⁺⁺, *SH_grp*, *SH_grp^r*; *Monomial*.
- **Arc consistency.** A pruning step for finite constraint problems. A value in one variable's domain is deleted when some other variable has no value compatible with it. It never deletes part of a complete solution, so a search that combines it with full branching is still exhaustive. The four-class search uses it on the Pauli-rule tables (one 64 × 64 Boolean table per vertex pair). Used in H.17.13–H.17.17; explained in H.26.1a. Source: constraint satisfaction (Mackworth 1977).
- **Activation-controlled (measurable process function).** A process function whose output space splits into countably many product regions. In each region at most one party is *active*, its own output is unconstrained, and its translation amount is an arbitrary measurable function of the other outputs, while the inactive amounts are constant. Two further conditions apply: Lugano-type exclusivity, and the skeleton with zero amounts is a process function. Example: the Lugano pattern on parities with continuous or even nowhere-continuous amounts. The closed loop with arbitrary local unitaries is unitary (F.5.12, Round 18). Paper's own term. See also *Countably controlled*; *Uniformly approximable*.
- **Admissible board.** A board $\{U_o\}$ in which every U_o is unitary and every pair o ≠ o′ obeys the Pauli rule. This is equivalent to purity of the Switchboard built from it (H.7.1, H.8.1). *Pairwise admissible* (H.17.3, H.17.9) means that the Pauli rule holds for one given pair. Defined in the H.17 preamble. Paper's own term. See also *Board*; *Hard board*; *Pauli rule*.
- **AFNB.** Araújo, Feix, Navascués and Brukner [17], the source of the paper's notions of pure process and purification. See *Pure process*; *Purification*.
- **Ancilla.** An auxiliary system on which a party's local operation may also act. Local ancillas are X_k, Y_k in Appendix A. A shared, possibly entangled ancilla is treated in Appendix A Step 3 and H.8.2 ("ancillas add nothing" for Switchboards). The Lean counterexample is checked for finite ancilla types, for ancilla index sets of any cardinality (unitary kernels), for ancillas in arbitrary Hilbert spaces (`isPureHilbert_Vsb`), and for normal CPTP local channels with ancillas of any cardinality (`valid_normalCPTP_Vsb`, countable; `valid_normalCPTP_Vsb_any`, Round 13) (H.12.3, H.19, H.20). With infinite-dimensional ancillas, "pure" means that the closed loop is a unitary of $C^P \otimes \bigotimes K_k$ for all Hilbert spaces K_k and unitaries on $C^2 \otimes K_k$ (H.19.3). For finite V this is equivalent to purity against finite ancillas (H.19.4; Lean: `isPure_iff_isPureHilbert`, H.20.1). In the process-matrix framework, ancillas of any cardinality are allowed by `IsValidPMInf` and `IsPurePMInf`, which agree with the finite-ancilla notions (`isValidPMInf_iff`, `isPurePMInf_iff`, H.20.4). Standard [14, 17].
- **Antinomic** → *Nomic, antinomic*.

- **Audit (completeness audit).** A separate check that an exhaustive search covered everything it claims to cover. It recounts the cases (here, recomputing the orbit key of all 21,906 labelled geometries) and matches them against the search's checkpoint records. For glue_k4 it found all 2,722 canonical geometries done, with 0 candidates and 0 UNRESOLVED (glue_k4_audit.py). Defined in H.26.1; explained in H.26.1a(d). Paper's own usage.
- **Baumeler–Wolf polytope** → *Valid (polytope)*.
- **Board** (U_o, also written C_o; "the board"). In a Switchboard, $U_o := C_o$ is the 8×8 unitary that the joint output o applies to the source (H.8 notation). In H.12, "eight 8×8 boards" means the eight U_o. Elsewhere "a board" means the whole family $\{U_o\}_{o\in\{0,1\}^3}$, as in "X-type board" and "≤3-term board". Defined in H.8, H.17 preamble. *Usage note:* the paper's own term, not used in the literature. See also *Switchboard*; *Admissible board*; *Term*.
- **Canonical representative; orbit key.** For a finite set acted on by a symmetry group, the *orbit key* of an element is the lexicographically smallest of its images, so two elements are in one orbit exactly when their keys are equal. The *canonical representative* of an orbit is one fixed member: in glue_k4canon.py, the first geometry in enumeration order with that key. A search over canonical representatives is complete when every orbit member has the same answer, which holds for symmetries of the problem (H.17.15(d)). Defined in H.17.17; explained in H.26.1a(b). Standard technique.
- **Candidate, job, UNRESOLVED** (search outcomes). In the exact searches of H.17.13–H.17.17, a *job* is one assignment of classes (or labels) and pair supports, handed to an exact finite-domain solver. A *candidate* is a complete assignment that passes every search filter. Each candidate is then checked against the full test (H.17.11a) and the hull facets. A job is *UNRESOLVED* if the solver's node budget runs out first. A run counts as "clean" when it has 0 candidates and 0 UNRESOLVED. Defined in H.17.15, H.17.17. Paper's own terms. A worked example is in H.26.1a(e).
- **Causal box.** A quantum system that receives and emits messages at positions of a partially ordered set, closed under composition [42]. Mentioned in H.18.4 as a framework the paper does not use.
- **Causal correlations; dynamic-order causal polytope.** Correlations P(i|o) between the parties' outputs o and inputs i that can arise with a possibly dynamical causal order: a party acts first, and its output can decide the order of the rest. For three binary parties they form a polytope with 138,304 deterministic vertices. Defined in H.15.7a. Sources: [14] for two parties; [52, 53] for the multipartite definition and polytopes. See also *Causal inequality*.
- **Causal inequality.** A linear inequality satisfied by every causal correlation. Its violation certifies that no causal order explains the data. The paper's inequalities have integer coefficients and minimum 0 over the 138,304 deterministic causal strategies. They are certified by LP plus an exact rational Farkas vector. Defined in H.15.7b, H.15.7d. Source: [14]; for the polytope approach, [53].
- **Causally separable; classically causally separable.** A quantum process is causally separable if it is a mixture of processes with a definite or recursively dynamical order [14, 52, 55]. The paper's *classically causally separable* is a classical process that is a convex combination of processes, each with some party first with valid conditionals. Defined in H.1. *Usage note:* this is the diagonal (classical) analogue of the recursive definition of Wechs, Abbott and Branciard [55, Def. 5] and of the extensible causal separability of [52]. It is not the quantum notion. See also *First party*.
- **Choi matrix; Choi vector** (J_A; $|U\rangle\rangle$). The Choi matrix of a linear map A on L(H) is $J_A = \Sigma_{ij} |i\rangle\langle j| \otimes A(|i\rangle\langle j|)$. Choi's theorem says A is completely positive iff $J_A \geq 0$ [48]. For a unitary U, J is $|U\rangle\rangle\langle\langle U|$ with $|U\rangle\rangle = \Sigma_i |i\rangle \otimes U|i\rangle$. Defined in Appendix A (Lean: `PFUL.Choi.isCP_iff_choi`); used in Lemma D.1 and Appendix F (countable alphabets). In the process-matrix framework of H.19.1, a local operation is

CPTP iff its Choi matrix $C \succeq 0$ and $\Sigma_b C((a,b),(a',b)) = \delta_{aa'}$ (`PFUL.PM.IsCPTPChoi`, `isCPTPChoi_choiOf_iff`). The counterexample's Choi vector is `choiVec Vsb`, and its process matrix is `choiMat Vsb` = $|Vsb\rangle\rangle\langle\langle Vsb|$ (H.19.2). For channels with infinite ancillas the Choi operator is not trace class, and the Kraus/kernel form is used (H.19.5). Round 13 allows Choi kernels on ancillas of any cardinality (`IsCPTPKer`: PSD finite sections, unconditional partial trace; H.20.4).

- **Class** (κ; V_κ). *Usage note:* the word has several meanings in the paper, depending on the section.
  - (a) In H.17.9 and H.17.15(a), a class is a generator tuple: () for V = 1, (A) for a two-term class α + iβA, and (A, B) with A, B anticommuting for a three-term class α + i(βA + γB). There are 1,071 non-identity classes, 1,072 with the identity.
  - (b) From H.17.16 on, a class is a unitary up to a left Pauli: $U_o = P_o V_\kappa(o)$. Two classes can then share a generator tuple, and in H.17.17 that tuple is called the class's *label*.
  - (c) In H.10.6, H.14.1 and H.17.8, the classes are the blocks of a partition κ of the outputs o.
  - (d) "Symmetry classes" of boards (H.10.4, H.13.3, H.14.2) are orbits of boards under the symmetry group, and "LP classes" in D.7 are classes of facets.
  - See also *Label*; *Orbit*; *Tuned*.
- **Class bound** (Theorem H.17.17). An admissible ≤3-term board has at most four classes, in sense (b) of *Class*. With exactly four, each class is one cube edge along its unique rigid direction. Proved in H.17.17; also checked in Lean (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/PFUL/LemmaH.lean), under hypotheses stated there. See also *Rigid qubit*; *Geometry*.
- **Class-constant selection.** Given a partition κ of the outputs, a selection that picks for each output o an input string from a set that depends only on the class κ(o). The coset-transport theorem needs every class-constant selection to be a PF. Defined in H.10.6, H.17.8(a). Paper's own term. See also *Coset transport*.
- **Classical process** (p(i|o); also W diagonal). A conditional probability p(i|o) of the parties' inputs i given their outputs o, such that for every tuple of local deterministic interventions $f_k: I_k \to O_k$ the total probability Σ_i p(i|f(i)) equals 1. Equivalently, a process matrix that is diagonal in the computational basis. Validity under all stochastic interventions follows because the condition is multi-affine (H.12.2). Defined in the Appendix H preamble, D setting, H.17.5. *Usage note:* this is Baumeler and Wolf's "logically consistent classical process" [15]. See also *Valid (polytope)*; *PF (process function)*.
- **Classical restriction; reading a process in a frame.** Decohere the agent wires (and fix bases on P and F) of a pure process in a chosen local basis, the *frame*, and record the result as a classical process. The H.13.2 board read in the Hadamard frame gives a classical process outside conv(PF), and read in the computational frame it gives one inside. Defined in H.15.8, H.15.9(B). Paper's own phrasing. See also *Frame*.
- **Classical multiple-use model.** A classical acyclic network in which each agent's classical instrument may be run more than once (once per possible input value, by separate sub-agents), and a central node decides afterwards which run counts. It reproduces every valid classical process (H.21.6(a)), so it says nothing about purity. Defined in H.21.6. See also *Single-use realisation*; *Fine-grained causal model*.
- **Classical-output pure process (COPP)** (U_o). A pure process $V|s\rangle_P|o\rangle_{AO} = (U_o|s\rangle)_{AI}|o\rangle_F$ whose future records the agents' outputs, with one unitary U_o on the agents' input qubits for each output triple. It is valid iff $\Sigma_o U_o\dagger(\otimes_k M^{k}_{o_k})U_o = 1$ for all binary POVMs. Equivalently, an alternating sum over every nonempty set of parties vanishes, and in particular no agent's output can reach its own input. PF phase boards and forward PF lifts are COPPs. Defined in H.29.1. Paper's own term. See also *Phase-process component*.
- **Classically controlled board.** A qubit board $i_k = U_{k,\, o_{\{-k\}}}\, s_k$ in which each party's unitary is selected by the other parties' classical outputs. It is valid for two-valued Lugano routing and, numerically, invalid for every other control pattern tested (H.24.2, Round 17). Paper's own term. See also *XOR board*.

- **Coset transport** (Pauli coset-transport theorem). Suppose a board can be written $U_o = X^{a(o)}G_\kappa(o)$, where κ partitions the outputs and each G_κ is a unitary in the span of $\{X^h : h \in H_\kappa\}$ for a subgroup H_κ (H.10.6); H.17.8(a) allows a monomial in place of $X^{a(o)}$. If every class-constant selection is a PF, then $p_\varphi \in$ conv(PF) for every source state. Proved in H.10.6, H.17.8(a); the right-absorbed version is H.17.11(a). Paper's own theorem. See also *SH, SH⁺, SH⁺⁺, SH_grp, SH_grp^r*.
- **Countably controlled (measurable process function).** Like *finitely controlled*, but each output space may split into countably many cells, so w can take infinitely many values (example: Lugano on the parities of the integer parts, with unbounded odd translations, F.5.10). The closed loop $M = \Sigma_c \otimes_k P_{c_k} V_k S_{\omega_k(c)}$ is then a strongly convergent series and is unitary (F.5.10, Round 16). Paper's own term. See also *Finitely controlled*.
- **Cube, vertex, edge, direction** ($o \in \{0,1\}^3$; e_p; $D(o,o')$). For three binary parties, the joint outputs o are the vertices of a cube. An edge along direction e_p joins o and $o \oplus e_p$, which differ in party p's output only. $D(o,o') := \mathrm{supp}(o \oplus o')$ is the set of parties whose output changed. A string x *covers* D if $x \wedge D = D$. Defined in H.8 notation, H.17. Standard combinatorics; the terminology is the paper's own.
- **D-CTC, P-CTC.** Deutsch's self-consistent model of closed timelike curves [10] and the postselected model [13], compared with process functions in Section 4 and H.15.1.
- **Deterministic intervention** ($f_k: I_k \to O_k$). A local function from a party's input to its output. A process function gives exactly one consistent history for every tuple of them. Defined in Section 1. Source: [15, 16].
- **Deterministic-extrema polytope** → *PF hull*.
- **Dual certificate; Farkas vector; inertia certificate.** An exact witness that an optimum or an infeasibility is what is claimed. Examples:
  - rational multipliers y for the 72 validity equalities, showing that orbit 92 holds on all of Valid (H.17.5);
  - an integer Farkas vector certifying a causal inequality (H.15.7b);
  - rounded Hermitian Lagrange multipliers with an exact LDL^T check, bounding the NS and PPT relaxations (H.15.9(C′));
  - exact Hermitian inertia arguments showing that E_{ex1} and vertex orbits 7 and 50 are not purifiable (C.2).
  - Standard LP and SDP duality; the specific certificates are the paper's own.
- **E_{ex1}** (= (C + C̄)/2). The three-party valid classical process of Baumeler and Wolf [15] that lies outside conv(PF). It is the uniform mixture of the circular identity channel C ($x_1 = a_3$, $x_2 = a_1$, $x_3 = a_2$) and its bitwise negation C̄, both logically inconsistent deterministic processes (Appendix C). The paper proves it is not purifiable (C.2). See also *Vertex orbit*.
- **EXACT-CERTIFIED** → *Result labels*.
- **Exclusivity lemma; pairwise exclusivity.** If w is a process function, then for every pair of outputs $o \neq o'$ some party k whose output changed ($k \in D(o,o')$) has the same input, $w_k(o) = w_k(o')$. Proved in Section 1 (Lemma). The converse, that pairwise exclusivity characterises PFs, is Dourdent et al. [23, Thm 7] (Section 1, "Converse"); for three binary parties it is checked exhaustively in H.10.3. The Pauli rule is its operator version (H.8.1).
- **Facet; facet inequality; facet operator; relative violation** ($g\cdot p + g_0 \geq 0$; $F = \Sigma\, g[i,o]P_{o,i} + g_0$).
  - A *facet* is a facet of the PF hull, written $g\cdot p + g_0 \geq 0$, modulo the 27 independent validity equalities. For three binary parties there are 29,344 facets in 93 orbits (D.7). Facets are numbered by their index in the computed list (e.g. facet 1741, the H.12 certificate, and facet 16962, the H.13.2 certificate) and orbits by 0–92 (e.g. orbit 82, the class-0 inequality of D.7).

    - The *facet operator* $F = \Sigma_{o,i}\, g[i,o] P_{o,i} + g_0$ evaluates a facet on a Switchboard as an operator on the source (H.8, H.10.4).
    - The *relative violation* is the violation divided by the facet's range on PFs (H.13.3, Appendix J).
    - See also *Orbit*; *Never-crossed orbit*; *Genuine orbit*.
- **Families A, B, C; Ring, Chorus, Switchboard, Shadows.** The three families of three-party binary purifications without an operator-first party found in H.7:
    - A: single-PF lifts of the 64 Lugano-orbit PFs (informal name: the Ring);
    - B: coherent blends of causal orders, the C.1 lift of a blend of three causally ordered PFs with different first parties (the Chorus);
    - C: the Switchboard.
    - A fourth informal name, the Shadows, refers to the numerical purifications lug_21–23. The names are listed in H.7 and used in graded.md, Section 58e. Paper's own names. See also *Switchboard*; *Lugano process*.
- **Fine-grained causal model.** A causal model whose nodes are finer than the parties' laboratories (individual systems or sectors), used to ask whether a process can be embedded in an acyclic spacetime. Discussed in the H.15.7 setting. Sources: Vilasini and Renner [32, Thm 5]; Vilasini and Colbeck [33, 34]; sector-level structure, Ormrod, Vanrietvelde and Barrett [46]. See also *Routed graph*; *QC-QC*.
- **Fine-tuned.** In Baumeler and Wolf [15], a classical process is fine-tuned if it lies outside the deterministic-extrema polytope, i.e. outside conv(PF). Quoted in this sense in H.15 (setting). *Usage note:* not the same as the paper's *tuned* (H.17.10), and also distinct from fine-tuning in causal-model discovery [33]. See also *Tuned*.
- **Finitely controlled (measurable process function).** A process function w on continuous groups such that each output space splits into finitely many cells and every $w_k(o)$ depends only on which cells the outputs lie in, e.g. the Lugano function lifted to $\mathbb{R}^3$ by threshold sets. For such w the closed loop with arbitrary local unitaries is a finite sum, $M = \Sigma_c \otimes_k P_{c_k} V_k S_{\omega_k(c)}$, and it is unitary (F.5.9). Defined in F.5.9. Paper's own term. See also *Countably controlled* (F.5.10).
- **First party; marginally first; first with valid conditionals; operator-level first.** Three different strengths of "A acts first":
    - *marginally first*: the marginal $p(a|x,y,z) = \Sigma_{b,c}\, p$ does not depend on the outputs (H.1);
    - *first with valid conditionals*: in addition, every conditional $q_{a,x}(b,c|y,z)$ is a valid bipartite classical process (H.1);
    - *operator-level first* in a purification V: $V = (V' \otimes 1_{I_A})(S \otimes 1_O)$, where $S: P \to I_A \otimes R$, so A's input is produced before any output is read (H.6).
    - Operator-first implies first with valid conditionals (H.6). Marginally first does not (H.5). Paper's own definitions, modelled on [52, 55]. See also *Last party*; *Causally separable*.
- **Fixed-order process; relativistic causality.** A process compatible with one fixed causal order of the parties, as tested in H.15.6 over the 6 orders. Relativistic causality in the sense of Vilasini and Renner [32] (H.15.1).
- **Forward PF lift; PF-wired box.** A board $V|s\rangle_P|a\rangle_{AO} = (\otimes_k U_{k,w_k(a)})|s\rangle_{AI}|a\rangle_F$ built from a process function w, with arbitrary node unitaries, node-wire dimensions and source; the future F records the agents' outputs. Its statistics are those of a quantum box whose settings are wired by a refined PF, $x = w'(o)$ (a *PF-wired box*). No PF-wired no-signalling box crosses the ten open orbits (Theorem H.27.1). Defined in H.27.1. Paper's own term. See also *Refined process function*; *Time-reversed PF lift*.

- **Frame** (computational, Hadamard; Hd). A choice of local bases on the agent wires in which a pure process is read classically. Hd = $H^{\otimes 3}$ is the three-qubit Hadamard. Defined in H.15.8, H.15.9(B). *Usage note:* "frame" is the paper's word, not the literature's reference frame or "causal perspective" [44]. See also *Classical restriction*; *LU-equivalent*.
- **G_{48}** (= $(\mathbb{Z}_2)^3 \rtimes S_3$). The symmetry group of the three-qubit Pauli-rule problem used to reduce class searches. An element g = (π, m) acts on a Pauli string (x | z) by z ↦ z ⊕ (x ∧ m) followed by the qubit permutation π. It maps admissible boards to admissible boards. The 1,071 non-identity classes fall into 61 orbits under G_{48} (9 two-term, 52 three-term). Defined in H.17.15(b), (d). Paper's own construction.
- **G_φ path.** The one-parameter family V_φ of pure X-type boards obtained by replacing √X in Theorem H.21.2 with $G_\varphi = \tfrac{1}{2}(1+e^{i\varphi})\cdot 1 + \tfrac{1}{2}(1-e^{i\varphi})\cdot X$. It runs from a PF blend (φ = 0) through H.12 (φ = π/2) to φ = π ($G_\pi = X$), a frame-rotated time reverse of the Lugano process with the H.13.2 maximal violation 0.1404. Defined in H.21.7. See also *Lugano family (VOKB)*.
- **Generalised Lugano board** (L_{U_A,U_B,U_C}). $|s\rangle_P|o\rangle_{AO} \mapsto (U_A{}^{\text{lug_A(o)}} \otimes U_B{}^{\text{lug_B(o)}} \otimes U_C{}^{\text{lug_C(o)}})|s\rangle_{AI}|o\rangle_F$ with arbitrary qubit unitaries in all three nodes, used with or without time reversal and with local frames on every agent wire. A fleshing-out of VOKB's Lugano graph, hence valid. When each U_k has eigenphase gap π it is locally equivalent to the Lugano purification. Defined in H.22.2. See also *Lugano family (VOKB)*.
- **Generalized switchboard.** $V|o, s, t\rangle = \Sigma_e |e\rangle_I |o\rangle_{F1} \otimes (C_o(s))_e \otimes |e \oplus t\rangle$, where each C_o: S → I ⊗ F′ is unitary and F′ is an extra sink. It is pure iff every 8×8 block of C_oC_{o′}† satisfies the Pauli rule. Defined in H.11.2. Paper's own term. See also *Switchboard*.
- **Generic; generic-support model.** A ≤3-term board is generic if the Pauli support of every ratio U_oU_q† is the full product support of the two classes, with no cancellations. The *generic-support model* assumes this throughout. SH_grp holds for every admissible board in this model, by exhaustive exact enumeration. Defined in H.17.9. Paper's own term. See also *Tuned*.
- **Genuine orbit (of facets).** One of the 22 never-crossed facet orbits that are not positivity. Orbit 92, the remaining never-crossed orbit, is positivity, and holds on all of Valid (exact dual certificate). Twelve of them were crossed in Round 15 (H.22.2): orbits 4–11, 14, 25 by a framed time-reversed Lugano board, and 53, 79 by a generalised Lugano board. Three more (26, 30, 31) were crossed in Round 21 by PF phase boards (H.28.1), so 7 remain open: 28, 54, 57, 66, 69, 75, 81 (unchanged after Rounds 22 and 23, H.29, H.30; Round 23 proves them on all non-Lugano families, Theorem H.30.2). Defined in H.17.5, H.17.15(e); listed in J.1. Paper's own term. See also *Never-crossed orbit*.
- **Geometry (labelled, canonical).** For the four-class search, a labelled geometry gives the class at each of the 8 cube vertices and each class's label, subject to the class bound and Lemmas A and B. There are 21,906 labelled geometries, and 2,722 canonical geometries up to cube translations × G_{48}. Defined in H.17.17. Paper's own term.
- **Hadamard frame** → *Frame*.
- **Hard board.** A complete, admissible ≤3-term board that has a genuine three-term class and no operator-first and no operator-last party. These are the boards that H.1 and H.6 do not already reduce to PF blends. Defined in the H.17 preamble. *Usage note:* the leaf test of the four-class search (H.17.17) uses "no W-level-last party" in place of "no operator-last party". Paper's own term.
- **Instrument** ($\{A_k{}^{a_k}\}$). A family of completely positive maps, indexed by a classical outcome a_k, whose sum is trace preserving. Defined in Appendix A Step 4. Source: Davies and Lewis [54]; in the process-matrix setting [14].
- **Intersected lift (lift-A ∩ lift-B).** Two lifted relaxations imposed together (H.23.3): lift-A and lift-B families, each with its own constraints, linked by equality of the no-signalling families they induce on (A,

B, C). Each is a relaxation of the set of instrument strategies, so the intersection is a tighter one. For y_A on H.12 it certifies −1.16564 (exact integer certificate), against −1.20330 for lift-B alone. With lift-C added as well (lift-A ∩ lift-B ∩ lift-C, H.26.2), it certifies −1.15861. Paper's own construction, in the spirit of NPA-type hierarchies. See also *Lifted relaxation*; *Lift-B, lift-C*.

- **Jordan decomposition** ($S = S^+ - S^-$). For a self-adjoint trace-class operator S, $S^{\wedge}\pm = ½(|S| \pm S)$ are positive and trace class, with $S^+ - S^- = S$ and $\mathrm{Tr}\, S^+ + \mathrm{Tr}\, S^- = \|S\|_1$. Standard; formalised from Mathlib's continuous functional calculus in `PFUL.TraceClass.jordan` (H.23.2).
- **$K_{o,o'}$** (= U_oU_{o′}†). The ratio of two boards. The Switchboard is pure iff each $K_{o,o'}$ obeys the Pauli rule for D(o,o′). Defined in H.8 notation. *Usage note:* not the Klein group K. See also *Pauli rule*.
- **Klein group; Klein cluster** (K = {1, A, B, AB}; KC). For a three-term class $\alpha + i(\beta A + \gamma B)$, K is the set of Pauli strings {1, A, B, AB} up to phase, a copy of $(\mathbb{Z}_2)^2$. Its support is K minus AB. A *Klein cluster* KC is the set of six classes built from one Klein group: (A), (B), (AB), (A,B), (A,AB), (B,AB). Klein groups fall into 21 G_{48}-orbits ("K-orbits"). Defined in H.17.12(a) (Klein group) and H.17.16 (cluster). Searches confined to one cluster: k = 4 (H.17.16), k = 5 (H.17.16b–c, finished, a consistency check of the class bound). Paper's own terms for a standard group.
- **Krawczyk test.** An interval-arithmetic test for a system F(z) = 0. Take a point $\tilde{z}$, a matrix $C \approx J(\tilde{z})^{-1}$ and a box X around $\tilde{z}$, and put $K(X) = \tilde{z} - C\,F(\tilde{z}) + (1 - C\,J(X))(X - \tilde{z})$. If K(X) lies in the interior of X, then X contains exactly one zero of F. Used in H.25.2 to certify the exact H.12 critical point. Standard (Krawczyk 1969).
- **Label.** In H.17.17, a class's Pauli support type (), (A) or (A, B). Different classes can share a label if their parameters differ. *Usage note:* in H.17.9 and H.17.15 the label is what is called a "class" (meaning (a) of *Class*). See also *Class*.
- **Last party; W-level last; operator-last.** Party A is *last* (or *W-level last*) if p does not depend on A's output x (H.1). Then p is a PF blend with A last (Theorem H.1). A party is *operator-last* in a Switchboard if every $K_{o,o\oplus e_A}$ is a scalar, so its output influences no input at the operator level (H.8.3). See also *First party*.
- **Lemma A, Lemma B, Lemma C.** Necessary conditions on the support S_{xy} of V_yV_x†, for classes x ≠ y at adjacent vertices.
  - *A*: |S| ≥ 2.
  - *B* (p-constant): across an edge along p, every string of S has the same qubit-p part.
  - *C* (triple consistency): for every triple x, y, z of classes, $S_{xz} \subseteq S_{xy} \oplus S_{yz}$.
  - Defined in H.17.16 (Lemma B at "p-constant"); C is also in H.17.15. Paper's own lemmas. See also *p-constant*.
- **Lemma D (failure witnesses are local).** Whether the refined test SH_grp^r fails at a pair of vertices depends only on the classes at the two vertices and at the absorbed vertex, so on at most three classes. Proved in H.17.17. Paper's own lemma.
- **Lemma H (rigid directions).** Every non-identity ≤3-term class has a rigid qubit. If p is rigid for the class at o, then $o \oplus e_p$ carries the same class. Proved in H.17.17; also checked in Lean (https://github.com/drewarrowood/process-function-unitary-lift/blob/main/lean/PFUL/LemmaH.lean), under hypotheses stated there. Paper's own lemma. See also *Rigid qubit*; *Class bound*.
- **Lift-B, lift-C.** The lifted relaxation of H.21.8 with party B (respectively C) as the copied party, obtained by an exact relabelling of the parties. For y_A on H.12, lift-B gives the best certified single-lift bound, −1.20330 (the intersection with lift-A gives −1.16564, H.23.3; see *Intersected lift*); lift-C is weaker (about −1.30, not certified). Defined in H.22.1. See also *Lifted relaxation*.

- **Liftable.** Used in Appendix I only, informally, for "purifiable". "Approximately liftable" there means a small purity residual. *Usage note:* informal; the defined notion is *Purifiable*. See also *Unitary lift*.
- **Lifted relaxation (lifted-A).** A relaxation of the set of instrument products in which one party's measurements for both of its settings act on two copies of its system, so that they must coexist in one positive operator. It is at least as tight as the NS relaxation. For H.12 lifting A certifies $y_A \geq -1.27720$. Lifting B instead (lift-B) certifies $y_A \geq -1.20330$ (H.22.1). Defined in H.21.8. See also *Lift-B, lift-C*. See also *NS relaxation; PPT relaxation*; *Dual certificate*.
- **Link product** ($*$). The composition of operators in the Choi picture, $G_A = W * (A_1 \otimes \ldots \otimes A_n)$: a partial trace over the shared spaces, with a partial transpose. Used in Appendix A. Source: Chiribella, D'Ariano and Perinotti [49]; in the form used here, [17, Sec. 2]. Lean: `PFUL.PM.link`, written in indices (H.19.1). For pure local operations, $|V\rangle\rangle\langle\langle V| * |A\rangle\rangle\langle\langle A| = |\text{compose } V\ A\rangle\rangle\langle\langle \text{compose } V\ A|$ (`link_choiMat_vecOp`). Its entries are finite sums over W's wires, so it is also defined for local kernels on ancillas of any cardinality; positivity and trace preservation carry over (`link_posSemidef_any`, `isValidPMInf_iff`; H.20.4). This is an entrywise (kernel) link product, not an operator identity for non-trace-class Choi operators.
- **LU-equivalent.** Two pure processes are LU-equivalent if one becomes the other under a unitary on each of the eight systems (P, F, AI_k, AO_k) and a permutation of the parties. Spectra of reduced states are LU invariants. Defined in H.15.9(B). Standard notion; the precise scope is stated there.
- **Lugano process; Lugano function; Lugano orbit** (w(a,b,c) = (¬b∧c, ¬c∧a, ¬a∧b)). The three-party binary process function of Section 4: each party's input is "the next party's bit is 0 and the one after is 1". It has no causal order and violates causal inequalities. The *Lugano orbit* is its orbit of 64 PFs under relabellings: family A of H.7. Source: Baumeler and Wolf [15, 30]; as a process matrix, the Araújo–Feix process [17, 37]. *Usage note:* the paper also calls it the AF/BW process (H.15.9, H.18.4a). See also *Time-reversed Lugano process*.
- **Lugano family (VOKB); √X-Lugano process** (L_U; L_G, $G = \sqrt{X}$). For a qubit unitary U, L_U: $|s\rangle_P|o\rangle_{AO} \mapsto (X^{\text{lug_A(o)}} \otimes U^{\text{lug_B(o)}} \otimes X^{\text{lug_C(o)}})|s\rangle_{AI}|o\rangle_F$ is the Lugano purification with Bob's flip X replaced by U. So L_X is the Lugano purification L, and L_G with $G = \sqrt{X} = h\ S\ h = \tfrac{1}{2}[[1+i, 1-i], [1-i, 1+i]]$ is the √X-Lugano process. These are fleshings-out of VOKB's Lugano routed graph with "arbitrary operations (as long as they follow the routes)" [18, Sec. 4.3]. H.12 is the frame-rotated time reverse of L_G (Theorem H.21.2), as H.13.2 is of L_X (H.15.7e.2). Defined in H.21.2. Source: VOKB [18] for the family; the identification with H.12 is the paper's own. See also *Lugano process*; *Time-reversed Lugano process*; *Routed graph*.
- **Lugano-type family** (component or rule). One of the 8 phase-process components 7–10 and 22–25 (H.29.3), or one of the 8 refined PFs 4, 5, 6, 7, 10, 11, 14, 15 whose block counts are (2,2,2) (H.27.1), with its time-reversed lifts. Every known crossing of a genuine orbit lies on such a family. They are the only families whose statistics span is the whole space. Off them, the ten H.27 orbits hold (Theorem H.30.2). Paper's own term. See also *Statistics span*; *Phase-process component*.
- **MECC** (mutually exclusive control conditions). A sufficient condition under which Daher Ahmed and Kunjwal [24, Thm VII.1] prove that a process function can be purified. Their Conjecture VII.1, that every PF can be purified, is what Section 1 settles for finite alphabets. Cited in Section 6 (opening).
- **Moment relaxation (Lasserre level 2); SOS certificate.** For a polynomial f on a set cut out by polynomial equalities (here the six unit spheres), replace the monomials by moment variables. Require the 190×190 moment matrix of all monomials of degree ≤ 2 to be positive semidefinite and the localised equalities to hold. The minimum is a lower bound on min f. Its dual is a sum-of-squares identity $f - \lambda = m^T G m + \Sigma\ h_i\ g_i$, which can be rounded to exact rationals and verified (H.26.3). Standard (Lasserre 2001; Parrilo 2003).

- **Monomial; X-monomial; phased permutation.** A monomial matrix is a permutation matrix times an invertible diagonal matrix. For a unitary, the diagonal is phases: a *phased permutation*. An X-monomial is a monomial whose permutation is a single X-string X^a, and a is then its X-part (H.17.11a). Defined in H.8.4; used in D.3 (phased-permutation form), H.7, H.15.8. Standard notion. *Usage note:* "phased permutation" is the paper's wording. See also *Coset transport*.
- **Never-crossed orbit.** A facet orbit never violated by the X-type $\mathbb{Z}_4$ (386 symmetry classes) and $\mathbb{Z}_8$ (10,603 classes) boards, maximised over source states [numerical]. There are 23 (Appendix J.1). With orbit 92 removed, these are the genuine orbits. The name is historical: fifteen genuine orbits are crossed by pure non-X boards (twelve in H.22.2, three in H.28.1), and seven remain open. Defined in J.1, H.17.5. Paper's own term. See also *Genuine orbit*. Round 16 (H.23.1a): every facet of the twelve crossed orbits is violated on Purif.
- **No-signalling box (NS box)** (P(i|x)). A table of conditional distributions of the parties' outcomes i given their settings x whose marginal for any subset of parties does not depend on the other parties' settings. Quantum boxes (shared state, local measurements) are NS boxes; the NS boxes form a polytope whose affine hull is spanned by the local deterministic boxes. Used in H.27.1. Standard (Popescu–Rohrlich; Barrett et al.).
- **Nomic, antinomic.** In Kunjwal and Oreshkov [36], correlations are *nomic* if they arise from classical processes in conv(PF) with arbitrary classical local operations, and *antinomic* otherwise. Discussed in H.13.5 [CITED].
- **NS relaxation; PPT relaxation.** Relaxations of the set of local instruments, used to bound how far H.12 can violate a causal inequality y·P. The product $E^A \otimes E^B \otimes E^C$ is replaced by any family $Z_{ao|x} \geq 0$ whose sums obey the linear constraints that products obey (NS: normalisation, and each party's marginal independent of its setting); PPT adds $Z^{T_k} \geq 0$. Minimising over the relaxation gives a lower bound on y·P for all instruments. Defined in H.15.9(C), with exact dual certificates in (C′). Standard relaxations; their use here is the paper's own.
- **OPEN** → *Result labels*.
- **Operator-first, operator-last** → *First party*; *Last party*.
- **Orbit.** *Usage note:* "orbit" refers to several group actions in the paper.
  - *Facet orbits*: 93, under the 384-element group of party permutations and input and output relabellings (D.7). This group maps Purif onto itself, so a facet orbit is crossed on Purif either in every facet or in none (Proposition H.23.1a).
  - *Vertex orbits* of Valid (C.2–C.3).
  - The *Lugano orbit* (64 PFs, H.7).
  - *Class orbits* under G_{48}: 61 (H.17.15).
  - *K-orbits*: 21 (H.17.16).
  - *Geometry orbits*: 2,722, the orbits of the 21,906 labelled four-class geometries under cube translations × G_{48} (H.17.17, H.26.1a).
  - Facet orbit numbers and vertex orbit numbers are separate numberings: "orbit 7" in C.2 is a vertex orbit, "orbit 82" in D.7 a facet orbit.
- **P, F (global past and future); source and sink.** The extra wires of a process matrix: P carries the initial state into the process, and F carries the final state out. In the Switchboard, the source state φ is on P and the register F records the outputs. Sources: global past and future, [17]; source and sink regions, [16]. See also *Source state*.
- **p-constant.** A set S of Pauli strings is p-constant if all its strings have the same qubit-p part. Lemma B says the ratio support across a class-changing edge along p is p-constant. Defined in H.17.16, restated in

H.17.17. Paper's own term.

- **Pauli rule** ($K \in A_D$). For $o \neq o'$, $K_{o,o'} = U_oU_\{o'\}\dagger$ lies in A_D, the span of the operators that act trivially on at least one party in D(o,o′). Equivalently, no Pauli string in the support of K is non-identity on every party of D. For an X-type string X^x Z^z this means $(x \wedge D) \neq D$. In general a string (x | z) is forbidden when $((x \mid z) \wedge D) = D$ (H.17.15(d)). Proved equivalent to purity in H.8.1. Paper's own name. *Usage note:* it is the operator form of the exclusivity lemma. See also *Exclusivity lemma*; *Admissible board*.
- **Pauli string; support; X-part; qubit-p part** (X^a Z^b; supp V; x(P)). A three-qubit Pauli string, written X^aZ^b with $a, b \in F_2^3$ (up to phase). The *support* of an operator V is the set of strings with nonzero coefficient in its Pauli expansion. The *X-part* of X^aZ^b is a. Its *qubit-p part* is its single-qubit factor on p (one of I, X, Y, Z). Defined in H.8.1, H.17.15(a), H.17.17. Standard.
- **Penalty search (projector residual).** A numerical search over all unitaries V: P ⊗ AO → AI ⊗ F in which validity of $\mathrm{Tr}_F|V\rangle\rangle\langle\langle V|$ is not built in but penalised by the residual $\|\Pi_V\, W - {}_{(}\mathrm{all}_{)}W\|^2$ of the Araújo et al. (2015) validity projector, with a growing weight. A run says something only if the residual reaches zero (H.23.1). Paper's own usage.
- **Per-class-pair model; over-approximating supports.** The search model of H.17.13–H.17.17. Each pair of classes is given every support its two classes can produce (H.17.12), filtered by Lemmas A–C. This list contains every actual support, and possibly more ("over-approximating"), so a clean search proves the claim for every board whose pair supports are in the list. The class-bound results and the four-class search are PROVED in this model. Paper's own model.
- **PF (process function)** ($w: \prod O_k \to \prod I_k$). A map w from joint outputs to joint inputs such that for every tuple of local functions $f_k: I_k \to O_k$, the equation i = w(f(i)) has exactly one solution. Defined in Section 1. Sources: Baumeler and Wolf [15]; Baumeler, Costa, Ralph, Wolf and Zych [16]. Lean: `PFUL.IsProcessFunction` and, for the counterexample, `PFset` (H.12.3).
- **PF blend.** A convex combination of process functions, i.e. a point of conv(PF). Paper's own wording. See also *PF hull*.
- **PF hull** (conv(PF)). The convex hull of the process functions, viewed as 0/1 classical processes. For three binary parties it has dimension 37, 744 vertices and 29,344 facets (D.7, H.8). *Usage note:* Baumeler and Wolf [15] call it the *deterministic-extrema polytope*. See also *Facet*; *Valid (polytope)*.
- **Phase board; PF phase board** ($\theta_k(o_k, x)$; w′). A qubit phase process $V|z\rangle_P|o\rangle_{AO} = \exp(i \Sigma_k \theta_k(o_k, w'_k(z_{-k})))|z\rangle_{AI}|o\rangle_F$, read with SU(2) frames on the agents' inputs. Each agent's phase depends on its own output and, through a refined PF w′, on the other agents' inputs. It is the time-reversed PF lift with qubit node wires and diagonal node unitaries, so it is pure. Phases not routed through a refined PF generally give invalid boards. H.12 is a PF phase board with phases in multiples of π/2 (w′ = index 14). Continuous phases cross orbits 26, 30 and 31 (Theorem H.28.1). By Lemma H.29.2a, phase boards are the extreme points of the time-reversed PF lifts on every rule whose parties have at most three blocks. Defined in H.28.1. Paper's own term. See also *Phase process; phase form*; *Time-reversed PF lift*.
- **Phase-process component** ($\varphi = N\, y$). One of the 34 maximal valid families of three-qubit phase processes $\varphi(o, z) = \Sigma\, x_m \cdot$ (mixed monomial). Each is a subtorus cut out by one-way-influence conditions: for every pair of agents and every setting of the third, one of the two does not influence the other. Eight are Lugano-type PF phase boards. Eight are new and use the monomials $o_j\, o_k\, z_l$, in which two outputs jointly steer a phase on the third input. Eighteen are five-dimensional mixtures. Classified in H.29.3 (made exact in H.30.3: these 34 subtori are all the valid three-qubit phase processes), searched in H.29.4. On the 26 non-Lugano components, the ten H.27 orbits are proved (Theorem H.30.2). Paper's own term. See also *Phase process; phase form*; *Classical-output pure process*; *Lugano-type family*.

- **Phase lift** (U_o^g = Hd · diag($(-1)^{o\cdot g(z)}$) · Hd). A way to build X-type boards from a map g: in the Hadamard frame the board is diagonal, with phases set by g. Defined in H.15.8. Paper's own construction.
- **Phase process; phase form** (D; Φ(o, z)). A pure process of the form D: $|z\rangle_P|o\rangle_{AO} \mapsto \Phi(o,z)|z\rangle_{AI}|o\rangle_F$, with $|\Phi| = 1$: the agents' inputs are a copy of the past, and the agents' outputs only add phases. In Hadamard frames on P and on the agents' inputs, H.12 is the phase process with $\Phi = i^{pre(z)}\,(-1)^{o_A(z_B \vee z_C)}\,i^{o_B\, z_A\, z_C}\,(-1)^{\{o_C\, z_B(1-z_A)\}}$, in which each agent's phase depends only on the other two agents' inputs. Defined in H.21.1. Paper's own term. See also *Phase board*; *Phase lift*; *Frame*.
- **Positive trace-preserving map** (`IsPTP`). A map on the trace class that is linear there, preserves the trace and sends positive operators to positive operators. Complete positivity is not assumed. Every such map is trace-norm bounded ($\|\Phi\| \le 2$ in Lean; = 1 by Russo–Dye, cited), so `IsNormalCPTP` ⇔ `IsCPTP` (H.23.2).
- **Process; process matrix** (W). A positive operator $W \ge 0$ on $P \otimes F \otimes \prod(I_k \otimes O_k)$ such that, for all local CPTP maps A_k with ancillas, the link product $G_A = W * (A_1 \otimes \dots \otimes A_n)$ is CPTP from P to F. Defined in Appendix A. Sources: [14]; with P and F, [17, Sec. 2]. See also *Pure process*; *Valid (process)*.
- **Process function** → *PF (process function)*.
- **PROVED, NUMERICAL, CITED, INTERPRETIVE, OPEN** → *Result labels*.
- **Pure process** ($W = |U\rangle\rangle\langle\langle U|$). A process for which G_A is unitary whenever every A_k is unitary [17, Def. 1]. By [17, Thm 2] a process is pure iff its process matrix is the Choi projector of a unitary. Lean (Round 13): `isPurePM_iff`, for equal local input and output dimensions and |P| = |F| (H.20.2). Used in Appendix A. Lean: `PFUL.PM.IsPurePM` (valid, and the link with local unitaries on any finite ancillas is $|M\rangle\rangle\langle\langle M|$ with M unitary). `isPure_iff_unitaryLink` shows that this agrees with the counterexample's `IsPure`, and `isPurePM_choiMat_Vsb` holds. For infinite-dimensional ancillas see `IsPureHilbert` (H.19.3) and `IsPurePMInf` (H.20.4); both agree with finite purity (`isPure_iff_isPureHilbert`, `isPurePMInf_iff`). See also *Purification*.
- **Purifiable; Purif.** A classical process is purifiable if it has a purification. Purif is the set of purifiable classical processes. It is convex, and conv(PF) ⊊ Purif ⊊ Valid (H.13.1, C.2, H.12.1). Defined in H.13 (Lean: `Purifiable`, H.12.3). Source: AFNB [17, Def. 3]. *Usage note:* the same idea is "unitary extension" or "unitarily extendible" in [36, 45, 18]. See also *Liftable*; *Unitary extension*.
- **Purification** ((V, ψ)). A purification of a classical process p is a unitary V: P ⊗ O → F ⊗ I with a fixed source state ψ on P such that (i) p is the reduced record, $p(i|o) = \Sigma_f\, |\langle i, f|V|o, \psi\rangle|^2$, and (ii) every closing with local unitaries and ancillas gives a unitary. Defined in the Appendix D setting. Source: AFNB [17, Def. 3]; this is the classical-input specialisation used throughout. In process-matrix form, (i) is the Born rule $p(i|o) = \Sigma\, W(\pi,\varphi,(i,o);\, \pi',\varphi,(i,o))\, \psi_\pi\, \mathrm{conj}(\psi_\pi')$ (`inducedP_eq_born`), and (ii) is `IsPurePM W`. Theorem H.12.1 is stated in these terms as `purification_conjecture_false_choi` (H.19.2), and with ancillas of any cardinality as `purification_conjecture_false_choiInf` (H.20.4). See also *Pure process*; *Switchboard*.
- **Purification conjecture.** The conjecture that every purifiable classical process is a PF blend, i.e. Purif = conv(PF). Stated in C.3, refuted by Theorem H.12.1. Its two sub-claims (C1) (Switchboard boards give PF blends) and (C2) (every purification reduces to Switchboard form) are in H.9. Paper's own conjecture. The inclusion conv(PF) ⊆ Purif was asserted in [27] and is proved in C.1.
- **QC-QC** (quantum circuits with quantum control of causal order). The class of processes realisable by quantum circuits with coherently controlled order, defined by Wechs, Dourdent, Abbott and Branciard [51]. Their correlations are causal, so they cannot realise H.13.2 in a single use (H.15.7b).

- **Quantum box** ($P_Q(i|x)$). A no-signalling box of the form $\mathrm{Tr}[\rho \otimes_k M\hat{}k_{i_k|x_k}]$, from a shared state and local measurements. In H.27.1 the statistics of a forward PF lift are a quantum box wired by a refined PF. Standard.
- **Quantum switch.** The two-party process that applies operations A and B in the order AB or BA, coherently controlled by a qubit [50]. The canonical example of indefinite causal order without violation of causal inequalities. Used in H.15.1, H.15.9 (a three-party "3-switch" comparison) and H.18.2. Sources: [50]; reversibility, [43]; causal models, [45, 46].
- **Rayleigh-quotient search.** The H.27.2 optimiser: minimise $\psi\dagger M\psi/\psi\dagger\psi$ jointly in the source ψ and the board parameters, instead of the smallest eigenvalue of M, which stalls on degenerate plateaus; the exact minimum over ψ is reported at the end. Paper's own term.
- **Refined process function** (w'). A map from binary outputs to settings, $x_k = w'_k(o_{-k})$ with up to four values, such that every local 2-colouring of the settings gives a binary PF; equivalently a PF composed with local deterministic output maps. Only the partition of the four values of o_{-k} into fibres matters: there are 186 such partition triples, 20 of them maximal (h20_fwd_enum.log). Defined in H.27.1. Paper's own term.
- **Residual** ($R(U)$; $\rho(U) = \sqrt{R}$). A nonnegative measure of how far a board is from satisfying the purity (Pauli-rule) conditions. $R = 0$ exactly for pure boards. Defined in H.8 and Appendix I, where the trade-off between violation and residual is measured. Paper's own quantity.
- **Result labels** (PROVED, NUMERICAL, CITED, INTERPRETIVE, OPEN; EXACT-CERTIFIED; [proved], [numerical], [cited], [conjecture], [gap], [failed]).
    - PROVED: proved in this paper (by hand, exact arithmetic, exhaustive exact search, or Lean, as marked).
    - NUMERICAL: floating-point or sampled evidence.
    - CITED: taken from a reference and checked against it.
    - INTERPRETIVE: a reading, not a theorem.
    - OPEN: not settled.
    - EXACT-CERTIFIED (or "certified exact"): a numerical result with an exact certificate.
    - Lower-case labels mark the same categories in older sections.
    - Defined in Section 9, the Appendix D and H headers, H.15 and H.18 headers.
- **Reversible extension (classical).** Extending a PF w to an invertible map on (inputs and outputs) × (source and sink), e.g. $U|o, e\rangle = |w(o) \oplus e, o\rangle$, which is a permutation lift. Sources: [16, Thm 2]; [45, Thm 6] for the quantum analogue. Used in Section 6 and D.6. *Usage note:* the paper says "reversible extension"; it does not use "reversible completion". See also *Unitary lift*.
- **Rigid qubit, rigid direction.** A qubit p is rigid for a non-identity class x if the strings in supp V_x have pairwise distinct qubit-p parts. The cube direction e_p is then rigid for x. Defined in H.17.17. Paper's own term. See also *Lemma H*; *Class bound*.
- **Root, leaf (of an exact search).** In the four-class search a *root* is a vertex pair (u_0, w_0) at which the solver requires SH_grp^r to fail for the class of vertex 0. Every counterexample has such a pair, so looping over roots loses nothing. A *leaf* is a complete assignment of the left Paulis that satisfies every constraint, and the leaf test then decides whether it is a candidate. Defined in H.17.17; explained in H.26.1a(c). Paper's own terms.
- **Routed graph; bi-univocal; strong and weak loops; fleshing out.** In Vanrietvelde, Ormrod, Kristjánsson and Barrett [18], a routed graph is a graph with routes (index constraints) on its arrows. It is *valid* if it is bi-univocal and its branch graph has no strong loops, i.e. every loop is weak [18, Sec. 2.4]. Any process obtained by *fleshing out* a valid routed graph is consistent. H.15.7 checks these conditions by brute force [18, Defs 3.1–3.7]. Applied to H.13.2 in H.15.7. CITED.

- **Run budget** (classical model with run budget r). An acyclic classical stochastic network that calls the agents' instruments r times in total, each call time-local, and reports for each agent one of its calls on the announced input. r = 3 (one call each) gives only causal correlations (Lemma H.15.7a); r = 4 (one agent called on both inputs) reproduces every valid three-party binary classical process (H.22.3). Defined in H.22.3. See also *Classical multiple-use model*; *Single-use realisation*.
- **Sector algebra.** For a bipartite unitary process V with past P, the algebra of operators X on P such that X ⊗ 1 commutes with every operator on the agents' inputs pulled back through V. Its central projectors split P into sectors with a definite order ("A first" or "B first"); this is the decomposition of Barrett, Lorenz and Oreshkov [45] and Yokojima et al. [43] that WBO use [41]. For H.12 with U_C fixed it is $M_2 \oplus M_2$ (dimension 8). Defined in H.21.1 (as a computational device). See also *TDS*.
- **SH, SH⁺, SH⁺⁺, SH_grp, SH_grp^r** (support-transport conditions). Sufficient F_2 conditions for a ≤3-term board to be a PF blend.
  - SH (H.17.2): for every pair o ≠ q with D = o ⊕ q, every X-shadow $x(P_o) \oplus x(P_q) \oplus t \oplus t'$, with t, t′ ∈ {0} ∪ X-parts of the class generators, satisfies (x ∧ D) ≠ D.
  - SH⁺ groups o ~ q when U_oU_q† is monomial. SH⁺⁺ first absorbs a common right factor (H.17.2).
  - SH_grp (H.17.8(b)) replaces the shadow by the group H_κ that the X-parts generate. It implies a PF blend (H.17.8).
  - SH_grp^r (H.17.11(a), refined H.17.14) is the right-absorbed version: SH_grp^r for some r implies a PF blend.
  - Paper's own conditions. See also *Absorbed class*; *Coset transport*; *Lemma D*.
- **Shadow; the Shadows.** An *X-shadow* is a string tested by SH → *SH, SH⁺, SH⁺⁺, SH_grp, SH_grp^r*. *The Shadows* are an informal family name → *Families A, B, C*.
- **Sign variant** (V^σ). V_κ^σ is the class V_κ with the signs of β and γ flipped by σ. Defined in the H.17 preamble; the sign-variant lemma is H.17.3. Paper's own term.
- **Statistics span** (S). For a family of pure processes, the linear space spanned by integer vectors (o-pattern) ⊗ (i-pattern) that contains every statistic p(i|o) of the family, for every source and every frame. It is computed from the expansion p(i|o) = Σ conj(ψ_z)ψ_{z′} χ_{zz′}(o) Π_k (frame factors), using two facts: an off-diagonal frame factor has no constant part, and torus characters are linearly independent. If a facet holds on Valid ∩ S, it holds on the whole family. It has dimension 20–24 on non-Lugano families and 38 (the full space) on Lugano-type families. Defined in Lemma H.30.1. Paper's own term. See also *Lugano-type family*.
- **Single-use realisation.** A fine-grained realisation in which each agent's operation is applied once, at one active slot, at the time-local level. Lemma H.15.7a and the QC-QC theorem [51] show such realisations give causal correlations (H.15.7, H.15.7b). *Usage note:* H.18.4 is not single-use: one agent acts twice at the time-local level.
- **Slice** (bipartite slice W_h). For a three-party classical process p and a deterministic local function h of one agent, the bipartite process of the other two obtained by closing that agent's loop with h. It is valid, hence causally separable (OCB [CITED]). Defined in H.22.3.
- **Source state** (φ or ψ). The fixed state on P fed into a purification or Switchboard. p_φ is the classical process a Switchboard induces with source φ (H.8). The H.13.2 counterexample works for an explicit φ.
- **Stabiliser reduction; Stab(K).** Stab(K) is the subgroup of G_{48} that maps a Klein group K onto itself; it permutes the six classes of the Klein cluster. A search over class subsets of the cluster may keep one subset per Stab(K)-orbit, the lexicographically smallest (the *canonical subset*), because these symmetries preserve admissibility and the leaf test (the H.17.15(d) argument). For k = 5 this gives 104 blocks over the 21 K-orbits. Defined in H.17.16b; audited in H.17.16c. Standard technique.

- **Stinespring dilation.** Every CPTP map is the reduction of an isometry, $A(\rho) = \mathrm{Tr}_E[V\rho V\dagger]$ [47]. Used in Appendix A Step 2 to replace local CPTP maps by unitaries with ancillas.
- **Streamed job generation** (tclose56.py). Producing the jobs of an exact search one at a time with a backtracking loop, which assigns one pair support at a time, prunes by Lemmas A and C as soon as they apply, and sends each finished assignment straight to the workers, instead of building the whole job list in memory. Defined in H.17.16b, where it made the k = 5 Klein-cluster search fit in memory. Its job counts agree with an eager itertools.product recount on all 104 k = 5 blocks (H.17.16c). Standard technique.
- **Switchboard** (family C). The purification $V|o, s, t\rangle = \Sigma_e\, C_o[e, s]\, |e\rangle_I\, |o\rangle_F\, |e \oplus t\rangle_F$: the output o selects a unitary C_o (the board) that maps the source to the parties' inputs, and F keeps copies of o and of $e \oplus t$. Defined in H.7 (family C), H.8. "The Switchboard" also names the H.12 counterexample machine. *Usage note:* paper's own name. Up to Hadamards, X-flips and unitaries on P and F, the H.13.2 board is the time-reversed Lugano process of [38] (H.15.8). See also *Board*; *Generalized switchboard*.
- **TDS; time-delocalised subsystem; realisation on TDS; time-local instance; temporal circuit.**
  - A *time-delocalised subsystem* is a subsystem of a composite of systems at different times in a fixed-order circuit, the *temporal circuit* (Oreshkov [40]).
  - A process is *realised on TDS* if its parties act on such subsystems.
  - A *time-local system* is one wire of a temporal circuit between two gates. A *time-local instance* of an agent's operation is one occurrence of it at that level: in the H.18.4 circuit, party C has two time-local instances.
  - Wechs, Branciard and Oreshkov [41] give such a realisation for the Baumeler–Wolf unitary extension of the Lugano process.
  - Defined in H.18.1. CITED.
- **Term** (≤3-term; "four terms per outcome"). The number of terms of a board U_o is the size of its Pauli support. For X-type boards it is the number of X-strings in U_{oW} for the common W of H.14.1. A ≤3-term board has $U_o = P_oV_\kappa(o)\hat{}\sigma$ with V_κ one of 1, $\alpha + i\beta A$, $\alpha + i(\beta A + \gamma B)$. The open question "is four terms per outcome the minimum?" asks whether every admissible ≤3-term board is a PF blend. Defined in H.14.1, H.17 preamble. Paper's own usage.
- **Time-reversed Lugano process** ($|w_r\rangle$; L^T). The pure process obtained by reversing the time direction of the Lugano process (swapping inputs with outputs and P with F), described by Guérin and Brukner [38]. Up to local Hadamards, X-flips and unitaries on P and F, it is the H.13.2 board (H.15.7e.2, H.15.8; Section 0, novelty notes).
- **Time-reversed PF lift.** The time reverse V^T of a forward PF lift: the agents read the old output wires in local frames and write on the old node wires, and the source sits on the old future. Its statistics are a Schur-product (dephasing) channel chosen by the outputs, applied to a shared three-qubit state, followed by fixed local measurements. Valid by Guérin–Brukner time reversal [CITED]. The H.27.2 search over this family found no crossing of the ten open orbits. Completed on all 20 refined PFs in Round 21, it crossed orbit 26, and its phase-board subfamily crosses orbits 26, 30 and 31 (H.28.1). Its statistics depend only on unit-diagonal correlation matrices $K_k(o)$, and a facet's minimum is attained at extreme points: phase boards, or rank 2 for four-block parties (Lemma H.29.2a). Defined in H.27.2. Paper's own term.
- **Tuned** (tuned classes, tuned parameters, tuned board). Two ≤3-term classes form a *tuned pair* if they are equal or their Klein groups share a non-identity element. Only then can $V'V\dagger$ have a smaller support than the generic product (H.17.12, H.17.15(a)). A *tuned board* has parameters where such cancellations occur (H.17.10). *Usage note:* not the *fine-tuned* of [15]. See also *Generic*.

- **Two-term board.** A flip-superposing board $U_o = \cos t\, X^{w1(o)} + i \sin t\, X^{w2(o)}$ $(0 < t < \pi/2)$, which superposes two flip patterns w1, w2. Admissibility forces w1 and w2 to be PFs. Defined in H.10.4 (structure proved, hull numerical for all 237 symmetry classes); every two-term board is a PF blend by the coset-transport theorem (H.10.6). Paper's own term.
- **Uniformly approximable (measurable process function).** A process function on Euclidean output spaces that is a uniform limit of countably controlled process functions, for example one whose translation amounts depend uniformly continuously on the outputs inside fixed Lugano cells. Its closed loop with arbitrary local unitaries is the strong limit of the countably controlled closed loops and is a canonical isometry (F.5.11, Round 17); whether it is always unitary is open. Paper's own term. See also *Countably controlled*.
- **Unitary extension; unitarily extendible.** A unitary extension of a process is a pure process with a global past P and future F that reduces to it when P is fed a fixed state and F is discarded (H.18.1, after [17]). Every pure board of the paper is its own unitary extension. The term "unitarily extendible" is used in [27, 36, 41]. *Usage note:* for classical processes it coincides with *Purifiable*.
- **Unitary lift; permutation lift** $(U|o, e\rangle = |w(o) \oplus e, o\rangle)$. The unitary process obtained from a PF w by this permutation of basis states (Section 1). It is the paper's main construction: every process function lifts to a pure process (Section 1, Appendix A; countable alphabets in Appendix F). Sources: the classical reversible extension is in [16]; the purification of PF blends was asserted in [27]; the lift for all PFs was conjectured in [24, Conj. VII.1] (see Section 0, novelty notes). See also *Reversible extension*.
- **Valid (polytope); Baumeler–Wolf polytope** (Valid). The set of valid classical processes for given alphabets. For three binary parties it has affine dimension 37, cut out by 72 validity equalities of rank 27, with 710,760 vertices (744 deterministic, the PFs) and 64 facets. Defined in H.13, H.17.5, H.15.1. Source: [15]. Lean: `Valid`, finite-dimensional (H.12.3). See also *Classical process*; *PF hull*.
- **Valid (process).** A process matrix is valid if G_A is CPTP for all local CPTP maps with ancillas (Appendix A). Source: [14, 17]. Lean: `PFUL.Validity`.
- **Vertex orbit.** An orbit of vertices of Valid under party permutations and local relabellings. Random LP vertices of the three-party binary polytope give 646 non-deterministic vertices in 51 orbits (C.3). Orbits 7 and 50 are certified non-purifiable (C.2); orbit 8 is probed in H.2, C.5 and C.6. *Usage note:* numbered independently of the facet orbits. See also *Orbit*.
- **VOKB** → *Routed graph*.
- **X-type board** (X-type k-term). A board is X-type k-term if there is a common unitary W such that every U_{oW} is a combination of at most k X-strings X^a. W only moves the source, $\varphi \mapsto W\dagger\varphi$. Theorem H.14.1: X-type boards with $k \le 3$ are PF blends. The H.13.2 counterexample is X-type with four terms. Defined in H.14.1. Paper's own term.
- **XOR board.** A classical reversible board $|s\rangle_P|o\rangle_{AO} \mapsto |s \oplus f(o)\rangle_{AI}|o\rangle_F$ with f_k a function of o_{-k}. Valid exactly when f is a PF; up to Pauli-X frames and party relabelling every non-causal one is the Lugano board (Proposition H.23.1b). Paper's own term.
- **$\mathbb{Z}$_N boards** ($\mathbb{Z}$_4, $\mathbb{Z}$_8, $\mathbb{Z}$_16). X-type boards whose Hadamard-frame phases are N-th roots of unity. $\mathbb{Z}$_4 boards are surveyed exhaustively (386 symmetry classes, H.13.3), $\mathbb{Z}$_8 boards in 10,603 classes (H.14.2, J.2–J.3), and $\mathbb{Z}$_16 boards by sampling (H.17). Paper's own family.

References

1. M. Dummett, Can an effect precede its cause?, Aristotelian Society Supplementary Volume 28, 27 (1954); Bringing about the past, Philosophical Review 73, 338 (1964).

2. M. Black, Why cannot an effect precede its cause?, Analysis 16, 49 (1956).
3. D. Lewis, The paradoxes of time travel, American Philosophical Quarterly 13, 145 (1976).
4. K. Gödel, An example of a new type of cosmological solutions of Einstein's field equations of gravitation, Reviews of Modern Physics 21, 447 (1949).
5. M. S. Morris, K. S. Thorne and U. Yurtsever, Wormholes, time machines, and the weak energy condition, Physical Review Letters 61, 1446 (1988).
6. J. Friedman, M. S. Morris, I. D. Novikov, F. Echeverria, G. Klinkhammer, K. S. Thorne and U. Yurtsever, Cauchy problem in spacetimes with closed timelike curves, Physical Review D 42, 1915 (1990).
7. F. Echeverria, G. Klinkhammer and K. S. Thorne, Billiard balls in wormhole spacetimes with closed timelike curves: classical theory, Physical Review D 44, 1077 (1991).
8. A. Carlini, V. P. Frolov, M. B. Mensky, I. D. Novikov and H. H. Solodukhin, Time machines: the Principle of Self-Consistency as a consequence of the Principle of Minimal Action, International Journal of Modern Physics D 4, 557 (1995).
9. J. Earman, Bangs, Crunches, Whimpers, and Shrieks: Singularities and Acausalities in Relativistic Spacetimes, Oxford University Press (1995).
10. D. Deutsch, Quantum mechanics near closed timelike lines, Physical Review D 44, 3197 (1991).
11. S. Aaronson and J. Watrous, Closed timelike curves make quantum and classical computing equivalent, Proceedings of the Royal Society A 465, 631 (2009).
12. C. H. Bennett, D. Leung, G. Smith and J. A. Smolin, Can closed timelike curves or nonlinear quantum mechanics improve quantum state discrimination or help solve hard problems?, Physical Review Letters 103, 170502 (2009).
13. S. Lloyd et al., Closed timelike curves via postselection: theory and experimental test of consistency, Physical Review Letters 106, 040403 (2011).
14. O. Oreshkov, F. Costa and Č. Brukner, Quantum correlations with no causal order, Nature Communications 3, 1092 (2012).
15. Ä. Baumeler and S. Wolf, The space of logically consistent classical processes without causal order, New Journal of Physics 18, 013036 (2016).
16. Ä. Baumeler, F. Costa, T. C. Ralph, S. Wolf and M. Zych, Reversible time travel with freedom of choice, Classical and Quantum Gravity 36, 224002 (2019), arXiv:1703.00779.
17. M. Araújo, A. Feix, M. Navascués and Č. Brukner, A purification postulate for quantum mechanics with indefinite causal order, Quantum 1, 10 (2017).
18. A. Vanrietvelde, N. Ormrod, H. Kristjánsson and J. Barrett, Consistent circuits for indefinite causal order, arXiv:2206.10042 (2022); Quantum 9, 1923 (2025).
19. H. Price, Does time-symmetry imply retrocausality? How the quantum world says yes, Studies in History and Philosophy of Modern Physics 43, 75 (2012).
20. M. S. Leifer and M. F. Pusey, Is a time symmetric interpretation of quantum theory possible without retrocausality?, Proceedings of the Royal Society A 473, 20160607 (2017).
21. T. Maudlin, A tale of two tensors, or, how not to argue for retrocausality, preprint (2017).
22. E. Specker, Die Logik nicht gleichzeitig entscheidbarer Aussagen, Dialectica 14, 239 (1960).
23. H. Dourdent, A. Leitherer, E.-C. Boghiu, K. Simonov, R. Kunjwal and A. Acín, What makes a causal loop consistent?, arXiv:2609.39735 (2026).
24. N. Daher Ahmed and R. Kunjwal, Characterizing unitaries via quasi-process functions, arXiv:2610.00579 (2026).
25. J. Faye, Backward causation, Stanford Encyclopedia of Philosophy, substantive revision 28 October 2025.
26. L. M. Tolksdorf and R. Verch, Quantum physics, fields and closed timelike curves, Communications in Mathematical Physics 357, 319 (2018).

27. Ä. Baumeler, A. S. Gilani and J. Rashid, Unlimited non-causal correlations and their relation to non-locality, Quantum 6, 673 (2022).
28. G. Tobar and F. Costa, Reversible dynamics with closed time-like curves and freedom of choice, Classical and Quantum Gravity 37, 205011 (2020), arXiv:2001.02511.
29. H. Dourdent, K. Simonov, A. Leitherer, E.-C. Boghiu, R. Kunjwal, S. Halder, R. Augusiak and A. Acín, Paradox-free classical non-causality and unambiguous non-locality without entanglement are equivalent, arXiv:2512.23599 (2025).
30. Ä. Baumeler, Causal loops: logically consistent correlations, time travel, and computation, PhD thesis, Università della Svizzera italiana (2017).
31. V. Baumann and Č. Brukner, Appearance of causality in process matrices when performing fixed-basis measurements for two parties, Physical Review A 93, 062324 (2016).
32. V. Vilasini and R. Renner, Embedding cyclic information-theoretic structures in acyclic spacetimes: no-go results for indefinite causality, Physical Review A 110, 022227 (2024); arXiv:2203.11245.
33. V. Vilasini and R. Colbeck, A general framework for cyclic and fine-tuned causal models and their compatibility with space-time, Physical Review A 106, 032204 (2022); arXiv:2109.12128.
34. V. Vilasini and R. Colbeck, Impossibility of superluminal signalling in Minkowski space-time does not rule out causal loops, Physical Review Letters 129, 110401 (2022); arXiv:2206.12887.
35. N. Paunković and M. Vojinović, Causal orders, quantum circuits and spacetime: distinguishing between definite and superposed causal orders, Quantum 4, 275 (2020); arXiv:1905.09682.
36. R. Kunjwal and O. Oreshkov, Nonclassicality in correlations without causal order, arXiv:2307.02565 (2023; v3 2025).
37. M. Araújo, P. A. Guérin and Ä. Baumeler, Quantum computation with indefinite causal structures, Physical Review A 96, 052315 (2017); arXiv:1706.09854.
38. P. A. Guérin and Č. Brukner, Observer-dependent locality of quantum events, New Journal of Physics 20, 103031 (2018); arXiv:1805.12429.
39. V. Baumann, M. Krumm, P. A. Guérin and Č. Brukner, Noncausal Page-Wootters circuits, Physical Review Research 4, 013180 (2022); arXiv:2105.02304.
40. O. Oreshkov, Time-delocalized quantum subsystems and operations: on the existence of processes with indefinite causal structure in quantum mechanics, Quantum 3, 206 (2019); arXiv:1801.07594.
41. J. Wechs, C. Branciard and O. Oreshkov, Existence of processes violating causal inequalities on time-delocalised subsystems, Nature Communications 14, 1471 (2023); arXiv:2201.11832.
42. C. Portmann, C. Matt, U. Maurer, R. Renner and B. Tackmann, Causal boxes: quantum information-processing systems closed under composition, IEEE Transactions on Information Theory 63, 3277 (2017); arXiv:1512.02240.
43. W. Yokojima, M. T. Quintino, A. Soeda and M. Murao, Consequences of preserving reversibility in quantum superchannels, Quantum 5, 441 (2021); arXiv:2003.05682.
44. J. Wechs and O. Oreshkov, Subsystem decompositions of quantum evolutions and transformations between causal perspectives, Physical Review Letters (2025), DOI 10.1103/9mk4-8sn5; arXiv:2411.16504.
45. J. Barrett, R. Lorenz and O. Oreshkov, Cyclic quantum causal models, Nature Communications 12, 885 (2021); arXiv:2002.12157.
46. N. Ormrod, A. Vanrietvelde and J. Barrett, Causal structure in the presence of sectorial constraints, with application to the quantum switch, Quantum 7, 1028 (2023); arXiv:2204.10273.
47. W. F. Stinespring, Positive functions on C*-algebras, Proceedings of the American Mathematical Society 6, 211 (1955). [Added for the glossary, Appendix K.]
48. M.-D. Choi, Completely positive linear maps on complex matrices, Linear Algebra and its Applications 10, 285 (1975). [Added for the glossary, Appendix K.]

49. G. Chiribella, G. M. D'Ariano and P. Perinotti, Theoretical framework for quantum networks, Physical Review A 80, 022339 (2009). [Added for the glossary, Appendix K.]
50. G. Chiribella, G. M. D'Ariano, P. Perinotti and B. Valiron, Quantum computations without definite causal structure, Physical Review A 88, 022318 (2013); arXiv:0912.0195. [Added for the glossary, Appendix K.]
51. J. Wechs, H. Dourdent, A. A. Abbott and C. Branciard, Quantum circuits with classical versus quantum control of causal order, PRX Quantum 2, 030335 (2021). [Cited inline in Section 0 and H.15.7; numbered for the glossary, Appendix K.]
52. O. Oreshkov and C. Giarmatzi, Causal and causally separable processes, New Journal of Physics 18, 093020 (2016). [Cited inline in H.1; numbered for the glossary, Appendix K.]
53. A. A. Abbott, C. Giarmatzi, F. Costa and C. Branciard, Multipartite causal correlations: polytopes and inequalities, Physical Review A 94, 032131 (2016). [Added for the glossary, Appendix K.]
54. E. B. Davies and J. T. Lewis, An operational approach to quantum probability, Communications in Mathematical Physics 17, 239 (1970). [Added for the glossary, Appendix K.]
55. J. Wechs, A. A. Abbott and C. Branciard, On the definition and characterisation of multipartite causal (non)separability, New Journal of Physics 21, 013027 (2019). [Cited inline in H.1; numbered for the glossary, Appendix K.]